
CONTRACT NO. 66645

FAM. SECTION COUNTY TOTAL SHEET NO.

180 SO-8HBR LASALLE 143 56

STA. TO STA.

FED. ROAD DIST. NO. 3



GENERAL NOTES

Locate poles over bridge plers where possible.

The vibration isolation pad and leveling plate shall match the footprint of the pole base plate.

Thickness of Isolation pad and washers shall be according to the Isolation pad manufacturer's recommendations based upon pole height and loading.

Should the length of the exposed anchor bolts be too short on an existing bridge to mount the poles as shown, then the leveling plate shall be mounted directly on the concrete and leveled with stainless steel washers. Remove concrete as directed by the Engineer to fully thread the top nut.

All dimensions are in millimeters (inches) unless otherwise shown.

DATE	REVISIONS	
7/31/08	Updated	☐ POLE MOUNTED
		ON BRIDGE PARAPET
-		- ON BILLDOC FARME
	•	
	-	

LGT018A.DGN