AGGREGATE SHOULDER, TYPE B

Aggregate shoulder, Type B shall be required for all granular construction of side roads, entrances, and mailbox turnouts, whether or not portions of the surfaces thus constructed are to be covered with a bituminous surface, except where noted differently on the plans.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

Contract 68934: IL 122, intersection of IL 122 & Springfield Rd (South Quad)

The following mixture requirements are applicable for this project:

Mixture Use(s):	Surface Course 2"	HMA Base Cse 6" PG 64-22					
AC/PG:	PG 64-22						
RAP% (Max): **	15%	25%					
Design Air Voids:	4.0% @ N=50	4.0% @ N=50					
Mixture Composition: (Gradation Mixture)	IL 9.5 or 12.5	IL 19.0					
Friction Aggregate:	Mix C	N.A.					

** If the RAP option is selected, the asphalt cement grade may need to be adjusted; this will be determined by the Engineer.

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

The Contractor shall consult with the Engineer in regard to the exact length of the box/pipe culverts, storm sewers, and/or pipe drains required prior to ordering these items.

EXISTING DRAINAGE PIPES CONNECTED TO NEW STRUCTURES

In accordance with Section 602 of the Standard Specifications, the connecting of existing drain tiles, pipe culverts, or storm sewers to the proposed drainage system structures will not be paid for separately but shall be considered as included in the pay items provided.

FILE NAME =	USER NAME = lebebidism	DESIGNED ~	REVISED -		GENERAL NOTES					F.A.P	SECTION	COUNTY C	TOTAL SHEET	
D468934-sht-cover_line Diagram.dgn		DRAWN -	REVISED -	STATE OF ILLINOIS			•	THATHAT IA	VILO		705	(126)L.I	TAZEWELL	36 4
	PLOT SCALE = 50.2283 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							1001	144.076.94	CONTRACT	NO. 68934
	PLOT DATE = 1/28/2010	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED.	AID PROJECT	100 00301