	SUMMARY OF QUANTITIES			
PAY ITEM #	DESCRIPTION	UNIT	QUANTITY	SPEC PRO\
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2069	
~~~~~	LEVELING BINDER (HAND METHOD), N50	TON	14**	
	LEVELING BINDER (MACHINE METHOD), N50	TON	1107	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	393	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	478	
	TEMPORARY RAMP	SQ YD	907	
	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1448	<b></b>
	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	662**	
	DETECTABLE WARNINGS	SQ FT	153**	
	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	1541	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1982	
	SIDEWALK REMOVAL	SQ FT	490**	
	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	75	*
	CLASS C PATCHES, TYPE II, 7 INCH	SQ YD	75 58	
	CLASS C PATCHES, TYPE II, 7 INCH	<del></del>	58	
	CLASS C PATCHES, TYPE III, 7 INCH	SQ YD	56	
		SQ YD		
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	30 604	
		FOOT		
	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13071**	
	VALVE BOXES TO BE ADJUSTED FRAMES AND GRATES TO BE ADJUSTED	EACH	18	
	***************************************	EACH	15 14	
	FRAMES AND LIDS TO BE ADJUSTED	EACH		ļ
	MOBILIZATION TRAFFIC CONTROL COMPLETE	L SUM	1	*
	TRAFFIC CONTROL COMPLETE	L SUM		-
	SHORT-TERM PAVEMENT MARKING	FOOT	910	
	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	379	
Z0048665	PAINT PAVEMENT MARKING - LINE 5" RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	910 1	*
20040003	TALLIOND THO LETTLE LINDLETT HOOMANCE	L SOW	-	
	△ SPECIALTY ITEMS	<del> </del>		
	**PARTIALLY OR WHOLLY ASSUMED	<u> </u>		

CONSTRUCTION TYPE CODE: IOOO-2A

LDK 11/04/09

## GENERAL NOTES

- THE COST OF REMOVAL OF ANY EXISTING OBSTRUCTIONS WHICH INTERFERE WITH CONSTRUCTION AND ARE NOT NOTED TO BE REMOVED WILL BE CONSIDERED INCLUDED WITH THE COST OF THE CONTRACT.
- 2. WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER OR AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
- 3. THE LOCATIONS OF THOSE BURIED AND ABOVEGROUND UTILITIES SHOWN ARE APPROXIMATE, ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTION PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUCED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVEGROUND UTILITY LOCATION, IDENTIFICATION, AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REROUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVEGROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS. J.U.L.I.E. MEMBERS ACTIVE IN THE VICINITY OF THE PROJECT ARE LISTED ON THE COVER SHEET.
- 4. ANY LOOSE MATERIAL DEPOSITED IN GUTTERS OR DRAINAGE STRUCTURES SHALL BE REMOVED AT THE END OF EACH WORKING DAY. THIS WORK SHALL BE INCLUDED WITH THE COST OF THE CONTRACT.
- 5. THE CONTRACTOR SHALL TAKE RESONABLE PRECAUTIONS TO PROTECT PUBLIC AND PRIVATE PROPERTY. IF AT ANY TIME, PUBLIC OR PRIVATE PROPERTY IS DAMAGED OR DESTROYED, THE CONTRACTOR SHALL RESTORE SUCH PROPERTY TO A CONDITION EQUAL TO THAT EXISTING BEFORE SUCH DAMAGE, AT NO ADDITIONAL COST TO THE DEPARTMENT.
- 6. THE CONTRACTOR SHALL COORDINATE WITH THE UNION PACIFIC RAILROAD COMPANY TO PERFORM OPERATIONS WITHIN 25' OF THE CENTERLINE OF TRACKS DURING TIMES WHEN NO TRAINS ARE SCHEDULED. THE CONTRACTOR SHALL NOTIFY THE UNION PACIFIC RAILROAD COMPANY AT THE CONTACT INFORMATION SHOWN BELOW AT LEAST 7 DAYS IN ADVANCE OF ANY CONSTRUCTION ACTIVITIES.

PAUL GEGG MANAGER OF TRACK MAINTENANCE UNION PACIFIC RAILROAD COMPANY 811 WEST CHESTNUT BLOOMINGTON, IL 61701 PHONE: (402) 501-3734 FAX: (309) 828-2481

0010077\CADD\BOAD\SHFET\C=002IDX

Registration No. 184-001084 Copyright Hanson Professional Services Inc. 2010	HANSON NO. 09L0077	DATE	~	2/01/2010	REVISED	
Hanson Professional Services Inc. 1525 South Sixth Street, Springfield, IL 62703		CHECKED		LDK 10/20/09	REVISED	
HANSON		DRAWN	_	BJB 9/4/09	REVISED	-
MILIANGONI		DESIGNED	_	BJB 9/4/09	REVISED	_

STATE OF ILLINOIS				
DEPARTMENT OF TRANSPORTATION				

UMMARY OF QUANTITIES & GENERAL NOTES	F.A.U. RTE.	SECTION
CITY OF LINCOLN LOGAN COUNTY, ILLINOIS	7718	09-00094-00-RS
ECOAN COOM I, ILLINOID		
PAGE 1 OF 1 STA. TO STA.	FFD 4	IOAO: DIST. NO

 COUNTY
 TOTAL SHEETS NO.

 LOGAN
 10
 2

 CONTRACT NO.
 93526