04-23-2021 LETTING ITEM 024

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

 FA. RTE.
 SECTION
 COUNTY
 TOTAL SHEET SHOOT.
 SHEET SHOOT.

 18
 (105VB-3) BJR
 CARROLL
 22
 1


FOR INDEX OF SHEETS, SEE SHEET NO. 2

PROPOSED HIGHWAY PLANS

F.A.P. ROUTE 308 (IL 84) SECTION (105VB-3)BJR

BRIDGE REPAIRS CARROLL COUNTY

C-92-009-21



50' 100' 1"= 50' 100' 1"= 50' 100' 1"= 30' 100' 1"= 20'


FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS
1–800–892–0123
OR 811

PROJECT ENGINEER SCOTT WYATT, PE, SE PROJECT MANAGER MAHMOUD ETEMADI, PE

GROSS LENGTH = 292.38 FT. = 0.053 MILE NET LENGTH = 292.38 FT. = 0.053 MILE

CONTRACT NO. 64P66





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

SHEET INDEX COVER GENERAL NOTES/ CONSTRUCTION SEQUENCE SUMMARY OF QUANTITIES PAVEMENT MARKING SCHEDULE STAGING TYPICAL SECTION

MAINTENANCE OF TRAFFIC PLAN STAGE I

MAINTENANCE OF TRAFFIC PLAN STAGE II US 52 MAINTENANCE OF TRAFFIC PLAN TEMPORARY TRAFFIC SIGNAL PLAN

10. PERMANENT STRIPING PLAN

11. GENERAL PLAN AND ELEVATION

CROSS SECTION AND STAGE CONSTRUCTION DETAILS 12.

13. S. ABUTMENT JOINT REPLACEMENT DETAILS

14. N. ABUTMENT JOINT REPLACEMENT DETAILS JOINT REPLACEMENT DETAILS

15. REPAIR-B DETAILS 16-17.

18-20. PREFORMED JOINT STRIP SEAL

21. BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS

INFORMATIONAL PAGE, EXISTING PLAN SHEET 22.

STATE STANDARDS

000001-08 ABBREVIATIONS, SYMBOLS AND PATTERNS OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE 701006-05 701201-05 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS 701301-04 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS-DAY ONLY LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER 701321-18 701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED 701801-06 SIDEWALK, CORNER OF CROSSWALK CLOSURE 701901-08 TRAFFIC CONTROL DEVICES 704001-08 TEMPORARY CONCRETE BARRIER 782006-01 GUARDRAIL AND BARRIER WALL REFLECTOR MOUNTING DETAILS 862001-01 UNINTERRUPTABLE POWER SUPPLY (UPS) TRAFFIC SIGNAL MOUNTING DETAILS 880006-01 886001-01 DETECTOR LOOP INSTALLATIONS TYPICAL LAYOUTS FOR DETECTOR LOOPS 886006-01

SUGGESTED MAINTENANCE OF TRAFFIC SEQUENCING

PRESTAGE

INSTALL CONSTRUCTION TRAFFIC CONTROL SIGNS AND BARRICADES.LOCATIONS DO NOT CHANGE DURING STAGE I OR II UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

INSTALL BOWEN STREET CLOSURE UPON CITY OF SAVANNA APPROVAL AS DIRECTED BY THE ENGINEER. INSTALLATION LOCATION DOES NOT CHANGE DURING STAGE I OR II UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

INSTALL TEMPORARY TRAFFIC SIGNALS AND DETECTION SYSTEM. ATTACH INTERCONNECT CABLE AND SERVICE DROP TO EXISTING ADJACENT UTILITY POLES. CONTRACTOR TO MAKE REQUIRED PERMITING AND ARRANGEMENTS WITH IDOT AND UTILITY COMPANIES. LOCATIONS DO NOT CHANGE DURING STAGE I OR II UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

REMOVE EXISTING PAVEMENT MARKINGS TO THE LIMITS SHOWN IN THE PLANS.

STAGE 1

INSTALL DRUM TAPERS, TEMPORARY CONCRETE BARRIER, AND IMPACT ATTENUATORS FOR STAGE I ROADWAY DETOUR.

INSTALL TEMPORARY PAVEMENT MARKINGS FOR STAGE 1 ROADWAY DETOUR.

INSTALL ACCESS RAMPS FOR THE SIDEWALK DETOUR IN ACCORDANCE WITH THE PLAN

INSTALL DETECTABLE PEDESTRIAN CHANNELIZING BARRICADE FOR THE SIDEWALK DETOUR PARALLEL TO, AND OFFSET 4'LEFT FROM THE STAGE I ROADWAY DETOUR TEMPORARY CONCRETE BARRIER.

MOVE DETECTABLE PEDESTRIAN CHANNELIZING BARRICADE TO THE TOP OF THE STRUCTURE CURB AND RELOCATE PEDESTRIAN TRAFFIC BACK TO THE STRUCTURE SIDEWALK ONCE WORK IS COMPLETE IN THE CURB AND SIDEWALK AREA.

STAGE 2

REMOVE ALL PEDESTRIAN CHANNELIZING BARRICADES AND ACCESS RAMPS USED FOR

REMOVE STAGE 1 ROADWAY DETOUR TEMPORARY PAVEMENT MARKING.

MOVE DRUM TAPERS, TEMPORARY CONCRETE BARRIER, AND IMPACT ATTENUATORS TO STAGE II ROADWAY DETOUR LOCATION.

INSTALL TEMPORARY PAVEMENT MARKINGS FOR STAGE 2 ROADWAY DETOUR.

POST STAGE

REMOVE ALL TEMPORARY CONCRETE BARRIERS, IMPACT ATTENUATORS, AND DRUMS.

REMOVE TEMPORARY SIGNALS, DETECTION, INTERCONNECT CABLE AND SERVICE DROP.

DESIGNED - MGB

01-11-2021

DRAWN - DWS

CHECKED -

DATE

REVISED

REVISED

REVISED

REVISED

REMOVE STAGE II ROADWAY DETOUR TEMPORARY PAVEMENT MARKINGS.

INSTALL PERMANENT PAVEMENT MARKINGS.

USER NAME = scottw

PLOT DATE = 03/09/2021

REMOVE ALL REMAINING CONSTRUCTION SIGNS AND BARRICADES.

MAINTENANCE OF TRAFFIC GENERAL NOTES

- THE MAINTENANCE OF TRAFFIC CONTROL (MOT) PLANS SHALL SERVE AS A GUIDE FOR SAFE DIVERSION OF TRAFFIC DURING EXECUTION OF THIS CONTRACT. HOWEVER, THE CONTRACTOR MAY MODIFY THE MOT PLANS TO MEET CONSTRUCTION NEEDS BUT NOT AT THE EXPENSE OF PUBLIC SAFETY OR CONVENIENCE. ANY CHANGES TO THE MOT PLANS
- 2. THE ENGINEER SHALL BE INFORMED 48 HOURS IN ADVANCE OF ANY CHANGE TO THE
- 3. ALL EXISTING PAVEMENT MARKINGS IN CONFLICT WITH THE MAINTENANCE OF TRAFFIC STRIPING SHALL BE REMOVED TO THE LIMITS SHOWN IN THE PLANS.
- 4. ALL TEMPORARY PAVEMENT MARKING WHICH CONFLICTS WITH THE NEXT STAGE OR FINAL STRIPING SHALL BE REMOVED TO THE LIMITS SHOWN IN THE PLANS AND IN THE SCHEDULE OF PAVEMENT MARKING.
- 5. ALL TRAFFIC CONTROL DEVICES USED FOR THE MAINTENANCE OF TRAFFIC, AS DETAILED ON THE PLANS, OR HIGHWAY STANDARD SHALL BE REFLECTORIZED PRIOR TO INSTALLATION AND CLEANED AS SPECIFIED IN MAINTENANCE OF TRAFFIC SPECIAL PROVISIONS OR AS DIRECTED BY THE ENGINEER.
- 6. ALL DRUMS, VERTICAL PANELS AND BARRICADES ADJACENT TO THE EDGE OF TRAVELED WAY SHALL BE EQUIPPED WITH BI-DIRECTIONAL STEADY-BURNING LIGHTS.
- ALL EXISTING SIGNS WITHIN MAINTENANCE OF TRAFFIC LIMITS WHICH ARE OBSCURED BY OR INTERFERE WITH CONSTRUCTION OPERATIONS AND MAINTENANCE OF TRAFFIC, SHALL BE COVERED OR REMOVED BY THE CONTRACTOR UNLESS SPECIFIED IN THE PLANS OR WHEN DIRECTED BY THE ENGINEER. THIS WORK SHALL BE IN ACCORDANCE WITH ARTICLE 107.25 OF THE IDOT STANDARD SPECIFICATIONS.
- 8. ORIGINAL STRUCTURE AND SECTION NUMBERS ARE INDICATED IN THE MOT PLANS AS AN ADDITIONAL INFORMATION SOURCE IF NEEDED.
- 9. THE CONTRACTOR SHALL CONTACT THE IDOT DISTRICT 2 ENGINEER AT (815)284-2271 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

PAY ITEMS FOR MAINTENANCE OF TRAFFIC WORK

ITEM "TRAFFIC CONTROL AND PROTECTION, STANDARD 701201" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY TO WARN AND CONTROL TRAFFIC IN ACCORDANCE WITH IDOT STANDARD 701201 DURING INSTALLATION, IMPLEMENTATION AND REMOVAL OF TRAFFIC SIGNALS, TEMPORARY CONCRETE BARRIERS, AND

ITEM "TRAFFIC CONTROL AND PROTECTION, STANDARD 701321" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY FOR THE INSTALLATION, MAINTENANCE AND ULTIMATE REMOVAL OF SIGNS, DRUMS, LIGHTS, PANELS, AND REFLECTORS NECESSARY FOR STAGED WORKZONE PROTECTION AS SPECIFIED IN THE PLANS AND

ITEM "TRAFFIC CONTROL AND PROTECTION, STANDARD 701501" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY FOR THE INSTALLATION, MAINTENANCE AND ULTIMATE REMOVAL OF SIGNS, AND PANELS NECESSARY FOR THE BRANDON ROAD CLOSURE AS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEM "TRAFFIC CONTROL AND PROTECTION, STANDARD 701801" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY FOR THE INSTALLATION, RELOCATION, MAINTENANCE AND ULTIMATE REMOVAL OF SIGNS, PANELS AND TEMPORARY ACCESS RAMPS NECESSARY FOR THE STAGE I SIDEWALK AND PEDESTRIAN DETOURS, INCLUDING FLAGGING, AS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEMS "TEMPORARY CONCRETE BARRIER" AND "RESET TEMPORARY CONCRETE BARRIER" ARE INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY FOR STAGE I AND BRANDON ROAD CLOSURE INSTALLATION, STAGE II RELOCATION, MAINTENANCE AND ULTIMATE REMOVAL OF TEMPORARY CONCRETE BARRIER TO THE LIMITS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEMS "IMPACT ATTENUATORS, TEMPORARY" AND "IMPACT ATTENUATORS, RELOCATE" ARE INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY FOR STAGE I INSTALLATION, STAGE II RELOCATION, MAINTENANCE AND ULTIMATE REMOVAL OF TEMPORARY IMPACT ATTENUATORS OF THE TYPE, AND TO THE LIMITS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEM "PAVEMENT MARKING TAPE" IS INTENDED FOR THE MATERIAL. EQUIPMENT AND LABOR NECESSARY TO PLACE AND MAINTAIN TEMPORARY PAVEMENT, MARKING TAPE OF THE TYPE, SIZE AND LIMITS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEM "PAVEMENT MARKING TAPE" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY TO PLACE AND MAINTAIN TEMPORARY PAVEMENT MARKING TAPE OF THE TYPE, SIZE AND LIMITS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEM "TEMPORARY PAVEMENT MARKING REMOVAL" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY TO REMOVE TEMPORARY TAPE TO THE LIMITS

ITEM "PAINT PAVEMENT MARKING LINE, 4" IS INTENDED FOR THE MATERIAL, EQUIPMENT AND LABOR NECESSARY TO PLACE PERMANENT 4" PAVEMENT MARKING OF THE TYPE AND TO THE LIMITS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

ITEM "TEMPORARY BRIDGE TRAFFIC INSTALLATION" IS INTENDED FOR THE PERMITTING, MATERIAL, EQUIPMENT AND LABOR NECESSARY TO INSTALL, OPERATE, MAINTAIN AND ULTIMATELY REMOVE A COMPLETE TEMPORARY TRAFFIC SIGNAL SYSTEM INCLUDING DETECTION AS SPECIFIED IN THE PLANS AND SPECIFICATIONS.

SCALE:

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

SECTION COUNTY IL 84, SAVANNA, IL 308 (105VB-3)BJR CARROLL 22 2 GENERAL NOTES / CONSTRUCTION SEQUENCE CONTRACT NO. 64P66 OF 10 SHEETS STA. ILLINOIS FED. AID PROJECT

0047 **100% STATE**

0047 **100% STATE**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
42001300	PROTECTIVE COAT	SQ YD	70
50102400	CONCRETE REMOVAL	CU YD	15.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.3
50301350	CONCRETE SUPERSTRUCTURE APPROACH SLAB	CU YD	18.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5880
5080 0515	BAR SPLICERS	EACH	16
52000110	PREFORMED JOINT STRIP SEAL	FOOT	84
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1
7010704	PAVEMENT MARKING BLACKOUT TAPE, 4"	FOOT	3, 049
70300904	PAVEMENT MARKING TAPE, TYPE IV, 4"	FOOT	2,675

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70300924	PAVEMENT MARKING TAPE TYPE IV, 24"	F00T	24
70400100	TEMPORARY CONCRETE BARRIER	FOOT	338
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	338
70600251	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
70600352	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
78001110	PAINT PAVEMENT MARKING LINE 4"	FOOT	1, 759
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	1,526
Z0004552	APPROACH SLAB REMOVAL	CU YD	43.3
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	20

*= SPECIALTY ITEM

G	USER NAME = scottw	DESIGNED	-	MGB	REVISED	-
		DRAWN	-	DWS	REVISED	=
	PLOT SCALE = 2.0000 '/in.	CHECKED	-		REVISED	=
	PLOT DATE = 02/15/2021	DATE	-	01-11-2021	REVISED	-

COUNTY TOTAL SHEET NO.

CARROLL 17 3

				Stag	e 1					
	STAT	ION			TEMP	ORARY TAPI	E (LF)	REMOVAL (SF)	PERMANEN	STRIPE (LF)
Line	From	To	Description	Location	4" Blackout	4" White	24" White	Temp Mark	4" Yellow	4" White
1	29+71	32+00	Blackout Existing Solid Line Y	Centerline	458					
2	32+00	36+20	Blackout Existing Skip Dash Y	Centerline	105					
3	30+09	35+60	Blackout Existing Solid Line W	Right Edgeline	551					
4	29+15	35+60	Blackout Existing Solid Line W	Left Edgeline	645					
5	28+20	35+60	Temporary Line White	Rt Stage I Detour Edgeline		740				
6	29+15	35+60	Temporary Line White	Lt Stage I Detour Edgeline		645				
7	29+	-20	Temporary Stop Bar	N End Stage I Detour			12			
8	36+	-20	Temporary Stop Bar	S Fnd Stage I Detour			12			
				Stag	e 2					
9	29+15	35+60	Temp Line Blackout 4"	Rt Stage Detour Edgeline	645					
10	29+15	35+60	Temp Line Blackout 4"	Lt Stage 1 Detour Edgeline	645					
11	29+15	35+60	Temporary Line White	Rt Stage II Detour Edgeline		645				
12	29+15	35+60	Temporary Line White	Lt Stage II Detour Edgeline		645				
				Post S	tage					
13	29+	-20	Remove Temporary Stop Bar	N End Stage II Detour				24.0		
14	36+	-20	Remove Temporary Stop Bar	S End Stage II Detour		<u> </u>		24.0		
15	28+20	35+60	Remove Temp Line White	Rt Stage II Detour Edgeline				246.7		
16	29+15	35+60	Remove Temp Line White	Lt Stage II Detour Edgeline				215.0		
17	29+15	35+60	Remove Temp Line Blackout 4"	Rt Stage Detour Edgeline				215.0		
18	29+15	35+60	Remove Temp Line Blackout 4"	Lt Stage 1 Detour Edgeline				215.0		
19	29+71	32+00	Perm Solid Line Yellow	Centerline				152.7	458	
20	32+00	36+20	Perm Skip Dash Yellow	Centerline		•		35.0	105	
21	30+09	35+60	Perm Solid Line White	Right Edgeline			•	183.7		551
22	29+15	35+60	Perm Solid Line White	Left Edgeline				215.0		645
				TOTAL	3049	2675	24	1526.0	563	1196


						Stage	I							
	STAT	ION			Begin Point		Breakpoint 1		Breakpoint 2		Breakpoint 3		End Point	
Line	From	To	Description	Location	Station	Offset	Station	Offset	Station	Offset	Station	Offset	Station	Offset
5	28+20	35+60	Temporary Line White	Rt Stage Detour Edgeline	28+20	22.0' rt	29+00	13.9' rt	33+90	13.9' rt	34+10	12.0' rt	35+60	12.0' rt
6	29+15	35+60	Temporary Line White	Lt Stage I Detour Edgeline	29+15	24.0' lt	30+15	0.0' It	30+75	3.9' rt	33+90	3.9' rt	35+60	12.0' lt
	30+45	34+80	Temp Concrete Barrier	Stage I Detour	30+45	4.0' It	30+75	2.9' rt	33+40	2.9' rt			33+80	4.0' lt
	30+63	33+50	Ped Channelizing Barricade	Stage IA Pedestrian Detour	30+63	20'-11' lt	30+75	2.9' lt	33+40	2.9' lt	33+40	2.9' lt	33+50	11'-20' lt
	30+63	33+50	Ped Channelizing Barricade	Stage IB Pedestrian Detour	30+63	16' lt							33+50	16' lt
						Stage I	I							
11	29+15	35+60	Temporary Line White	Rt Stage II Detour Edgeline	29+15	12.0' rt	30+15	0.0' rt	30+75	3.9' It	33+90	3.9' lt	35+60	12.0' rt
12	29+15	35+60	Temporary Line White	Lt Stage II Detour Edgeline	29+15	25.5' lt	30+00	13.9' lt	33+90	13.9' lt	33+90	13.9' lt	35+60	12.0' lt
	30+45	34+80	Temp Concrete Barrier	Stage II Detour	30+45	4.0' rt	30+75	2.8' It	33+40	2.8' It			33+80	4.0' rt
						Post Sta	ge							
19	29+71	32+00	Perm Solid Line Yellow	Centerline	29+71	0.0'							32+00	0.0'
20	32+00	36+20	Perm Skip Dash Yellow	Centerline	32+00	0.0'							36+20	0.0'
21	30+09	35+60	Perm Solid Line White	Right Edgeline	30+09	12.0' rt							35+60	12.0' rt
22	28+28	35+60	Perm Solid Line White	Left Edgeline	29+15	24.0' lt	30+00	12.0' lt					35+60	12.0' lt


SCALE: NONE


THE OF TH


USER NAME = scottw	DESIGNED - MGB	REVISED -
	DRAWN - DWS	REVISED -
PLOT SCALE = 2.0000'/in.	CHECKED -	REVISED -
PLOT DATE = 03/09/2021	DATE - 01-11-2021	REVISED -


	IL 84,	IA, IL	F.A.P. RTE	SEC	TION		COUNTY	TOTAL SHEETS	SHEET NO.		
PAVEMENT MARKING SCHEDULE						(105VB	(105VB-3)BJR			22	4
. ,,,,,		***************************************	COMEDCE					CONTRACT	NO. 641	- 66	
SHEET 3	OF 10	SHEETS	STA.	TO STA.			ILLINOIS	FED. All	D PROJECT		












NOTES FOR TEMPORARY TRAFFIC SIGNALS

- 1. ALL CONTROL EQUIPMENT FOR THE TEMPORARY TRAFFIC SIGNALS SHALL BE FURNISHED BY THE CONTRACTOR.
- 2. ONLY CONTROLLERS SUPPLIED BY ONE OF THE IDOT APPROVED CLOSED LOOP EQUIPMENT MANUFACTURERS WILL BE APPROVED FOR USE AT TEMPORARY SIGNAL LOCATIONS. ALL CONTROLLERS USED FOR TEMPORARY TRAFFIC SIGNALS SHALL BE FULLY ACTIVATED NEMA MICROPROCESSOR BASED WITH RS232 DATA ENTRY PORTS COMPATIBLE WITH EXISTING MONITORING SOFTWARE APPROVED BY IDOT, INSTALLED IN A NEMA TS2 CABINET. ONLY ONE BRAND OF CONTROLLER WILL BE ACCEPTED FOR ANY ONE CONTRACT.
- 3. ALL TRAFFIC SIGNAL SECTIONS SHALL BE LED AND 12" DIAMETER. HEADS SHALL BE BRACKET MOUNTED ON TEMPORARY WOODEN POLES IN ACCORDANCE WITH IDOT STANDARD 880006-01 AND AS INDICATED ON THE TEMPORARY SIGNAL PLAN OR AS DIRECTED BY THE ENGINEER. EACH TEMPORARY TRAFFIC SIGNAL HEAD SHALL HAVE ITS OWN CABLE FROM THE CONTROLLER CABINET TO THE SIGNAL HEAD.
- 4. THE CONTRACTOR SHALL VERIFY CLEARANCE REQUIREMENTS WITH UTILITY COMPANIES AND CONTACT JULIE PRIOR TO INSTALLATION OF TEMPORARY WOODEN POLES. ANY REQUIRED MODIFICATIONS OR ADJUSTMENTS TO HEIGHT OR LOCATION MUST BE APPROVED BY THE ENGINEER.
- 5. TEMPORARY SIGNALS SHALL BE POWERED AND INTERCONNECTED IN A MANNER APPROVED BY IDOT DISTRICT 2, AND SHALL INCLUDE AN UNINTERRUPTABLE POWER SUPPLY IN ACCORDANCE WITH IDOT STANDARD 862001. ELECTRIC UTILITY SERVICE DROP LOCATION AND THE AERIAL INTERCONNECT CABLE ROUTING ALONG EXISTING UTILITY POLES SHOWN IN PLANS IS SUGGESTED. ULTIMATE SERVICE DROP LOCATION AND INTERCONNECT CABLE ROUTING, INCLUDING ALL REQUIRED PERMITTING AND OTHER ARRANGEMENTS NEEDED WITH IDOT AND UTILITY COMPANIES, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 6. TRAFFIC SIGNAL MANAGEMENT SYSTEMS AND REQUIRED EQUIPMENT SHALL BE PLACED AND MAINTAINED IN OPERATION AS INDICATED ON THE PLANS AND TO THE SATISFACTION OF THE ENGINEER.
- 7. THE TEMPORARY TRAFFIC SIGNAL DETECTION SYSTEM SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH IDOT STANDARDS 701321, 886001 AND 886006, AND TO THE SATISFACTION OF THE ENGINEER.
- COST FOR ALL PERMITTING, INSTALLATION, POWER, AND MAINTENANCE FOR TEMPORARY TRAFFIC SIGNALS SHALL BE INCLUDED IN ITEM "TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION".



STAGE I & II TRAFFIC SIGNAL SEQUENCE												
PHASE		Α		В								
INTERVAL	1	2	3	4	5	6	7					
TIME (SEC)	40	5	15	20	5	15	REST					
1	G	Y	R	R	R	R	G					
2	R	R	R	G	Υ	R	R					

SYMBOL LEGEND

EXISTING UTILITY POLE

3-1/C NO2 AERIAL CABLE ALUMINUM WITH
MESSENGER WIRE
GROUND ROD 5%" DIA X 10'

BRACKET MOUNTED SIGNAL HEAD
TEMPORARY WOOD POLE NOMINAL 40 FT., CLASS 4

TEMPORARY TRAFFIC CONTROLLER WITH UPS AND BOTTOM
PLATE MOUNTED TO WOOD POLE
SINGLE ENTRY PHASE

CONTACT INFORMATION

IDOT DISTRICT 2 - (815) 284-2271

ELECTRICITY PROVIDER & WEST UTILITY POLE LINE JO-CARROLL ENERGY - Brandon Byer (815) 858-5746

EAST UTILITY POLE LINE MEDIACOM - Chris Minard (815) 597-5103

SCHEDULE OF QUANTITIES

 OUANTITY
 UNIT
 ITEM

 1
 EACH
 TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION


Ť	
ME: C:Us	Hamilton consulting engineers, inc.
FILE NAME:	3230 Executive Drive, Joliet, Illinois 60431 Ph: (815) 730-344 Fax: (815) 730-6703 IL LICENSE NO. 184-003205 © 2020 MAMILTON CONSULTING ENGINEERS, INC.


G	USER NAME = scottw	DESIGNED	-	MGB	REVISED	-
		DRAWN	-	DWS	REVISED	-
	PLOT SCALE = 40.0000 / in.	CHECKED	-		REVISED	-
	PLOT DATE = 03/09/2021	DATE	-	01-11-2021	REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: 1"=20'

IL 84, SAVANNA, IL						F.A.P. RTE	SEC	TION		COUNTY	TOTAL SHEETS		
TEMPORARY TRAFFIC SIGNAL PLAN				308	(105VB-3)BJR			CARROLL 22		9			
TENT OTALL TRAITIO SIGNAL TEAM										CONTRACT	Γ NO. 64I	P66	
SHEET 9 C	OF 1	10	SHEETS	STA.		TO STA.			ILLINOIS	FED. A	ID PROJECT		





EXPIRES 11-30-2022

DESIGNED -	Victor H. Veliz	EXAMINED	Tring A. Alak	DATE -	MARCH 16, 2021	
CHECKED -	Jeffrey S. Burke	-	ENGINEER OF STRUCTURAL SERVICES	-		ĺ
DRAWN -	Venkat Reddy	PASSED	De Corl Projey	REVISED	-	
CHECKED -	VHV JSB] -	ENGINEER OF BRIDGES AND STRUCTURES	REVISED	_	

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL PLAN AND ELEVATION IL 84 OVER SOO LINE RR/CITY STREET SN 008-0041 SHEET NO. 1 OF 12 SHEETS

Protective Coat


* Apply to new concrete only.

Sub-Base Granular Material, Type B

F.A.P. RTE	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.
18	(105VB-3)BJR			CARROLL	22	11
			CONTRACT	NO 64F	2 66	
		II I NIOIC	EED A	D BBO IECT		

| Sq. Yd. |


70





CROSS SECTION AT ABUTMENTS

(Looking North)


DESIGNED - VHV	EXAMINED	I mot A An at	DATE - MARCH 16, 2021		CROSS SECTION & STAGE CONSTRUCTION DETAILS	F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEET NO
CHECKED - JSB	_	ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	SN 008-0041	18	(105VB-3)BJR	CARROLL	22	12
DRAWN - Venkat Reddy	PASSED _	& Carl Prayey	REVISED -	DEPARTMENT OF TRANSPORTATION				CONTRAC	CT NO. 64	4P66
CHECKED - VHV JSB		ENGINEER OF BRIDGES AND STRUCTURES	REVISED -		SHEET NO. 2 OF 12 SHEETS		ILLINOIS FE	D. AID PROJECT		







SECTION THRU WEST SIDE BRIDGE PARAPET





DESIGNED - VHV	EXAMINED	I mot A All G	DATE - MARCH 16, 2021	CTATE OF ILLINOIS	JOINT REPLACEMENT DETAILS	F.A.P. RTE	SECTION	COUNTY SH	TOTAL SHEET NO.
CHECKED - JSB		ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	SN 008-0041	18	(105VB-3)BJR	CARROLL	22 15
DRAWN - Venkat Reddy	PASSED	S. Carl Princey	REVISED -	DEPARTMENT OF TRANSPORTATION	3N 008-0041			CONTRACT N	NO. 64P66
CHECKED - VHV JSB	-	ENGINEER OF BRIDGES AND STRUCTURES	REVISED -		SHEET NO. 5 OF 12 SHEETS		ILLINOIS FED. A	AID PROJECT	

 $BAR \ d(E)$

a1(E)

d1(E)

c1(E)

h(E)

h1(E)

Bar Splicers

Concrete Removal

Reinforcement Bars, Epoxy Coated

Concrete Superstructure

BAR d1(E)

BILL OF MATERIAL (TWO ABUTMENTS)

 Size
 Length
 Shape

 #6
 23'-4"
 —

 #6
 18'-5"
 —

#4 5'-2" #5 3'-11"

#5 2'-5" #5 5'-8"

#6

#6

23'-4" 18'-5"

Cu. Yd.


Cu. Yd.


Each


Pound

16


1050








A(E) & A1(E) BARS



<u>A2(E) BAR</u>





SOUTH EAST APPROACH DAMAGE

* Epoxy grouted bars A2(E) & A4(E) and C3(E) accordance with Article 584 of the Standard Specifications.

For existing plans of approach pavement see sheet 12 of 12


Reinforcement and Concrete Superstructure (Approach Slab) are included in the Bill of Material on Sheet 6 of 12.

PARTIAL PLAN OF APPROACH SLAB

DESIGNED - VHV	EXAMINED	I mot A. All 47	DATE -	MARCH 16, 2021
CHECKED - JSB		ENGINEER OF STRUCTURAL SERVICES		
DRAWN - Venkat Reddy	PASSED	d. Carl Prayer	REVISED	-
CHECKED - VHV .ISB	1	ENGINEER OF RRIDGES AND STRUCTURES	REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

APPROACH SLAB REPAIRS		F.A.P. SECTION		COUNTY	TOTAL SHEETS	SHEET NO.	
SN 008-0041	18	3 (105VB-3)BJR			CARROLL	22	17
311 000-0041					CONTRAC	Γ NO. 64F	- 66
SHEET NO. 7 OF 12 SHEETS	THE PROOF SEED, AND DOOLSOT						



Note

The strip seal shall be made continuous and shall have a minimum thickness of V_4 ". The configuration of the strip seal shall match the configuration of the locking edge rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.

The locking edge rails depicted are configured for typical applications and are conceptual only. The actual configuration of the locking edge rails and matching strip seal may vary from manufacturer to manufacturer provided they fit the application and meet the minimum anchorage shown. Flanged edge rails, however, will not be allowed. Locking edge rails may exceed the 4½" maximum depth provided the anchorage system is revised according to the manufacturer's recommendation.

The manufacturer's recommended installation methods shall be followed.

All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.


The Maximum space between locking edge rail segments shall be $\frac{3}{16}$ " and sealed with a suitable sealant; however, any rail joint within 10' measured perpendicular to the face of the curb or parapet shall be welded as shown in the locking edge rail splice detail.

The top surface of sidewalk sliding plates shall have a raised pattern according to ASTM A786.

Cost of parapet sliding plates, sidewalk sliding plates, embedded plates, anchorage studs, and expansion anchors included with Preformed Joint Strip Seal.

 39° constant slope barrier shown, 44° constant slope barrier similar as noted.

The concrete opening below the strip seal will vary based on the locking edge rail chosen by the Contractor. Deck and parapet lengths shown elsewhere in the plans are dimensioned to the concrete opening, not the joint opening, and are based on the rolled locking edge rail. If the Contractor elects to use a different locking edge rail, dimensional adjustments may be required. One exception to this would be the strip seal joint at the end of the precast bridge approach slab. For these cases the pavement connector length shall be adjusted, not the length of the bridge approach slab.




LOCKING EDGE RAILS

<u>SHOWING WELDED RAIL JOINT</u>

** Back gouge not required if complete joint penetration is verified by mock-up.

<u>ROLLED</u>

(EXTRUDED) RAIL



LOCKING EDGE RAIL SPLICE

The inside of the locking edge rail groove shall be free of weld residue. Rolled rail shown, welded rail similar.

BILL OF MATERIAL

Item	Unit	Total
Preformed Joint Strip Seal	Foot	84

SECTION

(105VB-3)BJR

COUNTY

CARROLL 22 18

CONTRACT NO. 64P66

SECTION A-A

miss studs. All rods shall be burned, or sawed

off flush with the plates after concrete is set.

at 50° I

1-1-2020

EJ-SS-S


SHOWING ROLLED RAIL JOINT


* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.


(Sheet 1 of 3)

WELDED RAIL

DESIGNED - VHV	EXAMINED	I mot A A I Co	DATE - MARCH 16, 2021		PREFORMED JOINT STRIP SEAL - SIDEWALK
CHECKED - JSB		ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	
DRAWN - Venkat Reddy	PASSED	& Carl Prover	REVISED -	DEPARTMENT OF TRANSPORTATION	SN 008-0041
CHECKED - VHV JSB		ENGINEER OF BRIDGES AND STRUCTURES	REVISED -		SHEET NO. 8 OF 12 SHEETS









SECTION AT MEDIAN

For skews > 30°, chamfer acute corners 2" similar to sidewalk.



PLAN AT RAISED SIDEWALK




EJ-SS-S 1-1-2020

DESIGNED - VHV EXAMINED MARCH 16, 2021 CHECKED - JSB DRAWN - Venkat Reddy PASSED REVISED CHECKED - VHV


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** PREFORMED JOINT STRIP SEAL - SIDEWALK SN 008-0041 SHEET NO. 9 OF 12 SHEETS

COUNTY TOTAL SHEETS NO.

CARROLL 22 19 SECTION (105VB-3)BJR CONTRACT NO. 64P66



DESIGNED - VHV EXAMINED MARCH 16, 2021 PREFORMED JOINT STRIP SEAL - SIDEWALK SECTION COUNTY STATE OF ILLINOIS CHECKED - JSB (105VB-3)BJR CARROLL 22 20 18 SN 008-0041 **DEPARTMENT OF TRANSPORTATION** DRAWN - Venkat Reddy PASSED REVISED CONTRACT NO. 64P66 CHECKED - VHV SHEET NO. 10 OF 12 SHEETS




STANDARD BAR SPLICER ASSEMBLY PLAN

(All components shall be provided from one supplier)

Threaded splicer bar length = min. lap length + $1\frac{1}{2}$ " + thread length

* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.


Location	Bar	No. assemblies	Minimum
Eocation	size	required	lap length
Deck	#6	8	3'-6"
Abutment	#6	8	3'-6"



INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt "B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E) : Indicates epoxy coating.



STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required

Notes:

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements

for reinforcement bars. See Section 508 of the Standard Specifications. See approved list of bar splicer assemblies and mechanical splicers for alternatives.

BSD-1

1-1-2020

DESIGNED - VHV	EXAMINED	I mote of A a	DATE -	MARCH 16, 2021
CHECKED - JSB		ENGINEER OF STRUCTURAL SERVICES		
DRAWN - Venkat Reddy	PASSED	& Carl Prayer	REVISED	-
CHECKED - VHV JSB		ENGINEER OF BRIDGES AND STRUCTURES	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

 BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
 F.A.P. RTE.
 SECTION
 COUNTY
 TOTAL SHEETS
 SHEET NO.

 SN 008 - 0041
 18
 (105VB-3)BJR
 CARROLL
 2
 21

 SHEET NO. 11 OF 12 SHEETS

