

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, COMMITMENTS, MIXTURE REQUIREMENTS
3-5	SUMMARY OF QUANTITIES
6-9	TYPICAL SECTIONS
10-11	SCHEDULE OF QUANTITIES
12-13	WIDENING PLANS
14-18	BRIDGE PLANS, SN 082-0033
19-33	BRIDGE PLANS, SN 082-0034

HIGHWAY STANDARDS

000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701423-10	LANE CLOSURE, MULTILANE, WITH BARRIER, FOR SPEEDS ≥ 45 MPH TO 55 MPH
701901-08	TRAFFIC CONTROL DEVICES
704001-08	TEMPORARY CONCRETE BARRIER
780001-05	TYPICAL PAVEMENT MARKINGS
781001-04	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKINGS
781326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH



GENERAL NOTES

- 1

ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY *. NON- J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
- 2

NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE PLANS WERE CREATED USING MICROFILM AND FIELD MEASUREMENTS.
- 3

THE PROPOSED PAVEMENT MARKING SHALL MATCH THE LOCATIONS OF THE EXISTING PAVEMENT MARKING, AS DIRECTED BY THE ENGINEER.
- 4

TWO CHANGEABLE MESSAGE SIGNS SHALL BE PLACED 14 DAYS IN ADVANCE OF CONSTRUCTION. EXACT LOCATION OF CHANGEABLE MESSAGE SIGNS SHALL BE DETERMINED BY THE ENGINEER.
- 6

THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS IN COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN METTING WORKFORCE AND TRAINEE GOALS.

COMMITMENTS

NONE

MIXTURE REQUIREMENTS

ROUTE	FAU 9166
SECTION	32-2BR-2
COUNTY	St. Clair
CONTRACT	76N39

DESCRIPTION:	Bridge Joint Repair and HMA Overlay w/ Bridge Repairs on St. Clair Ave over Harding Ditch - SN 082-0033, 0034
--------------	---

ADT (Construction Yr)	12000
MU%:	1
SU%:	3
20 YR. ESAL'S:	1.29

MIXTURE USE	POLY SURFACE	BINDER			
AC/PG	SBS PG 76-22	PG 64-22			
RAP % (MAX)	SEE SPECIAL	SEE SPECIAL			
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70			
MIX COMPOSITION (Gradation)	IL 9.5	IL 19.0			
FRICTION AGG	MIXTURE "D"	MIXTURE "B"			
QUALITY MGMT PROGRAM	QC/QA	QC/QA			

1 REVISED 4-6-2021

REV. - MS

MODEL \$MODELNAME\$
FILE NAME pw:\pwrcom\dot\illinois.gov\PHWDOT\Documents\DOT_Offices\District_8\Projects\UD76N39\CADDData\CADsheets\UD76N39-sht-typical.dgn

	USER NAME = jeffersonts	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES COMMITMENTS, MIXTURE REQUIREMENTS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - _____	REVISED - _____			9166	33-2BR-2	ST. CLAIR	33	2
	PLOT SCALE = 100.0676 ' / in.	CHECKED - _____	REVISED - _____			CONTRACT NO. 76N39				
	PLOT DATE = 1/27/2021	DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT				
	SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____									

