
F.A.P. RTE. SHEETS NO. 351 3277R COOK STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

CONTRACT NO. 60774



STONE DUMPED RIPRAP, CLASS A4 (675mm THICKNESS)

SECTION A-A

- LEVEL OF STREAM BED

FILTER FABRIC

MAXIMUM

RIPRAP, CLASS A4 -(525mm THICKNESS)

BEDDING, CLASS A1 (150mm THICKNESS)

- 4. EROSION CONTROL MEASURES WILL BE INSPECTED BY THE ENGINEER PERIODICALLY AND WITHIN 24 HOURS OF ANY STORM EXCEEDING  $\frac{1}{2}$  INCH PRECIPITATION. DAMAGED AND INEFFECTIVE EROSION CONTROL MEASURES SHALL BE REPAIRED OR REPLACED AS SOON AS POSSIBLE.
- 5. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SEDIMENT AND EROSION CONTROL MEASURES ARE OPERATIONAL.
- 6. THE COFFERDAMS SHALL NOT BE EARTHEN OR USE ANY PRACTICES THAT WOULD RESULT IN A RELEASE OF SEDIMENT INTO WATERS OF THE U.S. COFFERDAMS SHALL BE CONSTRUCTED OF NON-ERODABLE MATERIALS. ACCEPTABLE PRACTICES INCLUDE PRE-FABRICATED RIGID COFFERDAMS, SHEET PILING, INFLATABLE BLADDERS, SANDBAGS AND FABRIC-LINED BASINS.

- REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATI	
NAME	DATE		
		US	S RTE 6 FROM I-294 TO IL RTE 1
,			CONSTRUCTION AND
			EROSION CONTROL DETAILS
			W000 ST .T 0 U.D.D
			WOOD ST. AT C.U.D.D.
			DU-50 DRAWN BY MRF
		DATE	01/29/09 CHECKED BY IBB

100 S. WACKER DR., SUITE 500 CHICAGO, ILLINOIS 60606 TEL. (312) 339-1000 FAX (312) 939-4198