

SUB-BASE GRANULAR MATERIAL  
TYPE B, - 4"

LOCATION		QUANTITY
STATION	OFFSET	(SQ YD)
103+95.00 TO 105+96.39	RT	89
103+95.00 TO 107+12.93	LT	142
TOTAL		231

CONSTRUCTING TEST STRIP

LOCATION	QUANTITY
	(EACH)
JOBSITE	2
TOTAL	2

INCIDENTAL HOT-MIX  
ASPHALT SURFACING

LOCATION	QUANTITY
STATION	(TON)
TEMPORARY RAMP	30.0
TOTAL	30.0

PROTECTIVE COAT

LOCATION	QUANTITY	
	(SQ FT)	(SQ YD)
SIDEWALK		
105+77.57 TO 105+83.89 LT	44	4.9
106+24.73 TO 108+03.45 LT	897	99.6
SUBTOTAL =	x2 COATS	104.5
STATION	QUANTITY	
CURB & GUTTER	(FOOT)	(SQ YD)
103+95.00 TO 105+96.39 RT	203	78.8
103+95.00 TO 107+12.93 LT	370	144.0
SUBTOTAL =	x2 COATS	222.8
TOTAL		654.6

HOT-MIX ASPHALT SURFACE COURSE,  
MIX "D", N70

LOCATION	QUANTITY
STATION	(TON)
MAINLINE	
104+25.00 TO 114+30.00	533
TOTAL	533

BITUMINOUS MATERIAL (PRIME COAT)

LOCATION	QUANTITY	
	(SQ YD)	(TON)
HMA SURFACE COURSE	5720.0	2.2
HMA BINDER COURSE	4752.0	1.8
HMA SHOULDERS (X2)	1178.6	0.4
INCID. HMA SURFACING	840.0	0.4
ENTRANCES & SIDEROADS	1023.0	0.8
TOTAL		5.6

AGGREGATE (PRIME COAT)

LOCATION	QUANTITY
STATION	(TON)
103+95.00 TO 114+60.00	8.1
106+00.00 LT	0.2
108+62.50 LT	0.2
111+34.17 LT	0.2
112+00.00 LT	0.2
112+49.09 LT	0.2
TOTAL	9.1

PORTLAND CEMENT CONCRETE  
SIDEWALK, 5 INCH

LOCATION	QUANTITY
STATION	(SQ FT)
105+77.57 TO 105+83.89 LT	44
106+24.73 TO 108+55.17 LT	1205
TOTAL	1249

DETECTABLE WARNINGS

LOCATION	QUANTITY
STATION	(SQ FT)
105+77.57 TO 105+83.89 LT	44
106+24.73 TO 106+34.73 LT	44
108+45.17 TO 108+55.17 LT	44
TOTAL	132

DRIVEWAY PAVEMENT REMOVAL

LOCATION		QUANTITY
STA.	OFFSET	(SQ YD)
106+00.00	LT	135.4
108+62.75	LT	78.5
110+70.27	LT	30.9
111+34.07	LT	85.0
112+00.00	LT	75.0
112+49.09	LT	85.5
TOTAL		490.3

BITUMINOUS CONCRETE  
SHOULDER REMOVAL

LOCATION		QUANTITY
STATION	OFFSET	(SQ YD)
105+78.52 TO 109+30.57	RT	200.7
106+91.45 TO 109+30.64	LT	130.6
109+44.78 TO 114+60.00	RT	315.5
109+44.95 TO 110+70.35	LT	89.3
111+09.61 TO 111+24.97	LT	10.7
111+44.26 TO 111+94.10	LT	44.3
112+11.01 TO 112+38.30	LT	22.7
112+59.04 TO 114+00.93	LT	138.4
114+28.71 TO 114+60.00	LT	17.4
TOTAL		969.6

PAVEMENT REMOVAL

LOCATION	QUANTITY
STATION	(SQ YD)
105+75.66 TO 109+07.55 (LT)	478.0
109+67.55 TO 111+73.13 (LT)	13.8
103+95.00 TO 109+07.55 (RT)	94.0
VALLEY LANE	162.6
MANOR LANE	125.9
TOTAL	874.3

COMBINATION CURB AND  
GUTTER REMOVAL

LOCATION		QUANTITY
STATION	OFFSET	(FOOT)
103+95.00 TO 106+38.01	LT	244
103+95.00 TO 105+66.81	RT	172
TOTAL		416