


## PROPOSED SECTION

I-290 TO I90/I94 SOUTHBOUND RAMP - STA 16+38 TO 20+71



## PROPOSED SECTION


STA 20+71 TO 22+24

# **EXISTING LEGEND:**

- (A) EXISTING SUB-BASE GRANULAR MAT'L 6" OR STABILIZED SUB-BASE 4"
- (B) EXISTING HMA SHOULDERS
- C EXISTING PIPE UNDERDRAIN
- D EXISTING COMB CONC CURB AND GUTTER TYPE M-2.12
- (E) EXISTING HMA SURFACING
- (F) EXISTING P.C.C. SHOULDER
- G EXISTING P.C.C. BASE COURSE
- (H) EXISTING PGE WRAPPED IN FABRIC (VARIOUS LOCATIONS)
- I EXISTING HMA CONC SURFACE CSE, MIX D, CL I, TYPE 2 (1-3/4")
- J EXISTING HMA CONC SURFACE CSE, MIX E, CL I, TYPE 1 (1-3/4")
- (K) EXISTING HMA CONC SURFACE CSE, MIX B, TYPE 1 (2-1/4")
- (L) EXISTING CONCRETE BARRIER
- (M) EXISTING STEEL PLATE BEAM GUARD RAIL TO BE REMOVED
- (N) EXISTING RETAINING WALL

## PROPOSED LEGEND:

- 1 PROPOSED HMA SHOULDER, 10"
- 2 PROPOSED COMB CONC CURB AND GUTTER, TYPE M-2.12
- (3) PROPOSED CONCRETE JERSEY BARRIER, DOUBLE FACE, 32" HEIGHT
- 4) PROPOSED AGGREGATE BASE COURSE, TYPE B, 4"
- (5) PROPOSED SUB-BASE GRANULAR MATERIAL, TY B, 6" & VARIES



#### PROPOSED SECTION

I-290 TO I90/I94 SOUTHBOUND RAMP - STA 22+24 TO 23+00.81

FILE NAME =	USER NAME = 3690	DESIGNED - AAC	REVISED ~			F.A.I SECT	TON COUNTY TOTAL SHEET
S:\11-CADD\01-sht\07_D160D93-SHT-TYPICAL0	3.dgn	DRAWN - ED	REVISED -	STATE OF ILLINOIS	TYPICAL SECTIONS	290 2007-0	057 T COOK 60 7
	PLOT SCALE = 5:1	CHECKED - AAC	REVISED -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 60D93
	PLOT DATE = Thursday, December 11, 2008	DATE - 12/12/2008	REVISED		SCALE: NONE SHEET NO. 3 OF 4 SHEETS STA. 10+00.00 TO STA. 25+67.92	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT