

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

COUNTY TOTAL SHEET NO. FILE NAME = DESIGNED -USER NAME = gaglianobt REVISED - R. MIRS 09-15-97 SECTION ARTERIAL ROAD W:\d:ststd\22x34\tc22.dgr DRAWN REVISED - R. MIRS 12-11-97 STATE OF ILLINOIS LAKE 39 36 56 RS-8 352 INFORMATION SIGN PLOT SCALE = 50.000 '/ IN. CHECKED REVISED -T. RAMMACHER 02-02-99 **DEPARTMENT OF TRANSPORTATION** TC-22 CONTRACT NO. 60E23

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT PLOT DATE = 1/4/2008 REVISED - C. JUCIUS 01-31-07 TO STA. SHEET NO. 1 OF 1 SHEETS STA. SCALE: NONE