

SUMMARY OF QUANTITIES			100% STATE	
			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				CH 92 SFTY-2A
CODE NO	ITEM	UNIT		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1	1
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	43	43
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	28	28
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	28	28
28000400	PERIMETER EROSION BARRIER	FOOT	111	111
28100103	STONE RIPRAP, CLASS A2	SQ YD	40	40
28100105	STONE RIPRAP, CLASS A3	SQ YD	16	16
28200200	FILTER FABRIC	SQ YD	57	57
20900110	POROUS GRANULAR BACKFILL	CU YD	140	140
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	70	70
50102400	CONCRETE REMOVAL	CU YD	11	11
50200100	STRUCTURE EXCAVATION	CU YD	62	62
50202901	COFFERDAM (LOCATION-1)	EACH	1	1
50300225	CONCRETE STRUCTURES	CU YD	12	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,660	1,660

SUMMARY OF QUANTITIES			100% STATE	
			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				CH 92 SFTY-2A
CODE NO	ITEM	UNIT		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	13	13
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	106	106
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	115	115
67100100	MOBILIZATION	L SUM	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	100	100
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	3	3
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1
X0321781	MECHANICAL SPLICE	EACH	8	8
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2

* SPECIALTY ITEM

Rev 4-8-09

FILE NAME = 1024M_sht_S00.dgn
PLOT DATE = 1/23/2009



CHRISTIAN-ROSE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	-	S.J.P.	REVISED	-
DRAWN	-	A.Y.	REVISED	-
CHECKED	-	S.J.P.	REVISED	-
DATE	-	JANUARY 27, 2009	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
CH 92 (FOREST WAY DRIVE)

CH	SECTION	COUNTY	TOTAL SHEETS
92	2008-029 I	COOK	15
			CONTRACT NO. 60

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 130+00 TO STA. 131+15

ILLINOIS FED. RD. PROJECT