

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES CH 92 (FOREST WAY DRIVE)
3	SUMMARY OF QUANTITIES CH 92 (FOREST WAY DRIVE)
4	TYPICAL SECTIONS AND DETAILS CH 92 (FOREST WAY DRIVE)
5	ALIGNMENT AND TIES CH 92 (FOREST WAY DRIVE)
6	EXISTING AND PROPOSED PLAN AND PROFILE CH 92 (FOREST WAY DRIVE)
7	SUGGESTED TRAFFIC CONTROL AND STAGING PLAN CH 92 (FOREST WAY DRIVE)
8	EROSION CONTROL AND GRADING PLAN CH 92 (FOREST WAY DRIVE)
9	WINGWALL PLAN AND ELEVATION
10	WINGWALL DETAILS
11	SOIL BORING LOGS
12 - 13	CROSS SECTIONS CH 92 (FOREST WAY DRIVE)
14	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
15	ARTERIAL ROAD INFORMATION SIGN

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
630001-08	STEEL PLATE BEAM GUARDRAIL
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR AND MARKER AND MOUNTING DETAILS
701501-05	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901-01	TRAFFIC CONTROL DEVICES
704001-05	TEMPORARY CONCRETE BARRIER

GENERAL NOTES

1. FORTY-EIGHT HOURS BEFORE STARTING EXCAVATION, THE CONTRACTOR WILL CALL J.U.L.I.E. (1-800-892-0123) OR 811 TO HAVE THE LOCATION OF EXISTING UTILITIES STAKED.
2. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
3. SAW CUTTING PRIOR TO ANY REMOVAL ITEMS NOTED ON THE PLANS OR DIRECTED BY THE ENGINEER SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR CONCRETE REMOVAL.
4. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
5. THE CONTRACTOR SHALL USE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
6. THE CONTRACTOR MUST PROTECT PAVEMENT WHEN DUMPING RIPRAP ONTO THE PAVEMENT AND WILL BE RESPONSIBLE FOR RESTORING PAVEMENT MARKINGS.
7. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION.
8. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO ASSURE THAT NO DEBRIS FALLS IN THE CREEK. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR CONCRETE REMOVAL.
9. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
10. THE CONTRACTOR SHALL SUBMIT THEIR FINAL DE-WATERING AND SEDIMENT CONTROL PLANS FOR THE PROJECT PRIOR TO THE START OF WORK.
11. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
12. THE EXISTING EARTH SHOULDER TO BE REMOVED AND THE EARTH EXCAVATION FOR THE PROPOSED RIP-RAP, ESTIMATES 12" DEPTH, SHALL BE PAID FOR AS REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL. THE COST OF CLEARING THE AREA WITHIN THE CONSTRUCTION LIMITS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

FILE NAME = 1024M_sht.Index.dgn
PLOT DATE = 1/23/2009



DESIGNED	S.J.P.	REVISED	-
DRAWN	A.Y.	REVISED	-
CHECKED	S.J.P.	REVISED	-
DATE	JANUARY 27, 2009	REVISED	-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, LIST OF STATE STANDARDS
AND GENERAL NOTES CH 92 (FOREST WAY DRIVE)**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 130+00 TO STA. 131+15

CH	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
92	2008-029 I	COOK	15	2
CONTRACT NO. 60E61				

ILLINOIS FED. AID PROJECT