

**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN 100% FED.	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ U.S. ROUTE 30	TRAFFIC SIGNALS IL 59 @ LOCKPORT	ROADWAY LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/ SANITARY SEWER	SIDEWALK
				J000-2A									
60255500	MANHOLES TO BE ADJUSTED	EACH	6	6									
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2									
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1									
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2									
60500040	REMOVING MANHOLES	EACH	18	18									
60500050	REMOVING CATCH BASINS	EACH	47	47									
60500060	REMOVING INLETS	EACH	10	10									
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	5	5									
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1	1									
60500205	FILLING CATCH BASINS	EACH	8	8									
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	317	317									
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1270	1270									
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	529	529									
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6791	6791									
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	290	290									
60609800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18	FOOT	25	25									
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	24	24									
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	472	472									
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	688	688									
60900515	CONCRETE THRUST BLOCKS	EACH	6									6	
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	6	6									
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	145	145									
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18									
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	18	18									

\* Specialty Items