

**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITY	URBAN 100% F&D	ROADWAY & DRAINAGE	TRAFFIC SIGNALS IL 59 @ U.S. ROUTE 30	TRAFFIC SIGNALS IL 59 @ LOCKPORT	ROADWAY LIGHTING	TRAFFIC SIGNALS INTERCONNECT	TRAFFIC SIGNALS TEMPORARY INTERCONNECT	TRAFFIC SIGNALS EVP EQUIPMENT	WATER MAIN/ SANITARY SEWER	SIDEWALK
				J000-2A									
X0325885	STEEL CASING PIPE AUGERED AND JACKED 36"	FOOT	405									405	
X0326004	DUCTILE IRON WATER MAIN 20" x 12" (REDUCER)	EACH	3									3	
X0326005	DUCTILE IRON WATER MAIN 20" x 12" (TEE)	EACH	2									2	
X0326007	DUCTILE IRON WATER MAIN 20" x 8" (TEE)	EACH	7									7	
X0326009	DUCTILE IRON WATER MAIN 20" (45 DEGREE BEND)	EACH	4									4	
X0326010	DUCTILE IRON WATER MAIN 20" (22.5 DEGREE BEND)	EACH	3									3	
X0326011	DUCTILE IRON WATER MAIN PLUG, 20"	EACH	1									1	
X0712400	TEMPORARY PAVEMENT	SQ YD	4786		4786								
X2111000	TOPSOIL EXCAVATION	CU YD	1239		1239								
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	27		27								
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	10		10								
X4023000	TEMPORARY ACCESS (ROAD)	EACH	13		13								
X4200500	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	685		685								
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			1	1						
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2			1	1						
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3151						3151				
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1259			794	465						
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	675								675		
* X8900015	TEMPORARY TRAFFIC SIGNAL INTERCONNECTION SYSTEM	L SUM	1							1			
X0326413	CONCRETE COMBINATION CURB AND GUTTER, TYPE B-6.06 (TEMPORARY)	FOOT	5870		5870								
XX001621	BRICK PAVER: REMOVAL	SQ FT	1355		1355								
X0326414	CONCRETE STAMPED COLOR PORTLAND CEMENT MEDIAN SURFACE 8 INCH	SQ FT	1142		1142								
X0326415	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 16"	FOOT	45		38							7	
* X0326269	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1			1							
X0326416	DUCTILE IRON WATER MAIN TEE, 20" x 20"	EACH	2									2	

\* Specialty Items