

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

W:\diststd\22x34\tc22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97		ARTERIAL ROAD INFORMATION SIGN	F.A.U. RTE. SECTION 1350 2008-063 RS	COUNTY SHEETS NO.
	PLOT SCALE = 50.000 '/ IN. PLOT DATE = 1/4/2008	CHECKED -	REVISED - T. RAMMACHER 02-02-99 REVISED - C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	TC-22 FED. ROAD DIST. NO. 1 ILLINOIS FED	CONTRACT NO. 60F40