


EXISTING TYPICAL SECTION TOUHY AVE.

STATION: 131+00 TO 157+00



PROPOSED TYPICAL SECTION TOUHY AVE.

STATION: 131+00 TO 157+00

LEGEND

- (1) EXISTNG P.C.C. BASE COURSE, 9"(±)
- (2) EXIST. HOT-MIX ASPHALT SURFACE COURSE (BEFORE MILLING), 6"(±)
- (3) EXISTNG CURB & GUTTER, B-6.12 (MOD)
- (4) EXISTNG AGGREGATE SHOULDER
- 5 PROP. HOT-MIX ASPHALT SURFACE REMOVAL 2 1/2" (3 1/2" OF HOT-MIX ASPHALT TO REMAIN)
- © PROP. POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, 1 3/4"
- (7) PROP. POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4"
- 8 PROP. CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (LOCATIONS TO BE DETERMINED BY THE RESIDENT ENGINEER)
- (9) PROP. GRADING AND SHAPING
- (10) PROP. AGGREGATE SHOULDER, TYPE "B"

NOTES:

- 1. SEE ROADWAY AND PAVEMENT MARKING PLAN SHEETS FOR LOCATIONS OF LEFT TURN AND RIGHT TURN LANES
- 2. PAVEMENT PATCHING SHALL BE DONE PRIOR TO MILLING OF THE ROADWAY

ŀ					
	FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	Ī
	c:\pw_work\PWIDOT\KELLERS\dms89422\DI07	909-sht-plan.dgn	DRAWN -	REVISED -	1
		PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	1
	*	PLOT DATE = 2/2/2009	DATE -	REVISED -	ĺ

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TOUHY AVE. (N.W. HWY TO CENTRAL AVE.) EXISTING & PROPOSED TYPICAL CROSS SECTIONS							
SCALE:	NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.	

1	FED. RO	DAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT		
			CONTRACT	NO. 6	OF 48
1	341,375	2326.1RS-1	СООК	30	7
	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.