SCOTT HEMMINGS RED SPEED DIRECT - (630)-317-5740 CELL (630)-234-9789

IL ROUTE 68 (DUNDEE ROAD)

TEMP. RADIO INTERCONNECT

RAND ROAD (EAST)

10 20 30 40 SCALE IN FEET

TEMPORARY TRAFFIC SIGNAL LEGEND TEMPORARY TRAFFIC SIGNAL HEAD SPAN WIRE MOUNTED TEMPORARY TRAFFIC SIGNAL HEAD SPAN WIRE MOUNTED SECONDARY LOCATION TEMPORARY WOOD POLE (CLASS 5 OR BETTER) TEMPORARY CONTROLLER CABINET TEMPORARY SPAN WIRE, TETHER WIRE, AND CABLE  $\Box$ TEMPORARY SERVICE INSTALLATION TEMPORARY PEDESTRIAN SIGNAL HEAD, BRACKET MOUNTED 0 PEDESTRIAN PUSHBUTTON DETECTOR EMERGENCY VEHICLE LIGHT DETECTOR CONFIRMATION BEACON VEHICLE DETECTOR, INDUCTION LOOP COMMON TRENCH G.S. CONDUIT IN TRENCH OR PUSHED Н HEAVY DUTY HANDHOLE

VIDEO DETECTION CAMERA

RADIO INTERCONNECT

VIDEO DETECTION ZONE

EXISTING EQUIPMENT TO BE REMOVED LEGEND EXISTING SIGNAL HEAD TO BE REMOVED EXISTING SERVICE INSTALLATION TO BE REMOVED "E"() EXISTING SIGNAL POST AND FOUNDATION TO BE REMOVED EXISTING ALUMINUM MAST ARM POLE AND FOUNDATION TO BE REMOVED EXISTING CONTROLLER AND FOUNDATION TO BE REMOVED EXISTING HANDHOLE TO BE REMOVED "E"-EXISTING PEDESTRIAN SIGNAL HEAD TO BE REMOVED EXISTING PEDESTRIAN PUSH-BUTTON TO BE REMOVED EMERGENCY VEHICLE SYSTEM DETECTOR TO BE RELOCATED CONFIRMATION BEACON TO BE RELOCATED HEAVY DUTY HANDHOLE TO BE REMOVED "E"0-MAST ARM ASSEMBLY AND POLE TO BE REMOVED "R" "A" "S" SAVE EQUIPMENT IN CURRENT LOCATION

MATCH LINE B-B SEE SHEET 1 OF 2 동풍

SIDEWALK REMOVAL 1.183 SQ. FT. (FOR LIGHTING WORK ₽₽ 1025+00 1024 MAI IL ROUTE 5368 (DUNDEE ROAD) EXIST. R.O.W SIDEWALK REMOVAL = 376 SQ. FT. (FOR LIGHTING WORK)

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

ONE NORTH FRANKLIN **JACOBS** CHICAGO IL. 60606 312-251-3000 COUNTY

TEMPORARY TRAFFIC SIGNAL INSTALLATION - SHEET 2 OF 2 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT PLAN U.S. ROUTE 12 (RAND ROAD) AND IL ROUTE 53 / 68 (DUNDEE ROAD)

STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

DESIGNED CH, JS REVISED B\_TempSignalPlan\_Rand&Dundee\_2.dgr DRAWN REVISED LOT SCALE = \$SCALE\$ CHECKED MJL REVISED DATE REVISED

LYNDA DRIVE

1010+00

TEMPORARY INTERCONNECT DETAIL

LYNDA DRIVE RADIO INTERCONNECT

SCALE: 1"=20' SHEET NO. OF SHEETS STA.

TOTAL SHEE SHEETS NO. 80 16 соок 2008-08-3 CONTRACT NO. 60F87 FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT