

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	I000-2A			
0201006	GRADING AND SHAPING SHOULDERS	UNIT	191	191			
0600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	56			
0600300	AGGREGATE (PRIME COAT)	TON	280	280			
0600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	21	21			
10600895	CONSTRUCTING TEST STRIP	EACH	2	2			
10600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	860	860			
<del>10600982</del>	<del>TEMPORARY RAMP</del>	<del>SO YD</del>	<del>860</del>	<del>860</del>			
10603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5479	5479			
10603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	470	470			
42001300	PROTECTIVE COAT	SO YD	228	228			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	65223	65223			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	4796	4796			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	685	685			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	2077	2077			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	607	607			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	817	817			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	762	762			
55039700	STORM SEWERS TO BE CLEANED	FOOT	1400	1400			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN 100% FED. TOTAL QUANTITIES	I000-2A			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7500	7500			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	625	625			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	51047	51047			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2429	2429			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1326	1326			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2490	2490			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	464	464			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	23327	23327			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	625	625			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	51047	51047			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2429	2429			
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1326	1326			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2490	2490			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	464	464			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	717	717			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	610	610			
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1527	1527			
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	2757	2757			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Z0076600	TRAINEES	HOUR	1500	1500			

\* SPECIALTY ITEMS  
 NON-PARTICIPATING ITEMS (100% COST)  
 © Y080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES	
		F.A.P. 351 (US 6/ IL 7 (159TH ST.))	
		WILL-COOK RD. TO US 45 (LA GRANGE RD.)	
REV.		PLOT DATE: 2/10/2009	

2/10/2009 10:48:14 AM C:\p0248780\31109-8111-0000.dgn