

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% FED 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5				
40600300	AGGREGATE (PRIME COAT)	TON	25	25				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	37	37				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	487	487				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1363	1363				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	12162	12162				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8846	8846				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2949	2949				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	200	200				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48648	48648				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	365	365				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	365	365				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	200	200				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	617	617				
0 28076600	TRAINERS	Hour	500	500				

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT			I000-2A				

* SPECIALTY ITEM

0 Y080 (100% FEDERAL)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009