ROUTE: Roosevelt Rd. from just west of 25th. Ave. to N & S sides of bridge

	CROSS STREETS			LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM		ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
North Frontage Rd.			(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Just W/O 25th		IHB RR	WB	***************************************	12	6	72	8
		longit. Jt.	CL		2	45	90	10
			EB		12	10	120	13
			WB		12	10	120	13
	~ ~~~		EB & WB		12	6	72	8
			WB		12	25	300	33
			EB		12	12	144	16
			WB		12	35	420	47
			WB		12	6	72	8
			EB		12	6	72	8
,			EB		12	6	72	8
			WB		12	6	72	8
			EB		12	15	180	20
			WB		12	30	360	40
			EB		12	8	96	11
			WB		12	8	96	11
	South Fr	ontage Rd.						
Just W/O 25th		IHB RR	EB		12	12	144	16
			WB		12	20	240	27
			EB		12	12	144	16
			EB	*******	12	6	72	8
	· · · · · · · · · · · · · · · · · · ·		WB		12	6	72	8
			EB		12	6	72	8
			WB		12	6	72	8
			EB		12	6	72	8
			WB		12	6	72	8
			EB		12	20	240	27
			EB		12	6	72	8
			WB		12	6	72	8
			EB		12	25	300	33
			WB		12	6	72	8

TOTALS:

377 FT 453 SY

FILE NAME =	USER NAME = amithkl	DESIGNED -	REVISED -		PATCHING SCHEDULE				F.A.	SECTION	COUNTY	TOTAL SHEE	T		
c:\pw_work\PWIDOT\SMITHKL\dØ125091\Desig	c:\pw_work\PW[DOT\SM[THKL\dØ125Ø91\Destgn.dgn		REVISED -	STATE OF ILLINOIS						VAR.	2009-025 PP	соок	49 30	<u> </u>	
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	ROOSEVELT RD.						CONTRAC	CT NO. 60G2	4		
	PLOT DATE = 2/9/2009	DATE -	REVISED -		SCALE:	SHEET NO.	0F	SHEETS	STA.	TO STA.	FED. ROAD	DIST. NO. ILLINOIS	FED. AID PROJECT		J