

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | URBAN UNIT | TOTAL QUANTITY | ROADWAY | BRIDGE ① | LIGHTING | CDOT LIGHTING | CDOT TRAFFIC SIGNALS | CONSTRUCTION TYPE CODE | | | | | | | | | | | | |
|----------|---|------------|----------------|---------|-------------|----------|---------------|----------------------|------------------------|--|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | | | | | | | | | | | |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 70 | 70 | | | | | | | | | | | | | | | | | |
| 20101000 | TEMPORARY FENCE | FOOT | 500 | 500 | | | | | | | | | | | | | | | | | |
| 20101100 | TREE TRUNK PROTECTION | EACH | 20 | 20 | | | | | | | | | | | | | | | | | |
| 20700400 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 201 | | 201 | | | | | | | | | | | | | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 1996 | 1996 | | | | | | | | | | | | | | | | | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.4 | 0.4 | | | | | | | | | | | | | | | | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | | | | | | | | | | | | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | | | | | | | | | | | | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | | | | | | | | | | | | | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 1996 | 1996 | | | | | | | | | | | | | | | | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 547 | 547 | | | | | | | | | | | | | | | | | |
| 28000510 | INLET FILTERS | EACH | 4 | 4 | | | | | | | | | | | | | | | | | |
| 31200100 | STABILIZED SUB-BASE 4" | SQ YD | 44 | 44 | | | | | | | | | | | | | | | | | |
| 35300400 | PORTLAND CEMENT CONCRETE BASE COURSE 9" | SQ YD | 44 | 44 | | | | | | | | | | | | | | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 5 | 5 | | | | | | | | | | | | | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 13 | 13 | | | | | | | | | | | | | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 0.7 | 0.7 | | | | | | | | | | | | | | | | | |
| 40600635 | LEVELING BINDER (MACHINE METHOD), N70 | TON | 367 | 367 | | | | | | | | | | | | | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | | | | | | | | | | | | | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 551 | 551 | | | | | | | | | | | | | | | | | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 5 | 5 | | | | | | | | | | | | | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 305 | 305 | | | | | | | | | | | | | | | | | |
| 42001400 | BRIDGE APPROACH PAVEMENT (SPECIAL) | SQ YD | 370 | 370 | | | | | | | | | | | | | | | | | |
| 42001420 | BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) | SQ YD | 132 | 132 | | | | | | | | | | | | | | | | | |
| 42400410 | PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH | SQ FT | 1993 | 1993 | | | | | | | | | | | | | | | | | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 111 | 111 | | | | | | | | | | | | | | | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 143 | 143 | | | | | | | | | | | | | | | | | |
| 44000198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 6561 | 6561 | | | | | | | | | | | | | | | | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 436 | 436 | | | | | | | | | | | | | | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 1995 | 1995 | | | | | | | | | | | | | | | | | |
| 44000700 | APPROACH SLAB REMOVAL | SQ YD | 368 | 368 | | | | | | | | | | | | | | | | | |

• DENOTES SPECIALTY ITEMS
 NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 112TH PLACE OVER
 F.A.I. ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
 DATE: 01/16/09 CHECKED BY: ACL

TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312/618-0000

I:\LIBRARY\ALDEN\... \S\00005\ADEN... \S\00005\3.DGN
 1/16/2009, 10:56:05
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

Rev.