

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE ①	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE													
									100% FED. URBAN X771-2A													
44003100	MEDIAN REMOVAL	SO FT	400	400																		
44200104	PAVEMENT PATCHING, TYPE I, 9 INCH	SO YD	100	100																		
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SO YD	150	150																		
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SO YD	200	200																		
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SO YD	200	200																		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2460	2460																		
50102400	CONCRETE REMOVAL	CU YD	64.1		64.1																	
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1		1																	
50157300	PROTECTIVE SHIELD	SO YD	1613		1613																	
50200100	STRUCTURE EXCAVATION	CU YD	201		201																	
50300225	CONCRETE STRUCTURES	CU YD	62.6		62.6																	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	512.9		512.9																	
50300260	BRIDGE DECK GROOVING	SO YD	1596		1596																	
50300300	PROTECTIVE COAT	SO YD	2104		2104																	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	8210		8210																	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28		28																	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120540		120540																	
50800515	BAR SPLICERS	EACH	134		134																	
50901730	BRIDGE FENCE RAILING	FOOT	516		516																	
51500100	NAME PLATES	EACH	2		2																	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	171		171																	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28		28																	
52100520	ANCHOR BOLTS, 1"	EACH	112		112																	
58700300	CONCRETE SEALER	SO FT	346		346																	
59000200	EPOXY CRACK INJECTION	FOOT	55		55																	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	23	23																		
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	10	10																		
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	10	10																		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12																		
67100100	MOBILIZATION	L SUM	1	1																		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1																		

• DENOTES SPECIALTY ITEMS
 NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
112TH PLACE OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
255 N. MICHIGAN AVE., CHICAGO, IL 60601
TELEPHONE: 312/616-0000

ATTENTION: S:\0005\AD\001\SUB\0005\3.DWG
P:16-2009-1005607
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
HECHTER