F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1920.1B-R	COOK	101	007
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62533

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE ①	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
			100% FED. URBAN X771-2A	CONSTRUCTION TYPE CODE										
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1										
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	876	876										
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	61	61										
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	502	502										
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1725	1725										
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1378	1378										
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1600	1600										
* 72000100	SIGN PANEL - TYPE 1	SQ FT	30	30										
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	63	63										
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2	2										
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255	255										
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2490	2490										
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1084	1084										
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120										
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	156	156										
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	195	195										
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	861	861										
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	235	235										
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	60	60										
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	130	130										
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	128	128										
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	168	168										
✱ 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	820			820								
✱ 81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	920				920							
✱ 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6 " X 4"	EACH	12			12								
✱ 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10 " X 6"	EACH	6			6								
✱ 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	2860			2860								
✱ 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	12				12							
✱ 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8				8							
✱ 88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2				2							
✱ 88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2				2							

* DENOTES SPECIALTY ITEMS
☐ NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
112TH PLACE OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\T1B00MWA.DGN ..\S0000SVA.DGN ..\S0000S13.DGN
FRI 2009, 0:55:09 T:\DOCUMENT\030860\CIVIL\DGN\S0000TSV.DGN
HECHTBR