F. A. U. RTE.			COUNTY	TOTAL SHEETS	SHEET
348			соок	41	2
STA. TO STA.					
FED. F	ROAD DIST. NO.	ILLINOIS	FED. AID PR	DIECT	1

CONTRACT #63106

INDEX OF SHEETS

34. 5. 619. 19. 20. 2235. 36. 3739.	COVER SHEET INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTE SUMMARY OF QUANTITIES TYPICAL CROSS SECTIONS PLAN SHEETS (HARLEM AVENUE) PLANT SPECIFICATION LANDSCAPE PLANT LIST LANDSCAPING PLANS (HARLEM AVENUE) MISCELLANEOUS DETAILS CONCEPTUAL SIGN PLANTING DETAILS CONSTRUCTION DETAILS

STATE STANDARDS

000001-05	STANDARD SYMBOLS, ASSREUTATIONS AND PATTERNS
424001-05	CURB RAMP FOR SIDEWALKS
542301-02	PRECAST REINFORCED CONCRETE FLARED END SECTION
602011-01	CATCH BASIN, TYPE C
604001-03	FRAME AND LIDS TYPE I
604036-02	GRATE, TYPE 8
606001-04	CONCRETE CURB TYPE B AND COMBINATION
	CONCRETE CURB AND GUTTER
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
701601-06	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH
	NONTRAVERSABLE MEDIAN
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR
	SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720016-02	MAST ARM MOUNTED STREET NAME SIGNS
630001-08	STEEL PLATE BEAM GUARDRAIL

GENERAL NOTES

- BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- 10 FOOT TRANSITIONS SHALL BE USED TO MATCH THE PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY 3. COMPANIES AND THE VILLAGE OF BRIDGEVIEW.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE VILLAGE.
- THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION, SHALL GOVERN
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF
- UNDERBRUSH OR DEBRIS AT PLANTING LOCATIONS SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH SECTION 201 OF THE STANDARD SPECIFICATIONS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT THE COSTS SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICES FOR THE CONSTRUCTION ITEMS INVOLVED, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE CONTRACTOR SHALL PROTECT ALL EXISTING PLANT MATERIAL FROM DAMAGE FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS UNLESS OTHERWISE NOTED.
- ALL PERENNIAL PLANT BEDS SHALL HAVE ALL THE SOD REMOVED AND DISPOSED FROM THE BED PRIOR TO TILLING THE EARTH AS DESCRIBED IN ARTICLE 254.07(b) OF THE
- ALL PERENNIALS SHALL BE PLANTED 12" ON CENTER AND MULCHED AS DESCRIBED IN 10. ARTICLE 254.08 OF THE STANDARD SPECIFICATIONS.
- PRE-EMERGENT GRANULAR HERBICIDE SHALL BE PLACED IN MULCH BEDS ACCORDING 11.
- VILLAGE WATER, SEWER MAINS AND OTHER UTILITIES MAY BE LOCATED IN THE VILLAGE WATER, SEWER MAINS AIND OTHER UTILITIES MAT BE LOCATED IN THE LANDSCAPING AREA. THE ACTUAL LOCATION OF PROPOSED LANDSCAPING WILL BE ADJUSTED IN THE FIELD TO AVOID UTILITIES. THE VILLAGES OF WORTH, PALOS HILLS, CHICAGO RIDGE, OAK LAWN, BRIDGEVIEW, BURBANK, AND BEDFORD PARK ARE NOT PART OF "J.U.L.I.E." THE CONTRACTOR SHALL CONTACT THE RESPECTIVE VILLAGES TO LOCATE THEIR UTILITIES.
- THE CONTRACTOR WILL NOT BE ALLOWED TO PROCEED WITH ANY PLANTING WORK UNTIL ALL UTILITY OWNERS LOCATE THEIR FACILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS.
- MULCH PLACEMENT 3" IS TO BE PLACED AROUND EXISTING TREES AND SHRUBS IN LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER.
- WHERE MULCH BEDS ARE SPECIFIED, ALL EXISTING GRASS, WEEDS, AND DEBRIS ARE TO BE REMOVED AND THE BEDS TILLED TO A DEPTH OF 6" PRIOR TO PLACING PROPOSED PLANTS. FOLLOWING PLANTING, BEDS ARE TO BE MULCHED TO A DEPTH OF 3". THIS WORK WILL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR THE PLANTING ITEMS.

ILLINOIS DEPARTMENT OF TRANSPORTATION

REVISIONS FAP 348 (HARLEM AVENUE) DATE BEAUTIFICATION STREETSCAPING INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES

> SCALE: VERT. NA HORIZ. NA DATE 12-19-08

DRAWN BY PS CHECKED BY RJW