



EXISTING TYPICAL CROSS SECTION
STA 11+25 TO STA 12+13 AND STA 16+05 TO STA 18+08



PROPOSED TYPICAL CROSS SECTION
STA 11+25 TO STA 12+13 AND STA 16+05 TO STA 18+08

HOT-MIX ASPHALT MIXTURE REQUIREMENTS							
MIXTURE TYPE	AC TYPE	AIR VOIDS					
BUS LOADING ZONE LANE EXTENSION	,						
HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50; (IL 9.5mm)	PG 64-22	4% AT 50 Gyr					
HOT-MIX ASPHALT BINDER COURSE, N50; (IL-19.0mm)	PG 64-22 *	4% AT 50 Gyr					


*WHEN RAP EXCEEDS 20%, THE NEW ASPHALT BINDER IN THE MIX SHALL BE PG 58-22 THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX ASPHALT SURFACE MIXTURES IS 112 lbs/sq yd/ in.



EXISTING TYPICAL CROSS SECTION STA 12+13 TO STA 12+57

EXISTING LEGEND

- A) EXISTING ROADWAY TO REMAIN
- B EXISTING TYPE M-2.12 CURB AND GUTTER TO REMAIN
- C CONCRETE SIDEWALK TO REMAIN
- D EXISTING GRASSED PARKWAY
- E) EXISTING GRASSED PARKWAY TO BE REMOVED (TO BE PAID FOR AS EARTH EXCAVATION)
- F EXISTING BITUMINOUS DRIVEWAY TO BE REMOVED (TO BE PAID FOR AS EARTH EXCAVATION)
- G EXISTING BITUMINOUS BUS LOADING ZONE LANE
- H EXISTING CURB AND GUTTER TY. M-4.12 TO REMAIN
- () EXISTING DEPRESSED CURB TO REMAIN




EXISTING TYPICAL CROSS SECTION STA 12+88 TO STA 16+05

*STA 12+57 TO STA 12+88
EXISTING IS GRASSED PARKWAY UP TO P.C.C.
SIDEWALK AS SHOWN ON THE PLAN SHEET
(REMOVAL OF GRASSED PARKWAY TO BE PAID
FOR AS EARTH EXCAVATION.)

PROPOSED LEGEND

- 1) EXISTING ROADWAY TO REMAIN
- 2) EXISTING TYPE M-2.12 CURB AND GUTTER TO REMAIN
- 3 CONCRETE SIDEWALK TO REMAIN
- 4 EXISTING DEPRESSED CURB TO REMAIN
- PROPOSED P.C.C. SIDEWALK, 5" PROPOSED SUB-BASE GRANULAR MATERIAL, TYPE B 4"
- 6 PROPOSED TOPSOIL, FURNISH AND PLACE, 4" NUTRIENTS (NITROGEN, PHOSPHORUS, POTASSIUM) SODDING, SALT TOLERANT
- 7) AGGREGATE BASE COURSE, TYPE B 8"
- 8) HOT MIX ASPHALT BINDER COURSE, (HMA BINDER IL-19.0, N50) 2 ½""
- 9 HOT MIX ASPHALT SURFACE COURSE, MIX C, N50 2"
- PROPOSED COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12 PROPOSED SUB-BASE GRANULAR MATERIAL, TYPE B 4"



PROPOSED TYPICAL CROSS SECTION STA 12+13 TO STA 12+88

*NEW P.C.C. SIDEWALK, 5" AND SUB-BASE GRANULAR MATERIAL, 4" FROM STA 12+13 TO STA 12+57

FILE NAME = 05612_02-TYPX-01	USER NAME =	DESIGNED MPN	REVISED —	
		CHECKED MPN	REVISED —	
	PLOT SCALE =	DRAWN — MJD	REVISED	
	PLOT DATE = 12-23-08	CHECKED — MJD	REVISED	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DORCHESTER AVENUE						
SIDEWALK CONSTRUCTION AND BUS LOADING ZONE EXTENSION						
TYPICAL SECTIONS						
I/A	SHEET NO. 3	OF 6	SHEETS	STA. N/A	TO STA. N/A	

SCALE: N/A

F.A.U. SECTION					COUNTY TOTAL SH SHEETS N						
06-00162-02-SW					COOK 6						
						CONTRACT NO. 63119					
FED BOAD DIST NO. 1 JULINOIS FED AL						D PROJECT	CMM-C	MM-9003/079)			