LEGEND

	EXISTING FENCE
statement of the termination	EXISTING R.O.W.
	PROPOSED FENCE
	LIMITS OF TOP SOIL AND SOD
المستميل	TREE LINE
ц	LIGHT POLE
DET	ELECTRIC TRANSFORMER
F. F.	ELECTRICAL TRANSFORMER W/CONC. PA
0	TRAFFIC SIGNAL
-0-	POWER POLE
**	GUY WIRE
⊠T	TELEPHONE PEDESTAL
Ø	HANDHOLE
Ω	FIRE HYDRANT
С	LANDSCAPE STONE
000	STORM SEWER INLET
ñ	TREE STUMP
: O *	TREE OR SHRUB
(FOUND) C	PROPERTY PIPE (FOUND)
4	SIGN
PK1 A	CONTROL POINT (PK-NAIL)
, ou	

NOTE:
PROVIDE THERMOPLASTIC PAVEMENT MARKING TO PEDESTRIAN CROSSWALK AT THE FOLLOWING INTERSECTIONS:

BENCHMARK

105 L.F. THERMOPLASTIC PAVEMENT MARKING-LINE, 6" WHITE

100 L.F. THERMOPLASTIC PAVEMENT MARKING-LINE, 6" WHITE

75 L.F. THERMOPLASTIC PAVEMENT MARKING-LINE, 6" WHITE

-	-		SUMMARY OF QUANTITIES	7	SFTY-1B
51	e D	CODE NO	ITEM	UNIT	TOTAL
-	OF.		TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8
*	-		TREE ROOT PRUNING	EACH	23
			TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	15
*			TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	9
_			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CUYD	505
_				CUYD	46
			TRENCH BACKFILL TOPSOIL FURNISH AND PLACE, 4"	SQ YD	
*			NITROGEN FERTILIZER NUTRIENT	POUND	
*					45
*			PHOSPHORUS FERTILIZER NUTRIENT	POUND	1
			POTASSIUM FERTILIZER NUTRIENT	POUND	
*			SODDING, SALT TOLERANT	SQ YD	3390
*			SUPPLEMENTAL WATERING	UNIT	50
			STONE RIPRAP, CLASS A3	SQ YD	25
	,		FILTER FABRIC	SQ YD	
			AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	490
			HMA SURFACE COURSE, MIX C, N 50	TON	55
			PCC DRIVEWAY PAVEMENT, 5 INCH	SQ YD	97
			PCC SIDEWALK 5 INCH	SQ FT	
			DETECTABLE WARNINGS	SQ FT	222
			DRIVEWAY PAVEMENT REMOVAL	SQ YD	744
			SIDEWALK REMOVAL	SQ FT	38
_			PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	23
			PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	35
_			PIPE CULVERTS, TYPE 1 RCCP 12"	FOOT	10
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
_		54213867	STEEL END SECTIONS 12"	EACH	1
_		54213870	STEEL END SECTIONS 15"	EACH	2
_		54213873	STEEL END SECTIONS 18"	EACH	2
_		550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	156
_			STORM SEWER REMOVAL 10"	FOOT	8
	*	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	3
	_	60207305	CATCH BASINS, TYPE C. TYPE 5 FRAME, OPEN LID	EACH	2
		67100100	MOBILIZATION	LSUM	1
-	*	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
*			THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	280
		10000	TREE, ACER CAMPESTRE (HEDGE MAPLE), 2" CALIPER, TREE	+	
*		B2000116	FORM, BALLED AND BURLAPPED	EACH	1
_	+		CURB CUT	FOOT	23
	-		EMBANKMENT	CUYD	5
	 		CONSTRUCTION LAYOUT	LSUM	1 1
		230 101 30		+ 2000	

*SI = SPECIALTY ITEMS

HOT-MIX ASPHALT MIXTURE REQUIREMENTS					
PAY ITEM	AC TYPE	VOIDS			
HMA SURFACE COURSE, MIX C, N 50 (IL 9.5 mm); 2"	PG 64-22	4% @ 50 GYR			

UNIT WEIGHT FOR ALL HMA SURFACE MIX IS 112 LBS/SQ YD/IN

LOCATION		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU. YD.)	TOPSOIL FURNISH AND PLACE, 4" (SQ. YD.)
65th STREET STA. 1+00 TO STA. 4+70	-	60	170
<u>59th STREET</u> STA. 2+26 TO STA. 4+23		30	215
TRAUBE AVENUE STA. 1+00 TO STA. 7+45		100	700
LINCOLN STREET STA. 0+80 TO STA. 9+36		125	765
<u>63rd_STREET</u> STA. 1+00 TO STA. 13+88		190	1,540
	TOTAL	505	3,390

GENERAL NOTES

- 1. THE CONTRACTOR SHALL NOTIFY J.U.L.I.E. (800-892-0123) AT LEAST 48 HOURS PRIOR TO CONSTRUCTION FOR LOCATIONS OF UTILITIES, AND SHALL BE RESPONSIBLE FOR THE PROTECTION OF THE SAME.
- 2. THE CONTRACTOR SHALL NOTIFY THE DUPAGE COUNTY DIVISION OF TRANSPORTATION (630-682-7318) A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION WITHIN THE COUNTY'S RIGHT OF WAY AND WITHIN 300' OF ANY COUNTY MAINTAINED SIGNAL. TRAFFIC SIGNALS AND RELATED EQUIPMENT ARE NOT ON THE J.U.L.I.E.
- 3. THE CONTRACTOR SHALL NOTIFY BURNS & McDONNELL (THE ENGINEER) AND THE VILLAGE OF WESTMONT AT LEAST 48 HOURS IN ADVANCE OF CONSTRUCTION. NO UNDERGROUND WORK SHALL BE COVERED UNTIL IT HAS BEEN INSPECTED. APPROVAL TO PROCEED MUST BE OBTAINED FROM THE ENGINEER PRIOR TO POURING ANY CONCRETE AFTER FORMS HAVE BEEN SET. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM DUPAGE COUNTY
- 4. CONTRACTORS ARE CAUTIONED AGAINST INSTITUTING ANY CHANGES AND/OR SUBSTITUTIONS TO THE PROJECT REPRESENTED BY THESE DRAWINGS WITHOUT PRIOR WRITTEN APPROVAL BY THE ENGINEER. VISUAL CONTACT WITH THESE DRAWINGS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.
- 5. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL ELEVATIONS, DIMENSIONS, AND CONDITIONS ON THE JOB. THE ENGINEER SHALL BE NOTIFIED AS SOON AS POSSIBLE OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN ON THESE DRAWINGS.
- 6. IT IS UNDERSTOOD THAT THE UNIT QUANTITIES CONTAINED IN THE SCHEDULE OF PRICES ARE INSERTED TO ENABLE THE OWNER TO CANVASS THE PROPOSALS, THAT THE UNIT PRICES NAMED IN THE PROPOSAL WILL APPLY WHETHER THE ACTUAL QUANTITIES BE GREATER OR SMALLER THAN THE ESTIMATED QUANTITY; THAT PAYMENT WILL BE MADE FOR THE TOTAL WORK ACTUALLY DONE, AND THAT, IN THE EVENT THAT THE ACTUAL QUANTITY IS LESS IN ANY CASE THAN THE ESTIMATED QUANTITY OR THAT THE ACTUAL PROPOSED WORK IS OMITTED FROM THE CONTRACT, THE OWNER WILL NOT BE HELD LIABLE FOR ANY COMPENSATION IN ADDITION TO THE AMOUNT DETERMINED BY APPLYING AGREED PRICES TO QUANTITIES OF WORK DONE NOR WILL SAID OWNER BE HELD LIABLE FOR ANY LOSS OF ANTICIPATED PROFITS FOR WORK OMITTED OR FOR ANY OTHER CLAIM IN THE PREMISES.
- ALL WORK FOR WHICH THERE IS NO SPECIFIC PAY ITEM SHALL BE CONSIDERED INCIDENTAL AND NO SEPARATE PAYMENT SHALL BE MADE WITH RESPECT TO INCIDENTAL WORK.
- 8. ANY DELAY OR EXTRA COST TO THE CONTRACTOR CAUSED BY PIPELINES OR OTHER ANT DELAY OF EARTH COST TO THE CONTROLLING AUGUST OF THE LINES OF OBSTRUCTIONS WHICH ARE NOT SHOWN ON THE DRAWINGS OR FOUND IN LOCATIONS DIFFERENT FROM THOSE INDICATED, SHALL NOT CONSTITUTE A CLAIM FOR EXTRA WORK, ADDITIONAL PAYMENT, OR DAMAGES.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL PUBLIC AND PRIVATE UTILITIES, EVEN THOUGH THEY MAY NOT BE SHOWN ON THE DRAWINGS. ANY UTILITY DAMAGES DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER AT THE CONTRACTOR'S EXPENSE.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING IMMEDIATELY ANY MUD, DIRT, OR DEBRIS DEPOSITED ON ROADWAYS FROM ANY VEHICLES EXITING OR ENTERING THE SITE.
- THE CONTRACTOR IS ESPECIALLY ALERTED TO THE FACT THAT IT IS HIS RESPONSIBILITY TO GUARD AND PROTECT NEWLY POURED CONCRETE AGAINST ANY FOREIGN MARKINGS, GRAFFITI OR OTHER DAMAGE, AND AT HIS EXPENSE, REPLACE ANY SIDEWALK NOT ACCEPTABLE TO THE ENGINEER.
- 12. ON 63rd STREET DAILY LANE CLOSURES ARE PERMITTED BETWEEN 9:00 A.M. AND 4:00 P.M. ONLY. OTHER LANE CLOSURES SHALL BE RESTRICTED TO THE HOURS OF 8:00 A.M. TO 5:00 P.M. ALL LANES SHALL BE KEPT OPEN FOR THE REMAINING PART OF EVERYDAY. DAILY LANE CLOSURES ON 63rd STREET REQUIRE DUPAGE COUNTY APPROVAL.
- 13. TRAFFIC CONTROL SHALL CONFORM TO IDOT'S HIGHWAY STANDARDS AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AT ALL TIMES DURING CONSTRUCTION. TRAFFIC CONTROL SHALL INCLUDE ADVANCE WARNING LANE CLOSURE SIGNAGE, AN ARROW BOARD AND TYPE I BARRICADES WITH SANDBAGS.
- 14. BEFORE ACCEPTANCE BY THE VILLAGE, ALL WORK SHALL BE INSPECTED AND APPROVED BY THE ENGINEER, THE DUPAGE COUNTY DIVISION OF TRANSPORTATION AND THE ILLINOIS DEPARTMENT OF TRANSPORTATION. FINAL PAYMENT WILL BE MADE ONLY AFTER ALL OF THE CONTRACTOR'S WORK HAS BEEN APPROVED AND ACCEPTED.
- 15. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF WESTMONT.
- 16. THE CONTRACTOR'S ATTENTION IS CALLED TO THE FACT THAT THE PRESERVATION OF EXISTING TREES IS UTMOST IMPORTANCE TO THE VILLAGE OF WESTMONT. ALL TREE PROTECTION, TREE REMOVAL, PRUNING AND ROOT PRUNING SHALL BE COMPLETED BEFORE CONSTRUCTION OPERATIONS COMMENCE IN ANY AREA. AT NO TIME SHALL THE CONTRACTOR PRUNE OR REMOVE ANY TREES UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER
- 17. TEMPORARY FENCE SHOULD BE ERECTED ALONG THE DRIP LINE OF EXISTING TREES TO REMAIN WITHIN THE LIMITS OF CONSTRUCTION. AFTER TREES ARE SAFELY FENCED NOTHING IS TO BE STORED, DRIVEN, OR DISTURBED INSIDE THE FENCE. REMOVE PROTECTIVE TEMPORARY FENCE ONLY AFTER ALL CONSTRUCTION WORK HAS BEEN COMPLETED.
- 18. TREE ROOT PRUNING IS TO BE USED ON EXISTING TREES TO PREVENT THE RIEPING UP OF ROOTS WHEN TRENCHING OR EXCAVATION IS WITHIN THE ROOT ZONE OF ADJACENT TREES TO REMAIN. SUPPLEMENTAL WATERING OF TREES SHOULD BEGIN IMMEDIATELY AFTER ROOT PRUNING OF THE TREES HAS

SECTION COUNTY - 08-00098-00-SW DU PAGE FEDERAL RD. DIST. NO. | ILLINOIS | FEDERAL AID PROJECT

CONTRACT: 63132 no. date by ckd description

OCTOBER 29, 2008 M. BERENA

D. CHAVEZ A. BRYANT

63132



VILLAGE OF WESTMONT LEGEND, GENERAL NOTES, EARTHWORK SUMMARY AND SUMMARY OF QUANTITIES

48924

G002

sheet 2 of 12 file 002 LGND NOTES.DWG