## TREE REPLACEMENT SCHEDULE

CODE NUMBER	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY	
A2001714	ACER SACCHARUM	SUGAR MAPLE	1-3/4 INCH **	EACH	3	
		·				
			:			
	AND					

\*\* 1-3/4 INCHES CALIPER BALLED AND BURLAPPED ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

REVISED - 8-10-05

GENERAL NOTES:

1. LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE TECHNICIAN.
2. MULCH SHALL BE HARDWOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC.

## TREE REPLACEMENT SCHEDULE

90.4

REVISED -		F.A.I RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
REVISED -	REGION 2 / DISTRICT 2 STANDARD		(141-1)M-1	OGLE	82	52
REVISED -				CONTRAC	NO. 6	4E60
REVISED -	SCALE: 50.0000 / IN SHEET NO. 52 OF 82 SHEETS STA. TO STA.	FFD. ROA	AD DIST. NO. ILLINOIS FED. AT	D PROJECT		