CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - URBAN MULTILANE 10% STATE 90% FED X081-2A
20400800	FURNISHED EXCAVATION	CU YD	62.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	276.0
20800150	TRENCH BACKFILL	CU YD	14.0
25000200	SEEDING, CLASS 2	ACRE	0.25
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23.0
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23.0
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23.0
*25100630	EROSION CONTROL BLANKET	SQ YD	1,210.0
*28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25.00
*28000400	PERIMETER EROSION BARRIER	FOOT	705.0
28100125	STONE RIPRAP, CLASS B3	SQ YD	2.0
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	95.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	96.0
40600990	TEMPORARY RAMP	SQ YD	214.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	39.0
42001300	PROTECTIVE COAT	SQ YD	552.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	552.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	184.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	661.0
44000700	APPROACH SLAB REMOVAL	SQ YD	427.0
44004000	PAVED DITCH REMOVAL	FOOT	30.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	276.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	26.0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2.0
50102400	CONCRETE REMOVAL	CU YD	132.0
50104650	SLOPE WALL REMOVAL	SQ YD	4.0
50105220	PIPE CULVERT REMOVAL	FOOT	83.0
50200100	STRUCTURE EXCAVATION	CU YD	356.0
50300225	CONCRETE STRUCTURES	CU YD	96.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	543.0
50300260	BRIDGE DECK GROOVING	SQ YD	1,352.0
50300300	PROTECTIVE COAT	SQ YD	1,958.0
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	1,871.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	132,700.0
50800515	BAR SPLICERS	EACH	1,330.0
51100300	SLOPE WALL 6 INCH	SQ YD	4.0
51500100	NAME PLATES	EACH	2.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	48.0
52100520	ANCHOR BOLTS, 1"	EACH	96.0
52100540	ANCHOR BOLTS, 1 1/2"	EACH	8.0

*SPECIALTY ITEM

**SFTY 3N

CODE NO	ITEM	UNIT	TOTAL QUANTITY FAI - URBAN MULTILANE 10% STATE 90% FED X081-2A
54215547	METAL END SECTIONS 12"	EACH	2.0
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	156.0
59000200	EPOXY CRACK INJECTION	FOOT	79.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	137.0
60100945	PIPE DRAINS 12"	FOOT	165.0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	269.0
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1.0
60262700	INLETS TO BE RECONSTRUCTED	EACH	1.0
60600305	CONCRETE CURB (DOWELLED)	FOOT	40.0
60900515	CONCRETE THRUST BLOCKS	EACH	2.0
61000120	TYPE E INLET BOX, STANDARD 610001 (SPECIAL)	EACH	2.0
61000230	TYPE F INLET BOX, STANDARD 610001 (SPECIAL)	EACH	2.0
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	687.5
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2.0
63200310	GUARDRAIL REMOVAL	FOOT	868.0
64200105	SHOULDER RUMBLE STRIP	FOOT	298.0
66500105	WOVEN WIRE FENCE, 4'	FOOT	100.0
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	100.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7.0
67100100	MOBILIZATION	L SUM	1.0
70100207	TRAFFIC CONTROL AND PROTECTION,STANDARD 701402	EACH	2.0
70100700	TRAFFIC CONTROL AND PROTECTION,STANDARD 701406	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	305.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,915.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,871.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,000.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	950.0
*78000200	THERMOPLASTIC PAVEMENT MARKING- LINE 4"	FOOT	1,513.0
*78003130	PREFORMED PLASTIC PAVEMENT MARKING,TYPE B - LINE 6"	FOOT	412.0
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	990.0
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6.0
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12.0
*78200405	GUARDRAIL MARKERS	EACH	16.0
*78200500	BARRIER WALL MARKERS	EACH	16.0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	609.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18.0
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	227.0