

PAVEMENT MARKING ITEMS

LOCATION					PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING LINE-4"	PREFORMED PAVEMENT MARKING LINE-4"	EPOXY PAVEMENT MARKING LINE-4"	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING LINE - 4"
STAGE	O/S	STA TO STA	DESCPT	COLOR	SQ FT	FOOT	FOOT	FOOT	FOOT	
I&II	RT	771+78.3 782+28.3	CL SKIP DASH	WHITE	86.6		207.5	55.0	105.0	262.5
I&II	LT	779+00.0 789+37.4	CL SKIP DASH	WHITE	85.6		204.5	55.0	103.7	259.5
I	RT	776+78.3 779+38.5	DL EOP	WHITE	85.9	260.2			10.4	260.2
I	RT	779+38.5 781+58.4	DL EOP	WHITE				219.9	8.8	219.9
I	RT	781+58.4 783+77.2	DL EOP	WHITE	72.2	218.8			8.8	218.8
I	LT	777+38.1 779+38.5	DL EOP	WHITE	66.1	200.4			8.0	200.4
I	LT	779+38.5 781+58.4	DL EOP	WHITE				219.9	8.8	219.9
I	LT	781+58.4 784+37.3	DL EOP	WHITE	92.0	278.9			11.2	278.9
II	RT	777+83.9 779+00.0	PL EOP	YELLOW	38.3	116.1			4.6	116.1
II	RT	779+00.0 779+38.5	PL EOP	YELLOW		38.5			1.5	38.5
II	RT	779+38.5 781+58.4	PL EOP	YELLOW				219.9	8.8	219.9
II	RT	781+58.4 782+28.4	PL EOP	YELLOW		70.0			2.8	70.0
II	RT	782+28.4 782+93.4	PL EOP	YELLOW	21.5	65.0			2.6	65.0
II	LT	778+35.0 779+00.0	PL EOP	YELLOW	21.5	65.0			2.6	65.0
II	LT	779+00.0 779+38.5	PL EOP	YELLOW		38.5			1.5	38.5
II	LT	779+38.5 781+58.4	PL EOP	YELLOW				219.9	8.8	219.9
II	LT	781+58.4 782+00.0	PL EOP	YELLOW		41.6			1.7	41.6
II	LT	782+00.0 783+19.1	PL EOP	YELLOW	39.3	119.1			4.8	119.1
TOTAL					609.0	1512.1	412.0	989.6	304.4	2913.7
USE					609.0	1513.0	412.0	990.0	305.0	2915.0

TEMPORARY CONCRETE BARRIER

LOCATION				TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
O/S	STA	O/S	STA	FOOT	FOOT
STAGE I					
RT	777+22.3	RT	779+00.0	177.70	
RT	779+00.0	RT	782+28.3	328.30	
LT	779+00.0	LT	782+16.9	316.90	
LT	782+16.9	LT	783+93.5	176.60	
STAGE II					
RT	777+47.5	RT	778+99.1		151.60
RT	778+99.1	RT	782+28.4		329.30
LT	779+00.0	LT	782+04.0		304.00
LT	782+04.0	LT	783+67.9		163.90
ACTUAL TOTAL				999.5	948.8
USE TOTAL				1000.0	950.0

IMPACT ATTENUATORS

STATION	IMPACT ATTENUATORS TEMPORARY, NON-REDIRECTIVE, TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE, NON-REDIRECTIVE, TEST LEVEL 3
	EACH	EACH
LT 783+93.5	1.0	
RT 777+22.3	1.0	
LT 783+67.9		1.0
RT 777+47.5		1.0
ACTUAL TOTAL	2.0	2.0
USE TOTAL	2.0	2.0

WORK ZONE PAVEMENT MARKING REMOVAL

REMOVAL OF TEMPORARY & SHORT TERM PAVEMENT MARKINGS							
O/S	STATION	O/S	STATION	# LINES	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)
STAGE I							
RT	761+78.3	RT	771+78.3	1	1000.0	0.33	330.0
RT	771+78.3	RT	776+78.3	1	500.0	0.33	165.0
RT	776+78.3	RT	778+48.9	2	170.6	0.33	56.3
RT	778+48.9	RT	782+28.3	2	379.4	0.33	125.2
RT	782+28.3	RT	783+77.2	1	148.9	0.33	49.1
LT	777+38.1	LT	779+00.0	1	161.9	0.33	53.4
LT	779+00.0	LT	782+66.8	2	366.8	0.33	121.0
LT	782+66.8	LT	784+37.3	2	170.5	0.33	56.3
LT	784+37.3	LT	789+37.3	1	500.0	0.33	165.0
LT	789+37.3	LT	799+37.3	1	1000.0	0.33	330.0
STAGE II							
RT	762+83.9	RT	772+83.9	1	1000.0	0.33	330.0
RT	772+83.9	RT	777+83.9	1	500.0	0.33	165.0
RT	777+83.9	RT	778+48.9	2	65.0	0.33	21.5
RT	778+48.9	RT	782+28.4	2	379.5	0.33	125.2
RT	782+28.4	RT	782+93.4	1	65.0	0.33	21.5
LT	778+35.0	LT	779+00.0	1	65.0	0.33	21.5
LT	779+00.0	LT	782+54.1	2	354.1	0.33	116.9
LT	782+54.1	LT	783+19.1	2	65.0	0.33	21.5
LT	783+19.1	LT	788+19.1	1	500.0	0.33	165.0
LT	788+19.1	LT	798+19.1	1	1000.0	0.33	330.0

TEMP. PAVT MKG REMOVAL SUBTOTAL 2769.3  
 SHORT TERM MKG REMOVAL SUBTOTAL 101.7  
 TOTAL 2871.0  
 USE 2871.0