SCHEDULE OF QUANTITIES

78005110 EPOXY PAVEMENT MARKING - LINE 4 INCH

LENGTH LOCATION DESCRIPTION (FT)

DRIVING LANE EOP WHITE SOLID 1295.0
TRAVELED WAY CL WHITE SKIP DASH 325.0

TOTAL = 1620.0

78005140 EPOXY PAVEMENT MARKING - LINE 8 INCH

LENGTH

<u>LOCATION</u> <u>DESCRIPTION</u> <u>(FT)</u>

RAMP TERMINALS WHITE SOLID 335.0

<u>TOTAL = 335.0</u>

FILE NAME =	USER NAME = blackrt	DESIGNED -	REVISED -	
c:\pw_work\PWIDOT\BLACKRT\dms84829\D57	739-SHT-SCHEDULE.dgn	DRAWN - JJB	REVISED -	ST.
	PLOT SCALE = 40.0448 '/ IN.	CHECKED -	REVISED -	DEPARTME
	PLOT DATE = 3/23/2009	DATE -	REVISED -	

STATE OF ILLINOIS						
DEPARTMENT O	F TRANSPORTATION					

				F.A.I RTE.	SEC	TION	COUNTY	TOTAL SHEETS	SHEET NO.	
				39	39 D5 PATCHING		MCLEAN	25	18	
								CONTRAC	T NO.	70739
	SCALE: NA	SHEET NO. 6 OF 6 SHEETS	STA.	TO STA.	FED. R	DAD DIST. NO.	ILLINOIS FED.	. AID PROJECT		