



STAGE I REMOVAL (Looking North)




STAGE I CONSTRUCTION

(Looking North)



STAGE II REMOVAL

(Looking North)



MAURER & STUTZ, INC. J ENGINEERS SURVEYORS

STAGE II CONSTRUCTION (Looking North)

DESIGNED - BAS

CHECKED - KEF

DRAWN - LAD

CHECKED - RJA / KEF

STAGING NOTES:

- 1. Hatched areas indicate "Removal of Existing Structures".
- 2. For quantities of "Temporary Concrete Barrier", see Roadway Plans.


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Contract # 74233

If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.

The Contractor shall connect the first sheet to the existing abutment wall to ensure stability of sheets driven to the top of the existing footing. This connection shall be reviewed and accepted by the Engineer and included in the cost for Temporary Sheet Piling.

The minimum section modulus for cantilever sheet piling shall be 12 in.3/ft.




BILL OF MATERIAL

Item	Unit	Quantity
Temporary Sheet Piling	Sq. Ft.	1015

TEMPORARY SHEET PILING

(South Abutment)



TEMPORARY SHEET PILING
(North Abutment)

IL ROUTE 128 OVER
ROBINSON CREEK TRIBUTARY
F.A.P. RTE. 770 - SECTION (115BR)B-1
SHELBY COUNTY
STATION 408+75.45

STRUCTURE NO. 087-0031