

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION




BAR SPLICER ASSEMBLY ALTERNATIVES


**Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.



FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS


Bar Splicer for #5 bar
Min. Capacity = 23.0 kips - tension
Min. Pull-out Strength = 12.3 kips - tension
No. Required = 68





INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



Bar Splicer for #5 bar Min. Capacity = 23.0 kips - tension Min. Pull-out Strength = 12.3 kips - tension No. Required = 0

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:


Minimum Capacity (Tension in kips) = 1.25 x fy x A_t

(Tension in Kips)
Minimum *Pull-out Strength = 0.66 x fy x A_t (Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksi.

 A_t = Tensile stress area of lapped reinforcement bars. * = 28 day concrete

	BAR SPLIC	ER ASSEMBLI	ES		
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Strength Requirements			
		Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension		
#4	1'-8''	14.7	7.9		
#5	2'-2"	23.0	12.3		
#6	2'-7"	33.1	17.4		
#7	3′-5′′	45.1	<i>23.8</i>		
#8	4'-6''	58.9	31.3		
#9	5′-9″	75.0	39.6		
#10	7'-3''	95.0	50 . 3		
#11	9'-0''	117.4	61.8		



STANDARD

Bar Size	No. Assemblies Required	Location				
#5	345	Slab				
#6	16	Slab				
#7	10	N. Abut.				
#7	10	S. Abut.				
#5	26	Pier 1				
#5**	48	Pier 1				
#7	10	Pier 1				
#5	26	Pier 2				
#5**	48	Pier 2				
#7	10	Pier 2				

** Mechanical Splice

BAR SPLICER ASSEMBLY DETAILS IL ROUTE 242 OVER SHELTON CREEK STATION 470+76

SHEET NO.24	F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.	
01,221 110.21	776		(102)B-1		HAMILTON	53	51
26 SHEETS		S.N. 033-0053		CONTRACT	NO. 78	016	
	FED. RC	DAD DIST. NO.	ILLINOIS	FED. AI	D PROJECT		

JACOBS