

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 495	95-00215-01-RS	PIATT	21	15
FED. ROAD DIST. NO.	ILLINOIS		FED. AID PROJECT	

CONTRACT NO. 91383

DITCH ELEVATION TABULATION						
LOC.	STATION	ELEVATION	LOC.	STATION	ELEVATION	FOOT
RT. STA.	265+87.12	STD DITCH	TO RT. STA.	272+77.00	STD DITCH	690
LT. STA.	265+87.12	STD DITCH	TO LT. STA.	272+77.00	STD DITCH	690
RT. STA.	3+34.50	STD DITCH	TO RT. STA.	9+00.00	STD DITCH	566
LT. STA.	3+34.50	STD DITCH	TO LT. STA.	12+00.00	STD DITCH	866
RT. STA.	9+00.00	742.30	TO RT. STA.	17+00.00	739.90	800
LT. STA.	12+00.00	739.82	TO LT. STA.	16+45.00	728.00	445
LT. STA.	16+45.00	728.00	TO LT. STA.	20+00.00	745.38	355
RT. STA.	17+00.00	739.90	TO RT. STA.	20+00.00	745.38	300
RT. STA.	20+00.00	STD DITCH	TO RT. STA.	28+00.00	STD DITCH	800
LT. STA.	20+00.00	STD DITCH	TO LT. STA.	28+00.00	STD DITCH	800
RT. STA.	28+00.00	750.44	TO RT. STA.	29+00.00	750.03	100
LT. STA.	28+00.00	750.44	TO LT. STA.	29+00.00	749.03	100
RT. STA.	29+00.00	750.03	TO RT. STA.	30+00.00	749.33	100
LT. STA.	29+00.00	749.03	TO LT. STA.	30+00.00	748.83	100
LT. STA.	30+00.00	748.83	TO LT. STA.	35+90.00	747.65	590
RT. STA.	30+00.00	749.33	TO RT. STA.	35+90.00	748.15	590
RT. STA.	35+90.00	748.15	TO RT. STA.	37+00.00	749.31	110
LT. STA.	35+90.00	747.65	TO LT. STA.	37+00.00	748.33	110
RT. STA.	37+00.00	STD DITCH	TO RT. STA.	47+68.00	STD DITCH	1068
LT. STA.	37+00.00	748.33	TO LT. STA.	39+00.00	750.75	200
LT. STA.	39+00.00	750.75	TO LT. STA.	44+00.00	760.40	500
LT. STA.	44+00.00	760.40	TO LT. STA.	47+68.00	766.33	368
RT. STA.	48+56.00	765.19	TO RT. STA.	51+80.00	763	324
LT. STA.	48+56.00	766.19	TO LT. STA.	52+00.00	759.5	344
RT. STA.	51+80.00	763	TO RT. STA.	53+00.00	763.76	120
LT. STA.	52+00.00	759.5	TO LT. STA.	53+00.00	760.46	100
RT. STA.	53+00.00	763.76	TO RT. STA.	55+00.00	766.42	200
LT. STA.	53+00.00	760.46	TO LT. STA.	55+00.00	766.42	200
RT. STA.	55+00.00	766.42	TO RT. STA.	58+66.00	763.71	366
LT. STA.	55+00.00	766.42	TO LT. STA.	58+00.00	763.12	300
LT. STA.	58+00.00	763.12	TO LT. STA.	58+66.00	762.71	66
LT. STA.	59+00.00	STD DITCH	TO LT. STA.	61+00.00	STD DITCH	200
RT. STA.	59+00.00	764.76	TO RT. STA.	60+00.00	764.3	100
RT. STA.	60+00.00	764.3	TO RT. STA.	67+71.00	761.28	771
LT. STA.	61+00.00	763.12	TO LT. STA.	67+52.00	760.75	652
LT. STA.	67+52.00	760.75	TO LT. STA.	68+00.00	761.18	48
LT. STA.	68+00.00	761.18	TO LT. STA.	72+50.00	765	450
RT. STA.	67+71.00	761.28	TO RT. STA.	74+00.00	768.01	629
LT. STA.	75+00.00	767.1	TO LT. STA.	76+00.00	762	100
LT. STA.	76+00.00	762	TO LT. STA.	77+00.00	760.5	100
LT. STA.	77+00.00	760.5	TO LT. STA.	78+00.00	760	100
LT. STA.	78+00.00	760	TO LT. STA.	78+60.00	759.5	60
RT. STA.	78+60.00	759.6	TO RT. STA.	79+00.00	759.87	40
LT. STA.	78+60.00	759.5	TO LT. STA.	81+00.00	761.25	240
RT. STA.	79+00.00	759.87	TO RT. STA.	85+00.00	764.91	600
LT. STA.	81+00.00	761.25	TO LT. STA.	85+00.00	764.91	400
RT. STA.	85+00.00	STD DITCH	TO RT. STA.	90+00.00	STD DITCH	500
LT. STA.	85+00.00	STD DITCH	TO LT. STA.	90+00.00	STD DITCH	500
RT. STA.	90+00.00	770.7	TO RT. STA.	94+00.00	777.02	400
LT. STA.	90+00.00	770.7	TO LT. STA.	94+00.00	777.02	400
RT. STA.	94+00.00	777.02	TO RT. STA.	96+00.00	782.66	200
LT. STA.	94+00.00	777.02	TO LT. STA.	96+00.00	782.66	200
RT. STA.	96+00.00	STD DITCH	TO RT. STA.	101+00.00	STD DITCH	500
LT. STA.	96+00.00	STD DITCH	TO LT. STA.	101+00.00	STD DITCH	500
RT. STA.	101+00.00	788	TO RT. STA.	105+00.00	785.92	400
LT. STA.	101+00.00	788	TO LT. STA.	102+00.00	786.5	100
LT. STA.	102+00.00	786.5	TO LT. STA.	105+50.00	783	350
RT. STA.	105+00.00	785.92	TO RT. STA.	106+18.00	785.5	118
LT. STA.	105+50.00	783	TO LT. STA.	106+18.00	780	68
RT. STA.	106+18.00	785.5	TO RT. STA.	109+00.00	787.46	282
LT. STA.	106+18.00	780	TO LT. STA.	107+00.00	782.1	82
LT. STA.	107+00.00	782.1	TO LT. STA.	109+00.00	787.46	200
RT. STA.	109+00.00	STD DITCH	TO RT. STA.	116+00.00	STD DITCH	700
LT. STA.	109+00.00	787.46	TO LT. STA.	112+00.00	782.27	300
LT. STA.	112+00.00	782.27	TO LT. STA.	116+00.00	778	400
LT. STA.	116+00.00	778	TO LT. STA.	117+50.00	775.75	150
RT. STA.	116+00.00	779	TO RT. STA.	117+50.00	777.75	150
LT. STA.	117+50.00	775.75	TO LT. STA.	118+00.00	776.52	50
RT. STA.	117+50.00	777.75	TO RT. STA.	118+00.00	778	50

DITCH ELEVATION TABULATION						
LOC.	STATION	ELEVATION	LOC.	STATION	ELEVATION	FOOT
RT. STA.	118+00.00	778	TO RT. STA.	119+00.00	778.76	100
LT. STA.	118+00.00	776.52	TO LT. STA.	120+00.00	780.6	200
RT. STA.	119+00.00	778.76	TO RT. STA.	120+00.00	780.6	100
RT. STA.	120+00.00	STD DITCH	TO RT. STA.	126+00.00	STD DITCH	600
LT. STA.	120+00.00	STD DITCH	TO LT. STA.	129+00.00	STD DITCH	900
RT. STA.	126+00.00	790.58	TO RT. STA.	127+38.00	792.73	138
RT. STA.	127+38.00	792.73	TO RT. STA.	133+46.00	789.69	608
LT. STA.	131+00.00	STD DITCH	TO LT. STA.	132+50.00	STD DITCH	150
RT. STA.	133+46.00	789.69	TO RT. STA.	137+00.00	793.97	354
LT. STA.	133+46.00	788.7	TO LT. STA.	134+50.00	788.97	104
LT. STA.	134+50.00	788.97	TO LT. STA.	137+00.00	793.97	250
RT. STA.	137+00.00	STD DITCH	TO RT. STA.	148+30.00	STD DITCH	1130
LT. STA.	137+00.00	793.97	TO LT. STA.	143+00.00	797.75	600
LT. STA.	143+00.00	797.75	TO LT. STA.	146+15.00	800.96	315
LT. STA.	146+15.00	800.96	TO LT. STA.	148+30.00	800.1	215
LT. STA.	148+30.00	800.1	TO LT. STA.	150+00.00	800.68	170
RT. STA.	148+30.00	800.9	TO RT. STA.	150+00.00	801.24	170
LT. STA.	150+00.00	800.68	TO LT. STA.	153+84.00	802	384
RT. STA.	150+00.00	801.24	TO RT. STA.	153+84.00	802	384
RT. STA.	154+00.00	STD DITCH	TO RT. STA.	158+00.00	STD DITCH	400
LT. STA.	154+00.00	STD DITCH	TO LT. STA.	158+00.00	STD DITCH	400
LT. STA.	158+00.00	800.99	TO LT. STA.	161+29.00	796.8	329
RT. STA.	158+00.00	800.99	TO RT. STA.	161+29.00	797.7	329
LT. STA.	161+29.00	796.8	TO LT. STA.	162+00.00	796.99	71
RT. STA.	161+29.00	797.7	TO RT. STA.	162+00.00	797.99	71
LT. STA.	162+00.00	796.99	TO LT. STA.	163+00.00	799.99	100
RT. STA.	162+00.00	797.99	TO RT. STA.	163+00.00	799.99	100
RT. STA.	163+00.00	STD DITCH	TO RT. STA.	168+00.00	STD DITCH	500
LT. STA.	163+00.00	STD DITCH	TO LT. STA.	170+00.00	STD DITCH	700
RT. STA.	168+00.00	796.51	TO RT. STA.	169+00.00	796	100
RT. STA.	169+00.00	796	TO RT. STA.	173+00.00	788	400
LT. STA.	170+00.00	793.83	TO LT. STA.	172+50.00	788.43	250
LT. STA.	172+50.00	788.43	TO LT. STA.	178+00.00	781.89	550
RT. STA.	173+00.00	788	TO RT. STA.	175+00.00	786.88	200
RT. STA.	175+00.00	STD DITCH	TO RT. STA.	177+00.00	STD DITCH	200
RT. STA.	177+00.00	784.64	TO RT. STA.	179+33.00	780	233
LT. STA.	178+00.00	781.89	TO LT. STA.	179+33.00	780.8	133
RT. STA.	179+33.00	780	TO RT. STA.	180+00.00	780.38	67
LT. STA.	179+33.00	780.8	TO LT. STA.	180+00.00	781.01	67
RT. STA.	180+00.00	780.38	TO RT. STA.	182+00.00	781.5	200
LT. STA.	180+00.00	781.01	TO LT. STA.	184+00.00	785.22	400
RT. STA.	182+00.00	781.5	TO RT. STA.	184+00.00	785.22	200
LT. STA.	184+00.00	STD DITCH	TO LT. STA.	195+00.00	STD DITCH	1100
RT. STA.	184+00.00	STD DITCH	TO RT. STA.	198+00.00	STD DITCH	1400
LT. STA.	195+00.00	777.15	TO LT. STA.	202+60.00	775.24	760
RT. STA.	198+00.00	774.66	TO RT. STA.	202+60.00	771.5	460
LT. STA.	202+60.00	775.24	TO LT. STA.	205+00.00	777	240
RT. STA.	202+60.00	771.5	TO RT. STA.	203+00.00	772.12	40
RT. STA.	203+00.00	772.12	TO RT. STA.	204+00.00	773.5	100
RT. STA.	204+00.00	773.5	TO RT. STA.	206+65.00	779.7	265
LT. STA.	205+00.00	777	TO LT. STA.	206+49.00	780.5	149
					TOTAL	40744

**HAMPTON, LENZINI & RENWICK, INC.**  
 CIVIL & STRUCTURAL ENGINEERS

**HLR**

3085 STEVENSON DRIVE, SUITE 201  
 SPRINGFIELD, ILLINOIS 62703  
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 03-75-0007-1      DATE: 02/11/08  
 DESIGNED: L.P.S.      CHECKED: S.W.M.      DRAWN: TWK

**SPECIAL DITCH TABULATION**

**SECTION 95-00215-01-RS**

**FAS 495 C.H. 2**

**PIATT COUNTY**