

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	23	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\* (12-3)RS-2,(4-5)RS-3

RESURFACING SCHEDULE

LOCATION	STATION TO STATION		LENGTH	ROADWAY WIDTH	ROADWAY AREA	HOT-MIX ASP. SURF. REM. 2 1/4"	TEMPORARY RAMP	POLY. HOT-MIX ASP. SUR. CSE., MIX E, N 105	POLY. LEVEL. BINDER (MM) N105	POLY. BIT. MAT. (PRIME COAT)	AGG. (PRIME COAT)	NOTES	
			FOR INFORMATIONAL PURPOSE ONLY			(SQ YD)	(SQ YD)	(TON)	(TON)	(GAL)	(TON)		
			(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(GAL)	(TON)		
<b>MAINLINE - STA. 100+37 TO STA. 127+69.67 (INLAY)</b>													
	100+37.00	TO	127+69.67	2732.7	34.0	10323.4	10323	19	867	434	1858.2	31.0	
	127+69.67	TO	134+52.00	682.3	40.0	3032.6	3033		255	127	545.9	9.1	
	134+52.00		RR Xing					22					
	<b>134+52.00</b>	<b>TO</b>	<b>134+91.00</b>										
<b>RAILROAD OMISSION STA. 132+82 TO STA. 136+72</b>													
	134+91.00		RR Xing					22					
	134+91.00	TO	156+48.00	2157.0	40.0	9586.7	9587		805	403	1725.6	28.8	
	156+48.00	TO	181+00.00	2452.0	36.0	9808.0	9808		824	412	1765.4	29.4	
RT	1740+37	TO	1780+50	413.0	0' to 16'	506.0	506	9	43	21	182.2	1.6	Old IL 13 Conn.
	181+00.00	TO	182+66.00	166.0	36 - 48	775.0	775		65	33	139.6	2.4	Includes LTL
	182+66.00	TO	184+65.00	199.0	48.0	1061.3	1061	27	89	45	191.0	3.2	Includes LTL
<b>SUB-TOTALS</b>							<b>35093</b>	<b>99</b>	<b>2948</b>	<b>1474</b>	<b>6408</b>	<b>105</b>	
<b>PARKING LANES WITH BOULEVARD EXTENSIONS OMITTED</b>													
LT	100+74.00	TO	102+78.00	204.0	6.0	139	139		12	6	12.5	0.2	
LT	103+32.00	TO	106+60.00	328.0	6.0	223	223		19	9	20.1	0.3	
LT	107+43.00	TO	108+65.00	122.0	6.0	120	120		10	5	10.8	0.2	
LT	110+03.00	TO	111+77.00	174.0	6.0	120	120		10	5	10.8	0.2	
LT	113+17.00	TO	116+74.00	357.0	6.0	242	242		20	10	21.8	0.4	
LT	117+84.00	TO	127+27.00	943.0	6.0	631	631		53	27	56.8	0.9	
<b>SUB-TOTALS</b>							<b>1475</b>	<b>0</b>	<b>124</b>	<b>62</b>	<b>133</b>	<b>2</b>	
<b>PROJECT TOTALS</b>							<b>36568</b>	<b>99</b>	<b>3072</b>	<b>1536</b>	<b>6541</b>	<b>108</b>	

SIDE ROAD RESURFACING SCHEDULE

NAME	STATION	SURFACE TYPE	WIDTH AT EDGE OF PAVEMENT	DISTANCE TO END OF SURFACING	WIDTH AT END OF SURFACING	SURFACE AREA	TEMP RAMP	POLY BIT MATERIAL (PR CT)	AGGREGATE (PR CT)	INCIDENTAL HMA SURFACE
			(FT)	(FT)	(FT)	(SQ YD)	(SQ YD)	(GAL)	(TON)	(TON)
<b>FAP 331 (IL. 13/WALNUT ST.)</b>										
University Ave.	Lt. 127+69+67	b1+	74	17.5	34	87	31	7.8	0.13	11
University Ave.	Rt. 127+69+67	b1+	80				44			
Illinois Ave.	Lt. 132+41	b1+	62				34			
Illinois Ave.	Rt. 132+41	b1+	80	67	33	284	19	25.6	0.43	36
<b>TOTALS</b>							<b>128</b>	<b>33</b>	<b>0.56</b>	<b>47</b>

PLOT DATE = 12/14/2008  
 FILE NAME = n:\pavement\resurfacing\mccordr\mccordr\_13846\_v09r4496.plt  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = mccordr