STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PLANS FOR PROPOSED FEDERAL AID HIGHWAY

FAU RTE 1569 (73rd STREET)
CENTRAL AVENUE TO CICERO AVENUE (IL-50)
ROADWAY RESURFACING
SECTION No. 14-00037-00-RS
PROJECT No. M-4003(376)
JOB No. C-91-419-14
VILLAGE OF BEDFORD PARK
COOK COUNTY

THIS PROJECT IS LOCATED IN THE VILLAGE OF BEDFORD PARK


INDEX TO SHEETS: SEE SHEET 2
HIGHWAY STANDARDS: SEE SHEET 2

ADT = 13,500

SPEED LIMIT = 30 MPH

DESIGN SPEED = 35 MPH


DESIGN DESIGNATION - MAJOR COLLECTOR



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED

J.U.L.I.E.
JOINT UTILITY LOCATION FOR EXCAVATION
1-800-892-0123 -OR- 811

CONTRACT NO. 61B26



LOCATION MAP

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

APPROVED

APPROVE

SECTION

14-00037-00-RS

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

STA. 10+00 TO STA. 63+44.31

CONTRACT NO. 61B26

1569

SHEETS

20

COOK

NO.

GROSS LENGTH OF PROJECT: 5,344 FEET (1.01 MILES)
NET LENGTH OF PROJECT: 5,330 FEET (1.01 MILES)

hbe Hoefferle-Butler Engineering, Inc.

PROFESSIONAL DESIGN FIRM LICENSE NO. 184-000819 8714 S. ROBERTS ROAD HICKORY HILLS, ILLINOIS 60457 (708) 599-8980 FAX (708) 599-8790 PRINTED BY AUTHORITY OF THE STATE OF ILLINOIS

OGRAM AND OFFICE ENGINEER: CHARLES F. RIDDLE, P.E. 1-8

EXPIRES 11-30-15

IOIS 8

INDEX TO SHEETS:

SHEET NO. DESCRIPTION COVER SHEET GENERAL NOTES SUMMARY OF QUANTITIES TYPICAL SECTIONS, STRUCTURAL DESIGN INFORMATION, HOT-MIX ASPHALT MIXTURE PLAN AND PROFILE SHEETS STRUCTURE REPAIR SCHEDULE, DETECTOR LOOP PLAN 5-13.

15. PAVEMENT MARKING PLAN

DISTRICT 1 DETAIL-TC10-TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, 16. INTERSECTIONS, AND DRIVEWAYS

DISTRICT 1 DETAIL-TC13-TYPICAL PAVEMENT MARKINGS DISTRICT 1 DETAIL-BD24-CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

19. DISTRICT 1 DETAIL-BD32-BUTT JOINT AND HMA TAPER DETAIL

20. DISTRICT 1 DETAIL-TS07-DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY

RESURFACING

PAVEMENT FABRIC

HIGHWAY STANDARDS:

420701-02:

STANDARD	NO.	DESCRIPTION

STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS 000001-06 PERPENDICULAR CURB RAMPS FOR SIDEWALKS 424001-08: CLASS B PATCHES 602011-02: CATCH BASIN TYPE C 602301-04: INLET TYPE A FRAMES AND LIDS TYPE 1 604001-04: 606001-06 CONCRETE CURB, TYPE B AND COMBINATION CURB AND GUTTER URBAN SINGLE LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN 701606-10: 701901-03: TRAFFIC CONTROL DEVICES 780001-05. TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

PAVING

THE THICKNESS OF HMA SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR OR IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH

PAVEMENT GRADES SHOWN ON PLANS ARE TOP OF PAVEMENT

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS HMA LIFTS.

UTILITIES

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE OWNER OF ALL EXISTING FACILITIES SO THAT THE UTILITIES AND THEIR APPURTENANCES MAY BE LOCATED AND ADJUSTED OR MOVED, IF NECESSARY, PRIOR TO THE START OF CONSTRUCTION OPERATIONS. THE CONTRACTORS SHALL COOPERATE WITH ALL UTILITY OWNERS AS PROVIDED FOR IN THE STANDARD SPECIFICATIONS.

THE LOCATIONS OF EXISTING DRAINAGE STRUCTURES, STORM AND SANITARY SEWERS, WATER SERVICE LINES AND OTHER UTILITY LINES ARE APPROXIMATE, AND THE VILLAGE DOES NOT GUARANTEE THEIR ACCURACY, THEIR EXACT HORIZONTAL AND VERTICAL LOCATIONS ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR AT HIS OWN

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER OR THE VILLAGE. THIS WORK SHALL BE AT THE CONTRACTORS EXPENSE

COORDINATION OF ALL UTILITY WORK INVOLVED IN THE CONSTRUCTION AREA WILL BE DISCUSSED AT THE PRECONSTRUCTION CONFERENCE.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, GAS AND CABLE TELEVISION FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)

CARE IS TO BE TAKEN AS NOT TO DAMAGE ANY OF THE EXISTING TRAFFIC SIGNAL CONDUITS, DETECTORS AND EQUIPMENT. IF ANY OF THE TRAFFIC SIGNAL CONDUIT AND/OR EQUIPMENT IS DAMAGED, THE CONTRACTOR SHALL REPAIR AND/OR REPLACE THE CONDUIT AND/OR EQUIPMENT AT NO COST TO THE COUNTY OR VILLAGE.

ANY EXISTING STORM SEWER DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS OR HER OWN EXPENSE

RESTORATION

CONTRACTOR IS TO RESTORE ALL UNPAVED AREAS DAMAGED DURING CONSTRUCTION OPERATIONS TO THEIR ORIGINAL CONDITION INCLUDING THE FINE GRADING AND SODDING OR SEEDING OF AREAS WITHIN EASEMENTS AND RIGHTS-OF-WAY.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR, CORY JUCIUS, AT 847-705-4470 PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

MISCELLANEOUS

ACCESS: THE CONTRACTOR SHALL PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING CONSTRUCTION.

DIMENSIONS: IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

ALL SAWCUTTING SHALL BE INCLUDED IN THE UNIT OF COST OF REMOVAL ITEMS AND SHALL BE PERFORMED PRIOR TO BEGINNING REMOVAL. ANY ITEMS OF WORK REMOVED PRIOR TO SAWCUTTING WILL NOT BE MEASURED FOR PAYMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SAND BAGS ON EACH TYPE I OR TYPE II BARRICADE USED. (ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.) TYPE III BARRICADES SHALL HAVE A MINIMUM OF FOUR SANDBAGS PER BARRICADE.

ANY EXISTING PAVEMENT OUTSIDE THE AREAS DESIGNATED FOR REMOVAL IN THE PLANS DAMAGED BY THE CONTRACTOR DURING THE CONSTRUCTION SHALL BE REPLACED/REPAIRED BY THE CONTRACTOR AT HIS/HERS OWN EXPENSE TO THE SATISFACTION OF THE ENGINEER WITH NO ADDITIONAL COMPENSATION TO THE CONTRACTOR.

STAKING

THE CONTRACTOR SHALL TAKE CARE TO PROTECT AND PRESERVE ALL STAKING AND MARKING DURING CONSTRUCTION. CONTINUOUS DESTRUCTION OF STAKES AS A RESULT OF CARELESSNESS MAY RESULT IN THE CONTRACTOR BEING BILLED FOR THE COST OF REPLACEMENT.

THE ENGINEER SHALL BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO THE COMMENCEMENT OF WORK. THEY SHALL BE NOTIFIED AT LEAST 72 HOURS IN ADVANCE IF CONSTRUCTION STAKING IS REQUIRED.

SCALE: N.T.S.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES

BITUMINOUS MAT PRIME COAT	.05	LBS/S.F.
HMA RESURFACING	112	LBS/S.YIN
FERTILIZER NUTRIENTS	90	LBS/ACRE
MIXTURE FOR CRACKS, JTS FLGWYS	.0003	TONS/S.Y.

MEMBERS OF "JULIE" KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

- 1. NICOR GAS
- 2. AT&T
- 3. COMMONWEALTH EDISON Co.
- 4. VILLAGE OF BEDFORD PARK

1		
prost nas	DRAWN BY: JMH	REVISED:
Mayorana a	CHECKED BY: SAL	REVISED:
radional	DATE: 12.01.14	REVISED:
	REVISED:	REVISED:

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

GEN	IERAL NOTES	FAU RTE	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
		1569	14-00037-00-	RS	COOK	20	2
					CONTRA	ACT No. 61	B26
	SHEET No. 2 OF 20 SHEETS	FED. ROAD	DIST. NO.	ILLINO	IS FED. A	AID PROJECT	E E


			CONSTRUCTION CO
			STP FUNDS
			80% FED
			20% LOCAL
			0005
			URBAN
			TOTAL
CODE NO.		UNIT	QTY.
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	46
Z0004562	COMBINATION CURB AND GUTTER REMOVAL AND		
20004002	REPLACEMENT	FOOT	1,269
	THE TANCEMENT	1001	1,200
Z0048 665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1.00
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	78
25000210	SEEDING CLASS 1A	ACRE	0.02
20000210	DEEDING GEAGG IA	AOIL	0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	12,036
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	8
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD),		
	N50	TON	1,100
40000000	HOT MIX ACRUMIT CUREAGE REMOVAL BUTT JOINT	00.40	100
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	109
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE,	-	
40000000	MIX "F", N90	TON	4,494
		1,011	1,101
42400410	PORTLAND CEMENT CONCRETE SIDEWALK, 8"	SQ FT	715
42400800	DETECTABLE WARNINGS	SQ FT	60
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	26,747
44000600	SIDEWALK REMOVAL	SQ FT	715
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	700
77200310	OLAGO D PATORES, TIPE II, 10 INOR	30 10	700
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	350

			CONSTRUCTION COL
			STP FUNDS
			80% FED
			20% LOCAL
		_	0005
		_	URBAN TOTAL
CODE NO.	ITEM	UNIT	QTY.
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	100
11200010	DEAGO BY ATOMES, THE IV, TO MON	00.10	100
44213100	PAVEMENT FABRIC	SQYD	450
44213200	SAW CUTS	FOOT	1,600
44213204	TIE BARS 3/4"	EACH	2,100
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	26,747
1 1000100	THE THE ELOTIVE ORGAN CONTROL TREATMENT	00.10	20,171
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	3
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	4
60500060	REMOVING INLETS	EACH	4
60500050	REMOVING CATCH BASINS	EACH	3
00000000	NEWOVING OATON BAGING	LACIT	
60255410	CATCH BASINS TO BE CLEANED	EACH	35
60255500	MANHOLES TO BE ADJUSTED	EACH	2
	WALVE WALK TO TO BE AD INCIDE		
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	8
67100100	MOBILIZATION	LSUM	1.00
07 100 100	IN OBJECTION		1.00
70102625	TRAFFIC CONTROL AND PROTECTION, STD. 701606	LSUM	1.00
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,700
70000100	THE DMODLASTIC DAVEMENT MADIZING LETTERS &	_	
78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS & SYMBOLS	SQ FT	311.8
	I I I I I I I I I I I I I I I I I I I	10011	511.0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,200
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	477
70000055	THE DWO DIA OTIO DAVENESTE MARKETON AND AND AND AND AND AND AND AND AND AN	F005	0.07
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	267
88600600	LOOP DETECTOR REPLACEMENT	FOOT	333
5555555	TOO. DETECTOR RELEASEMENT	1.001	1 333


O DENOTES SPECIAL PROVISION ITEM

* DENOTES SPECIALTY ITEM

DRAWN BY	BY: JMH R	REVISED:		SUMMARY	OF QUANTITIES	FAU RTE	SECTION	COUN	TOTAL SHEETS	SHEET NO.
CHECKED	BY: SAL R	REVISED:	STATE OF ILLINOIS			1569	14-00037-00-RS	COO	20	3
DATE:	12.01.14 R	REVISED:	DEPARTMENT OF TRANSPORTATION					co	NTRACT No.	61B26
REVISED:	R	REVISED:		SCALE: N.T.S.	SHEET No. 3 OF 20 SHEETS	FED. ROAD	DIST. NO. ILLI	NOIS FE	D. AID PROJE	ст



73rd STREET, STA 10+00-STA 63+44



PROPOSED TYPICAL CROSS—SECTION 73rd STREET, STA 10+00-STA 63+44

- 1 PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 3"
- 2 PROPOSED CURB & GUTTER REMOVAL
- 3 EXISTING HOT-MIX ASPHALT SURFACE & BINDER COURSES, ±5.5"
- 4 EXISTING CONCRETE BASE, ±8"
- (5) EXISTING COMBINATION CURB & GUTTER, TY B6.12
- 6 EXISTING HOT-MIX ASPHALT BINDER COURSE

- 7 PROPOSED COMBINATION CURB & GUTTER, TY B6.12 (WHERE MARKED)
- 8 PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50, 3/4" (MAX)
- 9 PROPOSED POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, 3"
- 10 PROPOSED AREA REFLECTIVE CRACK CONTROL TREATMENT
- (1) PROPOSED CLASS B PATCHES, 10"

STRUCTURAL DESIGN TRAFFIC: YEAR 2025

PV= 9,990

SU= 1,080

MU = 2,430

ROAD/STREET CLASSIFICATION: I

PERCENT OF STRUCTURAL DESIGN TRAFFIC IN DESIGN LANE:

P= 32 S= 45 M= 45

TRAFFIC FACTOR: ACTUAL T.F.= 16.64 SN_C= 4.6

PG GRADE: SURFACE= SBS/SBR PG 70-22 IBV= 3 SSR= FAIR

HOT-MIX ASPHALT MIXTURE REQUIREMENTS (CHART
MIXTURE TYPE	AIR VOIDS AT Ndes
PAVEMENT RESURFACING	
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'F', N90, 3"	4% AT 90 GYR
POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	4% AT 50 GYR

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN


THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 70-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS.


FOR "PERCENT OF RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.


Tarana and a same a		
New Inch	DRAWN BY: JMH	REVISED:
Augustiti P	CHECKED BY: SAL	REVISED:
i viverate	DATE: 12.01.14	REVISED:
	REVISED:	REVISED:


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


73	Brd STREET	FAU RTE	SECTION		COUNTY	TOTAL SHEETS	S
TYPICAL	CROSS-SECTIONS	1569	14-00037-00	D-RS	COOK	20	
HMA MIXTURE CH	ART, STRUCTURAL DESIGN				CONTR	RACT No. 6	1B26
SCALE: NOT TO SCALE	SHEET No. 4 OF 20 SHEETS	FED. ROA	D DIST. NO.	ILLIN	IOIS FED.	AID PROJEC	Т
























	T		T RESURFACING	REMOVE &	-	
TRUCTURE	STRUCTURE	PROPOSED	ADJUST	REPLACE		
No.	TYPE	RIM ELEV.	STRUCTURE	STRUCTURE	CLEAN	NOTES
1	CB, 4'-DIA	615.53	JINOCIONE	JIKOCIOKE	CLLAIN	NOTES
2	VALVE VAULT	615.79			X	
3	MH, 4'-DIA	615.78				ОК
4	MH, 4'-DIA	615.71				ок
5	VALVE VAULT	615.63	X			
6	VALVE VAULT	615.76				ок
7	CB, 4'-DIA	614.75	Х			
8	CB, 2'-DIA	614.73	X		Х	
9	VALVE VAULT	615.12	X			
10	INLET, TY. A	614.93				ОК
11	CB, 4'-DIA	614.70	X		X	
12	INLET, TY. A	614.88		Х		
13	VALVE VAULT	615.04	X			
14	CB, 2'-DIA	614.63		X	-	
15	CB, 4'-DIA	614.61	X		X	
16	INLET, TY. A	614.61	X		X	RE-MORTAR AROUND OUTLET PIPE
17 18	CB, 4'-DIA CB, 2'-DIA	615.04	X		X	RE-MORTAR AROUND OUTLET PIPE
19	INLET, TY. A	614.75 614.71	X		X	RE-ALIGN RINGS TO MEET FLOW LINE
20	CB, 4'-DIA	614.90	X		X	RE-MORTAR AROUND OUTLET PIPE RE-MORTAR AROUND OUTLET PIPE
21	CB, 2'-DIA	614.79	X		X	THE INDIVIAN ANDUND OUTLET PIPE
22	INLET, TY. A	614.59	X		x	RE-MORTAR AROUND OUTLET PIPE
23	CB, 4'-DIA	614.71	X		X	III III III III III III III III III II
24	CB, 2'-DIA	614.68	X		X	
25	VALVE VAULT	615.22	X		1	
26	MH, 4'-DIA	614.89	X			
27	CB, 4'-DIA	614.46	х		X	
28	INLET, TY. A	614.33	Х		Х	
29	CB, 4'-DIA	614.61	X		Х	
30	CB, 2'-DIA	614.70	Х		Х	
31	CB, 4'-DIA	615.02	Х			
32	VALVE VAULT	615.00				OK
33	CB, 4'-DIA	614.58	X			
34	VALVE VAULT	614.88				OK
35	CB, 2'-DIA	614.80	X		X	RE-MORTAR WALL AROUND OUTLET PIPE
36	CB, 4'-DIA	614.43				OK
37	CB, 2'-DIA	614.64	Х		X	
38 39	VALVE VAULT	614.98				ОК
40	INLET, TY. A MH, 4'-DIA	614.25 614.70	x	Х	X	
41	VALVE VAULT	614.74	x		_ A	
42	CB, 2'-DIA	614.30	X		х	
43	INLET, TY. A	614.60	X		X	
44	VALVE VAULT	614.97				ок
45	VALVE VAULT	614.78	х			
46	CB, 4'-DIA	614.43	х		х	
47	VALVE VAULT	614.71	х			
48	CB, 2'-DIA	614.52		х		
49	CB, 4'-DIA	614.36	X		Х	
50	CB, 2'-DIA	614.40		X		
51	VALVE VAULT	614.87				ОК
52	INLET, TY. A	614.51	X		X	LID CANNOT BE OPENED
53	INLET, TY. A	614.56	X		X	
54	CB, 4'-DIA	614.89	X		X	RE-MORTAR INSIDE WALL WHERE NEEDED
55	CB, 2'-DIA	614.81	X		X	
56 57	CB, 4'-DIA	614.57	X X		X	DE MODTAD INCIDE WALL WILLDE MEEDES
58	INLET, TY. A VALVE VAULT	614.53 614.73	^			OK RE-MORTAR INSIDE WALL WHERE NEEDED
59	CB, 2'-DIA	614.76	x		x	OK.
60	VALVE VAULT	614.79	^		^	ок
61	INLET, TY. A	614.57	- 22	х		
62	VALVE VAULT	614.58		-		ОК
63	CB, 2'-DIA	614.27	x		X	United States
64	INLET, TY. A	614.39		х		
65	CB, 2'-DIA	614.50	x		X	
66	VALVE VAULT	614.88	x		X	
67	VALVE VAULT	614.46				ок
68	CB, 4'-DIA	614.67	x		х	
69	INLET, TY. A	614.35	х			RE-ALIGN RINGS & RE-MORTAR
70	INLET, TY. A	614.34	X		X	


NOTES: STRUCTURES WITHIN PAVED AREAS WHERE IT HAS BEEN DETEREMINED THAT NEW ADJUSTING RINGS ARE NEEDED SHALL BE MODIFIED TO INSTALL RUBBERIZED ADJUSTMENT RINGS. MAXIMUM ADJUSTMENT FOR RUBBER RINGS TO BE 3 INCHES. ADDITIONAL ADJUSTMENTS IN HEIGHT SHALL BE MADE WITH PCC RINGS FOR A MAXIMUM TOTAL HEIGHT ADJUSTMENT OF 8 INCHES. ALL STRUCTURES WHICH INVOLVE ADJUSTMENTS WITH RUBBER RINGS SHALL BE PAID AS "FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)".




DRAWN BY: JMH	REVISED:
CHECKED BY: SAL	REVISED:
DATE: 12.01.14	REVISED:
REVISED:	REVISED:

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

	FAU RTE	SECTION	C	COUNTY SHE		SHEET NO.	
STRUCTURE R	1569	14-00037-00-RS		COOK 20 14 CONTRACT No. 61B26		14	
	LOOP PLAN				CONTRA	ACT NO. 61	826
SCALE: N.T.S. SHEET No. 14 OF 20 SHEETS		FED. ROAD	DIST. NO.	ILLINOIS	FED. A	ND PROJECT	





TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS

NOTES:

- A. FOR NO LANE RESTRICTION ON THE SIDE ROAD OR DRIVEWAYS
- SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- O) ONE ROAD CONSTRUCTION AHEAD SIGN 36 x 36 (900×900) WITH A FLASHER AND FLAG MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
- b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- 2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- O) ONE ROAD CONSTRUCTION AHEAD SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN POLITE
- b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
- WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).

B. FOR A LANE CLOSURE ON A SIDE ROAD OR DRIVEWAY:

USE APPLICABLE PORTIONS OF THE TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES (STD. 701501, STD. 701606 OR THE APPROPRIATE STANDARD). THE SPACING OF SIGNS AND BARRICADES SHALL BE ADJUSTED FOR FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. THE DIRECTIONAL ARROW SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE SIDE ROAD LANE CLOSURE.


- C. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAY UNLESS OTHERWISE NOTED.
- D. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCIDENTAL TO THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.


All dimensions are in millimeters (inches) unless otherwise shown.

FILE NAME =	USER NAME = gaglianobt	DESIGNED - LHA	REVISED - J. OBERLE 10-18-95
Wi\diststd\22x34\tc10.dgn		DRAWN -	REVISED - A. HOUSEH 03-06-96
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED - A. HOUSEH 10-15-96
	PLOT DATE = 1/4/2008	DATE - 06-89	REVISED -T. RAMMACHER 01-06-00


STATI	E 0	F ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

	TRAFFIC CONTROL AND P	FOR	F.A. RTÉ.	SECTION	COUNTY	TOTAL	SHEET NO.	
	SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS				14-00037-00-RS	COOK	20	16
					TC-10	CONTRACT	NO.	51B26
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. RO	AD DIST. NO. 1 ILLINOIS FED. AT	D PROJECT		






4' (1.2 m) WIDE MEDIANS ONLY



DIAGONAL LINE SPACING: 50' (15 m) C-C (LESS THAN 30MPH (50 km/h))
75' (25 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h))
150' (45 m) C-C (MORE THAN 45MPH (70 km/h))

MEDIANS OVER 4' (1.2 m) WIDE




A MINIMUM OF TWO PAIRS OF TURN ARROWS SHALL BE USED, WHITE IN COLOR, ADDITIONAL PAIRS SHALL BE PLACED AT 200' (60 m) TO 300' (90 m) INTERVALS.



MEDIAN WITH TWO-WAY LEFT TURN LANE

TYPICAL PAINTED MEDIAN MARKING




FULL SIZE LETTERS 8' (2.4 m) AND ARROWS SHALL BE USED. \upphi AREA = 15.6 SO. FT. (1.5 m²) \upphi AREA = 20.8 SO. FT. (1.9 m²)

* TURN LANES IN EXCESS OF 400' (120 ml in length may have an additional SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF ARROW - "ONLY".

TYPICAL LEFT (OR RIGHT) TURN LANE

TYPICAL TURN LANE MARKING



TYPICAL ISLAND MARKING

ISLAND AT PAVEMENT EDGE

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING / REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVIDED PAVEMENT	2 a 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 b 4 (100)	SOLID SOLID	YELLOW	5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MOUNTABLE MEDIANS IN YELLOW: EDGE LINES ARE NOT USED NEXT TO BARRIER CURB
TURN LANE MARKINGS	6 (150) LINE; FULL SIZE LETTERS & SYMBOLS (8' (2,4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	2 # 4 (100) EACH DIRECTION 8' (2,4m) LEFT ARROW	SKIP-DASH AND SOLID	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5/5; 14(0) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN
	O 12.4III LEFT ARROW	IN PAIRS	WALTE	MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 12 (300) @ 45° 12 (300) @ 90°	SOL 1D SOL 1D SOL 1D	WHITE WHITE WHITE	NOT LESS THAN 6' (I.8 m) APART 2' (500) APART 2' (500) APART 5' (500) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' 11.2 m) IN ADVANCE OF AND PARALLEL TO CROSSMALK, IF PRESENT. OTHERWISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE
PAINTED MEDIANS	2 # 4 (100) WITH 12 (300) DIAGONALS # 45° NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS	SOLID	YELLOW: TWO WAY TRAFFIC WHITE: ONE WAY TRAFFIC	11 (280) C-C FOR THE DOUBLE LINE SEE TYPICAL PAINTED MEDIAN MARKING.
GORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS 9 45°	SOLID	WHITE	DIAGONALS: 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h)) 30' (9 m) C-C (OVER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES; "RR" IS 6' (1.8 m) LETTERS; 16 (400) LINE FOR "X"	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: "M"43.6 SO. FT. (0.33 m²) EACH "X"54.0 SQ. FT. (5.0 m²)
SHOULDER DIAGONALS	12 (300) e 45°	SOL10	WHITE - RIGHT YELLOW - LEFT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) T0 45MPH (70 km/h)) 150' (45 m) C-C (0VER 45MPH (70 km/h))


FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

All dimensions are in inches (millimeters) unless otherwise shown.

FILE NAME =	USER NAME = drivakovgn	DESIGNED - EVERS	REVISED -T. RAMMACHER 10-27-94
c:\pw_work\pwidot\drivakosgn\d8188315\tc	3.dgn	DRAWN -	REVISED - C. JUCIUS 09-09-09
	PLOT SCALE = 50.000 "/ IN.	CHECKED -	REVISED -
	PLOT DATE = 9/9/2009	DATE - 03-19-90	REVISED -

STATE	OF	ILLINOIS	
DEPARTMENT	OF	TRANSPORTATION	

	DISTRICT ONE TYPICAL PAVEMENT MARKINGS					F.A RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
						1569	14-00037-00-RS	COOK	2120	17
							TC-13	CONTRAC	T NO. 61	B26
	SCALE: NONE	SHEET NO. 1 OF	F 1 SHEET	S STA.	TO STA.	FED. RO	DAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT		



CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.


 COUNTY
 TOTAL SHEETS NO.

 COOK
 20
 18


 CONTRACT
 NO. 61B26

FILE NAME : g:\pw.work\pwidot\drivokosgn\d0188315\bi	USER NAME = drivakosgn	DESIGNED - A. HOUSEH	REVISED - R. SHAH 10-03-96			F.A. SECTION
	PLOT SCALE = 58.888 7 / IN. CHECKED - REVISED - A. ABBAS 03-21-97 PLOT SCALE = 58.888 7 / IN. CHECKED - M. GOMEZ 01-22-01 DEPARTMENT OF TRANSPORTATION	CURB OR CURB AND GUTTER	1569 14-00037-00-RS			
		REVISED - M. GOMEZ 01-22-01	DEPARTMENT OF TRANSPORTATION	REMOVAL AND REPLACEMENT	BD600-06 (BD-24)	
	PLOT DATE = 12/15/2009	DATE - 03-11-94	REVISED - R. BORO 12-15-09	DEFAITMENT OF THAINGE ON ATTOM	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PR

HBE JOB No:13-517



OPTION 1




HMA CONSTRUCTED TEMPORARY RAMP

(FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW)

OPTION 2

TYPICAL TEMPORARY RAMP



TYPICAL BUTT JOINT AND HMA TAPER FOR MILLING AND RESURFACING

REVISED - R. SHAH 10-25-94

REVISED - A. ABBAS 03-21-97

REVISED - M. GOMEZ 04-06-01

REVISED - R. BORO 01-01-07

DESIGNED - M. DE YONG

- 06-13-90

DRAWN

DATE

CHECKED .

USER NAME = gaglianobt

PLOT SCALE = 58.0000 ' / IN.

PLOT DATE = 1/4/2008

FILE NAME =

W:\d:ststd\22x34\bd32.dgn

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

PROP. HMA OR PCC SURFACE REMOVAL - BUTT JOINT SAW CUT (INCLUDED IN THE COST EXIST. HMA OR PCC SURFACE 30'-0" (9.0 m) (NOTE "A") OF HMA OR P.C.C. SURFACE REMOVAL 15'-0" (4.5 m) (NOTE "B") BUTT JOINT) (NOTE "D") 13/4 (45) FOR E AND F MIX 11/2 (40) FOR C AND D MIX * * EXIST. PAVEMENT BUTT JOINT DETAIL TAPER LENGTH * * * VARIES PROP. HMA SURF. CRSE. 13/4 (45) FOR E AND F MIX PROP. HMA BINDER CRSE. 11/2 (40) FOR C AND D MIX * * EXIST. PAVEMENT HMA TAPER DETAIL TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY * * PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.
- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F: INSTALLATION AND REMOVAL OF THE 4'-6" (1,35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- * SEE TYPICAL SECTIONS FOR MILLING THICKNESS.

BASIS OF PAYMENT:

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT".

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

SECTION

BD400-05 BD32 CONTR.
ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

569 14-00037-00-RS

COUNTY TOTAL SHEETS NO.

CONTRACT NO. 61B26

COOK

HBE JOB No:13-517

