

---

**STRUCTURE GEOTECHNICAL REPORT  
MANHATTAN-MONEE ROAD CULVERT  
OVER DRAINAGE DITCH  
STATION 70+01.53  
WILL COUNTY, ILLINOIS**

**For  
Quigg Engineering Inc.  
111 S. Wacker Drive, Suite 3910  
Chicago, IL 60606**

**Submitted by  
Wang Engineering, Inc.  
1145 North Main Street  
Lombard, IL 60148**

**Original Report: June 21, 2019  
Revised Report: NA**

**Technical Report Documentation Page**

<b>1. Title and Subtitle</b> Structure Geotechnical Report, Manhattan-Monee Road Culvert over Drainage Ditch		<b>2. Original Date:</b> June 21, 2019 <b>Revised Date:</b> NA
		<b>3. Report Type</b> <input checked="" type="checkbox"/> SGR <input type="checkbox"/> RGR <input type="checkbox"/> Draft <input checked="" type="checkbox"/> Final <input type="checkbox"/> Revised
<b>4. Route / Section / County/ District/ Region</b> FAP531/2018-063-CR&D/Will/1/1		<b>5. Contract</b> 62G85
<b>6. PTB / Item No./Work Order</b> 185-002/NA/15 and 15A	<b>7. Existing Structure Number(s)</b> SN 099-0441	<b>8. Proposed Structure Number(s)</b> NA
<b>9. Prepared by</b> Wang Engineering, Inc. 1145 N Main Street Lombard, IL 60148	<b>Contributor(s)</b> Author: Mohammed Kothawala, PE, DGE QA/QC: Corina Farez, PG, PE PM: Mohammed Kothawala, PE, DGE	<b>Contact</b> (630) 953-9928 ext. 1036 mkothawala@wangeng.com
<b>10. Prepared for</b> Quigg Engineering Inc. 111 S. Wacker Drive, Suite 3910 Chicago, IL, 60606	<b>Design Engineer</b> Sapan Trivedi, Structural Designer Accurate Group, Inc.	<b>Contact</b> (847) 613-1100 ext. 508 sapant@accgi.com
<b>11. Abstract</b> <p>Several improvements are proposed to the site near the existing culvert carrying a drainage ditch under the Manhattan-Monee Road. The improvements include removing the existing culvert under the driveway on the south side of the Manhattan-Monee Road and replacing with a new 5-foot wide and 4-foot high box culvert, three new retaining walls, the existing gabion wall removal and abandoning in place the existing Manhattan-Monee Road culvert.</p> <p>Beneath the pavement and topsoil, the general lithologic profile encountered during the investigation includes up to 3 feet of medium stiff to stiff silty clay to silty clay loam fill and buried topsoil over medium stiff to hard clay, silty clay to silty clay loam interbedded sand to sandy gravel. Groundwater was observed at elevations of 689 to 691 feet and measured at elevations of 671 to 689 feet.</p> <p>With about the 30 inches of the unstable soils removal and replacement to elevation of 693 feet, it will be feasible to construct the culvert. Following the recommended treatment, the culvert barrel can be designed a factored bearing resistance of 4,000 psf. The long-term settlements are estimated to be 0.5 inches with a differential settlement of 0.5 inches or less.</p> <p>We provided recommendations for the potential wingwall types including horizontal, precast apron end sections, cast-in-place T-type walls, and sheet pile walls.</p> <p>Three new retaining walls are proposed to be sheet pile walls. We provide the recommended soil parameters for the wall design.</p>		
<b>12. Path to archived file</b> S:\Netprojects\1990208\Reports\SN_099-0441\RPT_Wang_NSB_1990208_SGR_DrainageDitchCulvert_V03_20190621.doc		

## TABLE OF CONTENTS

<b>1.0</b>	<b>INTRODUCTION.....</b>	<b>1</b>
1.1	PROPOSED IMPROVEMENTS.....	1
1.2	EXISTING STRUCTURES.....	2
<b>2.0</b>	<b>METHODS OF INVESTIGATION.....</b>	<b>2</b>
2.1	FIELD INVESTIGATION.....	2
2.2	LABORATORY TESTING.....	3
<b>3.0</b>	<b>INVESTIGATION RESULTS.....</b>	<b>3</b>
3.1	LITHOLOGICAL PROFILE.....	4
3.2	GROUNDWATER CONDITIONS.....	5
<b>4.0</b>	<b>FOUNDATION ANALYSIS AND RECOMMENDATIONS.....</b>	<b>5</b>
4.1	SCOUR CONSIDERATIONS.....	5
4.2	CULVERT FOUNDATION.....	5
4.3	SETTLEMENT.....	6
4.4	WINGWALLS.....	6
4.5	CAST-IN-PLACE OR PRECAST CULVERT CONSIDERATIONS.....	6
4.6	RETAINING WALLS.....	7
4.7	GLOBAL STABILITY.....	11
4.8	STAGE CONSTRUCTION.....	11
<b>5.0</b>	<b>CONSTRUCTION CONSIDERATIONS.....</b>	<b>12</b>
5.1	SITE PREPARATION.....	12
5.2	EXCAVATION, DEWATERING AND UTILITIES.....	12
5.3	FILLING AND BACKFILLING.....	12
5.4	RETAINING WALLS.....	12
5.5	EARTHWORK OPERATIONS.....	13
<b>6.0</b>	<b>QUALIFICATIONS.....</b>	<b>14</b>
	REFERENCES.....	15

---

**EXHIBITS**

- 1. SITE LOCATION MAP*
- 2. BORING LOCATION PLAN*
- 3. SOIL PROFILE*

**APPENDIX A***BORING LOGS***APPENDIX B***LABORATORY TEST RESULTS***APPENDIX C***GLOBAL STABILITY ANALYSES***APPENDIX D***GENERAL PLAN AND ELEVATION SHEETS***LIST OF TABLES**

Table 1: Geotechnical Parameters for Design of Wall No.1 .....	7
Table 2: Geotechnical Parameters for Design of Wall No. 2 .....	8
Table 3: Geotechnical Parameters for Design of Wall No. 3 .....	9
Table 4: Recommended Parameters for Lateral Load Analysis of Wall No. 1 .....	9
Table 5: Recommended Parameters for Lateral Load Analysis of Wall No. 2 .....	10
Table 6: Recommended Parameters for Lateral Load Analysis of Wall No. 3 .....	11

---

**STRUCTURE GEOTECHNICAL REPORT  
MANHATTAN-MONEE ROAD CULVERT  
OVER DRAINAGE DITCH  
STATION 70+01.53  
WILL COUNTY, ILLINOIS  
FOR  
QUIGG ENGINEERING INC.**

## **1.0 INTRODUCTION**

This report presents the results of our subsurface investigations, laboratory testing, geotechnical evaluations, and recommendations to support the proposed improvements at the existing culvert, designated as SN 099-0441. The culvert site is located about 0.25 miles west of US Route 45 in Will County, Illinois. On the USGS *Manhattan Quadrangle 7.5 Minute Series* map, the project site is generally located at SE ¼ of Section 18, NE ¼ of Sec. 19, Township 34N, Range 11E of the Third Principal Meridian. A *Site Location Map* is presented as Exhibit 1.

The purpose of this investigation was to characterize the site soil and groundwater conditions, perform geotechnical analyses, and provide recommendations for the design and construction of the proposed improvements.

### **1.1 Proposed Improvements**

Based on General Plan and Elevation (GPE) Drawing (Appendix D) dated June 5, 2019 and information provided by Accurate Group, Inc. (Accurate), Wang Engineering, Inc. (Wang) understands that the following improvements are proposed at the existing culvert, SN 099-0441:

- The existing culvert, SN 099-0441 currently has three plastic pipes inserted the length of the culvert barrel with grout filling voids around the pipes. This culvert will be filled with CLSM and abandoned in place;
- At the southeast corner of the existing culvert, SN 099-0441, there is an existing pipe culvert carrying the private driveway over the drainage ditch and running east to west direction. This pipe culvert will be removed and replaced with a new 5-foot wide and 4-foot high concrete box culvert with an out-to-out length of 39 feet. The proposed culvert will have invert elevations of 696.69 and 696.28 feet at upstream and downstream ends, respectively;

- A new retaining wall, designated as Wall No. 1 begins at proposed culvert northwest wingwall at Station 69+50 and ends at Station 69+73 running along south side of the Manhattan-Monee Road;
- A new retaining wall, designated as Wall No. 2 begins at the existing retaining wall at Station 69+84.75 and ends at Station 70+14.75 running along north side of the Manhattan Monee Road; and
- The existing gabion wall along north side of the Manhattan Monee Road will be removed and replaced with a new retaining wall, designated as Wall No.3. The new Wall No.3 begins at Station 70+86 and ends at Station 71+53.

## **1.2 Existing Structures**

The existing culvert, SN 099-0441 is a single cell concrete box culvert currently having three 24 inches plastic pipes inserted for full length of culvert and grout filling the void around the pipes. The existing box culvert is 7-foot wide and 3-foot high with an out-to-out length of 33.9 feet along the centerline of culvert. There is a retaining wall running on the north side of Manhattan-Monee Road. The culvert carries one lane of traffic in each direction.

A 36-inches diameter pipe culvert carrying the private driveway over the drainage ditch is located at the southeast corner of existing culvert.

## **2.0 METHODS OF INVESTIGATION**

The following sections outline the field and laboratory investigations performed by Wang.

### **2.1 Field Investigation**

The field investigation consisted of four structure borings, designated as CB-03, CB-04, RW-01 and RW-02 drilled from elevations 700.7 to 702.7 feet to a depth of 30 feet below ground surface (bgs). In addition, we have considered Boring B-4 drilled by others in 1990. The subsurface investigation performed by Wang was completed on April 19 and 22, 2019.

For the existing gabion wall replacement, the field investigation consisted of two structure borings, designated as 3-RWB-1 and 3-RWB-2 and two geoprobe borings, designated as 3-HA-1 and 3-HA-2 drilled from elevations 697.9 to 703.1 feet to depths of 10 to 35 feet bgs. The field investigation was performed by Wang on June 5, 2019.

The as-drilled coordinates and elevations were obtained with a mapping-grade GPS unit. Stations and offsets were provided by Accurate. As-drilled boring locations are presented in the *Boring Logs* (Appendix A) and the as-drilled boring locations are shown in the *Boring Location Plan* (Exhibit 2).

ATV and truck-mounted drilling rigs, equipped with hollow stem augers, were used to advance and maintain open boreholes. Soil sampling was performed according to AASHTO T206, "*Penetration Test and Split Barrel Sampling of Soils.*" The soil was sampled at 2.5-foot intervals to the boring termination depths. Jackhammer driven Geoprobe samplers were used to continuously sample the soil in the hand auger borings. Soil samples collected from each sampling interval were placed in sealed jars and transported to the laboratory for further examinations and laboratory testing.

Field boring logs, prepared and maintained by Wang geologist, include lithological descriptions, visual-manual soil (IDH Textural) classifications, results of Rimac and pocket penetrometer unconfined compressive strength tests ( $Q_u$ ), and results of Standard Penetration Tests (SPT) recorded as blows per 6 inches of penetration.

Groundwater levels were measured while drilling and at completion of each boring. Each borehole was backfilled upon completion with soil cuttings and/or bentonite chips. The pavement surface was restored as close as possible to its original condition.

## **2.2 Laboratory Testing**

The soil samples were tested in the laboratory for moisture content (AASHTO T265). Atterberg limits (AASHTO T89 and T90) and particle size analyses (AASHTO T88) were performed on selected samples. Tested samples were classified according to the IDH classification system. Field visual descriptions of the soil samples were verified in the laboratory. Laboratory test results are shown in the *Boring Logs* (Appendix A) and in the *Laboratory Test Results* (Appendix B).

## **3.0 INVESTIGATION RESULTS**

Detailed descriptions of the soil conditions encountered during the subsurface investigation are presented in the attached *Boring Logs* (Appendix A) and in the *Soil Profile* (Exhibit 3). Please note that strata contact lines represent approximate boundaries between soil types. The actual transition between soil types in the field may be gradual in horizontal and vertical directions.

### 3.1 Lithological Profile

Borings CB-04 and RW-02, drilled on the roadway encountered 3 inches of asphalt over 9 inches of concrete. Borings 3-RWB-1 and 3-RWB-2, drilled on the roadway along the existing gabion wall encountered 14 and 15 inches of asphalt over sandy gravel aggregate base. Borings CB-03 and RW-01, drilled on the grassy area revealed 12 inches of topsoil at the surface. Geoprobe Borings 3-HA-1 and 3-HA-2, drilled in front of the gabion wall encountered running water at the surface over 6 inches of topsoil and stiff to hard silty clay. In descending order, the general lithologic succession encountered beneath the surface includes: 1) man-made ground (fill); and 2) medium stiff to hard clay silty clay to silty clay loam.

#### 1) *Man-made ground (fill)*

Beneath the pavement and topsoil, the borings encountered up to 3 feet of stiff, black and brown silty clay loam and silt fill. The soil has unconfined compressive strength ( $Q_u$ ) values of 1.3 to 1.7 tsf and moisture content values of 15 to 26%. Boring CB-04 revealed 2 feet of medium dense gravel with N value of 16 blows per foot and moisture content of 27%.

At elevations of 699.2 to 701.2 feet, Borings CB-04, RW-02, and 3-RWB-1 encountered 1.6 to 3.3 feet of silty clay loam buried topsoil with unconfined compressive strength ( $Q_u$ ) values of 1.0 and 3.0 tsf and moisture content values of 30 and 37%.

#### 2) *Medium stiff to hard clay, silty clay to silty clay loam*

Beneath the fill and buried topsoil, at elevations of 695.9 to 700.1 feet, the borings encountered medium stiff to hard, orange, brown, and gray clay, silty clay to silty clay loam interbedded with water-bearing, loose to medium dense sand to sandy gravel. The unit has  $Q_u$  values generally between 0.9 and 4.8 tsf and moisture content values between 14 and 29%; Boring CB-03 recorded lower  $Q_u$  values between 0.4 and 0.8 tsf with moisture content values of 16 to 55%. Laboratory index testing on samples from this layer showed liquid limit ( $L_L$ ) values of 25 to 48% and plastic limit ( $P_L$ ) values of 14 to 22%.

The interbedded 2 to 5 feet thick sand to sandy gravel has N-values of 5 to 14 blows per foot and moisture content values of 10 to 22%.

### **3.2 Groundwater Conditions**

Groundwater was encountered while drilling at elevations of 689 to 695 feet within the sand and gravel layer (3.0 to 11.8 feet bgs). At the completion of drilling, groundwater was measured at elevations of 671 to 689 feet (14 to 30 feet bgs).

## **4.0 FOUNDATION ANALYSIS AND RECOMMENDATIONS**

Geotechnical evaluations and recommendations for the proposed culvert, wingwalls, and retaining walls are included in the following sections.

### **4.1 Scour Considerations**

The design scour elevation should be taken at the bottom of the cutoff wall (IDOT 2012). To prevent local erosion, we recommend placing stone riprap or a concrete apron at the ends of the proposed culvert. This will also prevent sediments from entering and accumulating in the culvert and minimize long term maintenance.

### **4.2 Culvert Foundation**

Based on our subsurface investigation, the soils at the base of the culvert barrel are expected to be medium stiff silty clay with a  $Q_u$  value of 0.66 tsf and moisture content value of 55% followed by stiff to hard silty clay. Prior to placement of the culvert barrel, we recommend removing 2.5 feet of the medium stiff silty clay loam to an elevation of 693.0 feet. The replacement material should be the pay item “*Rockfill*” in accordance with the 2017 IDOT *Culvert Manual*. Rockfill material gradation and capping requirements should be as per IDOT District One Rockfill Special Provision, January 2010. The replacement material should extend a minimum of two feet beyond the edge of the box.

The soils at the culvert bearing level should be evaluated in the field to determine the actual undercut depth. The actual extent of the removal shall be determined in the field by a geotechnical soil inspector at the time of construction.

Following the recommended foundation treatment, the culvert barrel can be designed with a factored bearing resistance of 4,000 psf using a bearing resistance factor of 0.45 (AASHTO 2017).

### **4.3 Settlement**

Following the recommended treatment as described in Section 4.2, we estimate the foundation soils will experience settlement up to 0.5 inches at the widening portion of the new culvert with the differential settlement of 0.5 inches or less. The settlement estimates are acceptable for the culvert structure.

### **4.4 Wingwalls**

Based on the TSL plan, we understand the wingwalls at both culvert barrel ends will be horizontal cantilever wingwalls with a length of 7'-3". Other wingwall types suitable for this culvert include precast apron end sections, cast-in-place T-type or sheet pile walls.

Horizontal cantilever wingwalls should be designed based on the structural guidelines provided in Section 4.2 of the IDOT Culvert Manual (2017). Horizontal cantilever wingwalls should be founded at a minimum depth of 3.0 feet below the culvert invert elevations.

If precast apron end sections are selected, they should be as per IDOT Basesheet dated 2/17/2017 "*SCB-AES, Precast Concrete Box Culvert Apron End Section Details*" and constructed based on IDOT Standard Specifications.

If sheet pile wingwalls are selected, they can be designed based on our recommendations as described in Section 4.6 for the Retaining Wall No. 1.

For the cast-in-place T-type wingwalls, the footings should be established at a depth such that they would be at least 4 feet below culvert barrel invert elevation. Footings will be established at elevations 692.3 and 692.7 feet. Based on subsurface investigation, stiff to hard silty clay is expected to be encountered at the footing elevation. The T-type wingwalls can be designed based on a factored resistance of 4,000 psf and the information and typical sections shown in IDOT Section 4.4 (IDOT 2017).

### **4.5 Cast-In-Place or Precast Culvert Considerations**

The results of the settlement evaluations indicate that both cast-in-place and precast culvert options are appropriate and feasible at the site. Following the recommended foundation treatment as described in Section 4.2, the differential settlement will be about 0.5 inches, which will not cause excessive separation of the precast sections.

#### 4.6 Retaining Walls

Based on the TSL plan provided by Accurate, the proposed Retaining Walls No. 1 and No.2 will have out-to-out lengths of 23 and 30 feet, respectively. Based on the preliminary cross-section drawings, we estimate the Walls No.1 and No.2 will have approximate maximum retained heights of 2 and 5 feet, respectively. The existing gabion wall will be removed and replaced with Wall No.3. The proposed Wall No.3 will have out-to-out length of 67 feet and a maximum retained height of 5.5 feet. The walls are proposed to be sheet pile type with 2-foot concrete cap on the top.

We do not recommend the gravity wall types such as a cast-in-place cantilever concrete and Mechanically Stabilized-Earth walls due to the flowing surface water in ditches and the need of foundation excavations for wall construction. Thus, we provide recommendations for the design of flexible wall types including sheet pile wall.

We recommend the soil parameters shown in Tables 1 through 3 to be used for the design of the flexible/sheet pile walls. The embedment depth for the wall should be designed in accordance with the 2017 AASHTO LRFD guidelines considering a horizontal earth pressure load factor of 1.50 and a passive resistance factor of 0.75. In developing the design lateral pressure, the lateral pressure due to construction equipment surcharge load and traffic surcharge should be added to the lateral earth pressure. The active and passive earth pressure coefficients are provided for straight backfill behind and in front of the wall.

Table 1: Geotechnical Parameters for Design of Wall No.1

Soil Description	Unit	Drained Shear Strength Properties		Earth Pressure Coefficients <sup>(1)</sup>	
		Cohesion (psf)	Friction Angle (°)	Active Pressure	Passive Pressure
M Stiff to Stiff SI CLAY FILL Surface to 696.5 feet	120	100	30	0.33	3.00
M Stiff SI CLAY EL 696.5 to 692.5 feet	115	0	28	0.36	2.77
Stiff to Hard SI CLAY EL 692.5 to 689.0 feet	120	100	30	0.33	3.00

Soil Description	Unit	Drained Shear Strength Properties		Earth Pressure Coefficients <sup>(1)</sup>	
		Cohesion (psf)	Friction Angle (°)	Active Pressure	Passive Pressure
M Dense SAND to GRAVEL EL 689.0 <sup>(2)</sup> to 686.5 feet	58 <sup>(3)</sup>	0	31	0.32	3.12
Stiff SI CLAY EL 686.5 to 670.7 feet	58 <sup>(3)</sup>	100	30	0.33	3.00

<sup>(1)</sup>Straight slope; <sup>(2)</sup>Groundwater elevation; <sup>(3)</sup>Submerged Unit Weight

Table 2: Geotechnical Parameters for Design of Wall No. 2  
 Reference Borings: RW-01, RW-02, and B-04

Soil Description	Unit	Drained Shear Strength Properties		Earth Pressure Coefficients <sup>(1)</sup>	
		Cohesion (psf)	Friction Angle (°)	Active Pressure	Passive Pressure
Stiff SI CL LOAM FILL Surface to 696.5 feet	120	100	30	0.33	3.00
Stiff SI CLAY EL 696.5 to 690.5 feet	120	100	30	0.33	3.00
SAND EL 690.5 <sup>(2)</sup> to 689.0 feet	58 <sup>(3)</sup>	0	30	0.33	3.00
M Stiff SI CLAY EL 689.0 to 687.5 feet	53 <sup>(3)</sup>	0	28	0.36	2.77
Stiff to V Stiff SI CLAY EL 687.5 to 670.8 feet	58 <sup>(3)</sup>	100	30	0.33	3.00

<sup>(1)</sup>Straight slope; <sup>(2)</sup>Groundwater elevation; <sup>(3)</sup>Submerged Unit Weight

Table 3: Geotechnical Parameters for Design of Wall No. 3  
 Reference Borings: 3-HA-1, 3-HA-2, 3-RW-1, and 3-RW-2

Soil Description Elevation Range	Unit Weight, $\gamma$ (pcf)	Drained Shear Strength Properties		Earth Pressure Coefficients <sup>(1)</sup>	
		Cohesion (psf)	Friction Angle ( $^{\circ}$ )	Active Pressure	Passive Pressure
Stiff to Hard SI CLAY Surface to 694.8 feet	120	100	30	0.33	3.00
SAND and SANDY GRAVEL EL 694.8 <sup>(1)</sup> to 690.2 feet	53 <sup>(2)</sup>	0	30	0.33	3.00
M Stiff to Stiff SI CLAY EL 690.2 to 682.1 feet	53 <sup>(2)</sup>	0	29	0.35	2.88
Stiff to V Stiff SI CLAY EL 687.5 to 670.8 feet	58 <sup>(2)</sup>	100	30	0.33	3.00

<sup>(1)</sup>Straight slope; <sup>(2)</sup>Groundwater elevation; <sup>(3)</sup>Submerged Unit Weight

The lateral deformation of the wall should also include deflection control at the top of flexible wall. The evaluations should be performed using the parameters shown in Tables 4 through 6 via p-y curve (COM624P, LPILE, and any other programs) method.

Table 4: Recommended Parameters for Lateral Load Analysis of Wall No. 1  
 Reference Borings: CB-03 and RW-02

Soil Description Elevation Range	Unit Weight, $\gamma$ (pcf)	Undrained Shear Strength, $c_u$ (psf)	Estimated Friction Angle, $\Phi$ ( $^{\circ}$ )	Estimated Lateral Soil Modulus Parameter, k (pci)	Estimated Soil Strain Parameter, $\epsilon_{50}$ (%)
M Stiff to Stiff SI CLAY FILL Surface to 696.5 feet	120	1500	0	400	0.75
M Stiff SI CLAY EL 696.5 to 692.5 feet	115	700	0	100	1.20
Stiff to Hard SI CLAY EL 692.5 to 689.0 feet	120	1500	0	400	0.75

Soil Description	Unit Weight, $\gamma$ (pcf)	Undrained Shear Strength, $c_u$ (psf)	Estimated Friction Angle, $\Phi$ ( $^\circ$ )	Estimated Lateral Soil Modulus Parameter, k (pci)	Estimated Soil Strain Parameter, $\epsilon_{50}$ (%)
M Dense SAND to GRAVEL EL 689.0 <sup>(1)</sup> to 686.5 feet	58 <sup>(2)</sup>	0	31	60	--
Stiff SI CLAY EL 686.5 to 670.7 feet	58 <sup>(2)</sup>	1100	0	200	0.95

<sup>(1)</sup>Groundwater elevation; <sup>(2)</sup>Submerged Unit Weight

Table 5: Recommended Parameters for Lateral Load Analysis of Wall No. 2

Reference Borings: RW-01, RW-02, and B-04

Soil Description	Unit Weight, $\gamma$ (pcf)	Undrained Shear Strength, $c_u$ (psf)	Estimated Friction Angle, $\Phi$ ( $^\circ$ )	Estimated Lateral Soil Modulus Parameter, k (pci)	Estimated Soil Strain Parameter, $\epsilon_{50}$ (%)
Stiff SI CL LOAM FILL Surface to 696.5 feet	120	1400	0	400	0.80
Stiff SI CLAY EL 696.5 to 690.5 feet	120	1600	0	500	0.75
SAND EL 690.5 <sup>(1)</sup> to 689.0 feet	58 <sup>(2)</sup>	0	30	50	--
M Stiff SI CLAY EL 689.0 to 687.5 feet	53 <sup>(2)</sup>	900	0	200	1.05
Stiff to V Stiff SI CLAY EL 687.5 to 670.8 feet	58 <sup>(2)</sup>	1300	0	300	0.85

<sup>(1)</sup>Groundwater elevation; <sup>(2)</sup>Submerged Unit Weight

Table 6: Recommended Parameters for Lateral Load Analysis of Wall No. 3  
 Reference Borings: 3-HA-1, 3-HA-2, 3-RW-1, and 3-RW-2

Soil Description	Unit Weight, $\gamma$ (pcf)	Undrained Shear Strength, $c_u$ (psf)	Estimated Friction Angle, $\Phi$ ( $^\circ$ )	Estimated Lateral Soil Modulus Parameter, k (pci)	Estimated Soil Strain Parameter, $\epsilon_{50}$ (%)
Stiff to Hard SI CLAY Surface to 694.8 feet	120	1500	0	400	0.80
SAND and SANDY GRAVEL EL 694.8 <sup>(1)</sup> to 690.2 feet	53 <sup>(2)</sup>	0	30	30	--
M Stiff to Stiff SI CLAY EL 690.2 to 682.1 feet	53 <sup>(2)</sup>	1100	0	300	0.95
Stiff to V Stiff SI CLAY EL 687.5 to 670.8 feet	58 <sup>(2)</sup>	1400	0	350	0.80

<sup>(1)</sup>Groundwater elevation; <sup>(2)</sup>Submerged Unit Weight

#### 4.7 Global Stability

We have analyzed the global stability of embankment behind the Retaining Wall No.1 at the most critical location where weaker soil layers were encountered with a maximum retained height of 10 feet. The analyses were performed with *Slide v6.0* and the results of the evaluations are provided in *Slope Stability Analysis* (Appendix C). We estimate the wall with an embedment depth of 4 feet has an undrained Factor of Safety (FOS) of 6.08 (Appendix C-1) and a drained FOS of 2.54 (Appendix C-2), satisfying the minimum FOS requirement of 1.7 (IDOT 2015); however, the wall designer should perform other analyses to determine the required embedment depth.

Considering similar soil conditions along Retaining Wall No. 2, Retaining Wall No.3, and wingwalls, we do not anticipate global stability concerns.

#### 4.8 Stage Construction

Based on the TSL plan, Manhattan-Monee Road will be detoured and only open for local traffic during construction. The access to the private property driveway will be a temporary runaround during culvert replacement.

## **5.0 CONSTRUCTION CONSIDERATIONS**

### **5.1 Site Preparation**

The existing vegetation, surface topsoil, pavement, and debris should be cleared and stripped where the culvert and walls will be placed.

### **5.2 Excavation, Dewatering and Utilities**

Excavations should be performed in accordance with local, state, and federal regulations. The potential effect of ground movements upon nearby roadways, structures, and utilities should be considered during construction. Any excavation that cannot be sloped 1:2 (V:H) should be properly shored with temporary sheet piling or temporary soil retention systems.

The groundwater was encountered at elevations of 689 to 691 feet, about 4 to 6 feet below the culvert base elevation. However, during our site visit, the surface water was observed in the ditches as well as in the culvert. Depending upon prevailing climate conditions and the time of the year when culvert construction take place, control runoff and maintenance of existing flows may require temporary water diversion and control. Any water that accumulates in open excavations by seepage or runoff should be immediately removed.

### **5.3 Filling and Backfilling**

Fill used as embankment material and for replacement of any unstable or unsuitable soils encountered during construction should be pre-approved by the Engineer. The material used to backfill around and to a level at least 1 foot over the top of the culvert box, should be porous granular material conforming to the requirements specified in the IDOT 2019 Supplemental Specifications and Recurring Special Provisions, *Granular Backfill of Structures*.

### **5.4 Retaining Walls**

The walls should be constructed as per IDOT Section 522 and in particular in accordance with 522.06. Difficulty in sheet pile driving should be expected between elevations 690 and 695 feet.

## **5.5 Earthwork Operations**

The required earthwork can be accomplished with conventional construction equipment. Moisture and traffic will cause deterioration of exposed subgrade soils. Precautions should be taken by the Contractor to prevent water erosion of the exposed subgrade. A compacted subgrade will minimize water runoff erosion.

Earth moving operations should be scheduled to not coincide with excessive cold or wet weather (early spring, late fall or winter). Any soil allowed to freeze or soften due to the standing water should be removed. Wet weather can cause problems with subgrade compaction.

The retaining wall should be constructed according to the current IDOT Standard Specifications for Road and Bridge Construction (2016). It is recommended that an experienced geotechnical engineer be retained to inspect the exposed subgrade, monitor earthwork operations, and provide material inspection services during the construction phase of this project.

## 6.0 QUALIFICATIONS

The analysis and recommendations submitted in this report are based upon the data obtained from the borings drilled at the locations shown on the boring logs and in Exhibit 2. This report does not reflect any variations that may occur between the borings or elsewhere on the site, variations whose nature and extent may not become evident until the course of construction. If changes are planned to the proposed improvements as described in this report, we should be timely informed so that our recommendations can be adjusted accordingly.

It has been a pleasure to assist Quigg Engineering Inc and Accurate Group, Inc. this project. Please call if there are any questions, or if we can be of further service.

Respectfully Submitted,


### WANG ENGINEERING, INC.



Mohammed Kothawala, P.E., DGE.  
Geotechnical Department Manager



Corina T. Farez, P.G., P.E.  
Vice President




Nesam S. Balakumaran, P.Eng.  
Project Geotechnical Engineer

---



## ***REFERENCES***

- AASHTO (2017) *LRFD Bridge Design Specifications*. Washington, D.C., American Association of State Highway and Transportation Officials.
- IDOT (2012) *Bridge Manual*. Illinois Department of Transportation.
- IDOT (2015) *Geotechnical Manual*, Illinois Department of Transportation.
- IDOT (2016) *Standard Specifications for Road and Bridge Construction*. Illinois Department of Transportation.
- IDOT (2017) *Culvert Manual*. Illinois Department of Transportation.
- IDOT (2019) *Supplemental Specifications and Recurring Special Provisions*. Illinois Department of Transportation


## **EXHIBITS**



Manhattan-Monee  
Road Culvert Over Drainage Ditch  
SE 1/4 of Sec. 18, NE1/4 of Sec. 19  
T34N, R11E



Will County



SITE LOCATION MAP: MANHATTAN-MONEE ROAD CULVERT OVER DRAINAGE DITCH, WILL COUNTY, ILLINOIS

SCALE: GRAPHICAL	<b>EXHIBIT 1</b>	DRAWN BY: RKC CHECKED BY: M. Kothawala
------------------	------------------	---

**Wang Engineering**  
1145 N. Main Street  
Lombard, IL 60148  
www.wangeng.com


FOR QUIGG ENGINEERING, INC.	199-02-08
-----------------------------	-----------



**Legend**

-  Soil Borings -Wang
-  Soil Borings -Others

**Scale**



BORING LOCATION PLAN: MANHATTAN-MONEE RETAINING WALL REPLACEMENT, WILL COUNTY, ILLINOIS

SCALE: GRAPHICAL

**EXHIBIT 2-1**

DRAWN BY: RKC  
CHECKED BY: NSB



1145 N. Main Street  
Lombard, IL 60148  
www.wangeng.com



FOR ACCURATE GROUP, INC.

199-02-09

Benchmark:



Existing Structure: The Structure No. 099-0441 carrying Manhattan-Monee Rd. over a ditch is a single barrel reinforced concrete box culvert with 15 degree left ahead skew. Three 24 inch corrugated plastic pipes inserted for the full length of the barrel with grout filling the void around the pipes. The barrel dimensions are 7'W x 3'H and 33'-11" out to out length along the  $\bar{C}$  culvert. There is also a corrugated metal pipe culvert running east-west below the private driveway at the southeast corner of the Structure No. 099-0441. The pipe culvert is 36"  $\bar{O}$  and 30'-0" long. Manhattan-Monee Rd. will be detoured and only open for local traffic during construction. Driveway to the private property will have a temporary runaround during culvert replacement

No salvage.




**SCOPE OF WORK:**


1. Construct a temporary runaround for the driveway just east of Structure No. 099-0441.
2. Remove the pipe culvert under the driveway.
3. Construct proposed Box Culvert under the driveway.
4. Construct proposed ditch on the south side of Manhattan-Monee Road.
5. Remove existing wingwalls and headwalls for existing Structure No. 099-0441 at both upstream and downstream ends.
6. Construct the Retaining wall at north and south side of Manhattan-Monee Road.
7. Drill holes in the roadway through the pipes and fill existing pipes with CLSM for Structure No. 099-0441.



SECTION A-A



SECTION B-B



PLAN

**Legend**

- Soil Borings -Wang
- Soil Borings -Others

**GENERAL PLAN  
MANHATTAN-MONEE ROAD CULVERT  
OVER DRAINAGE DITCH  
WILL COUNTY  
STATION 70+01.53**

BORING LOCATION PLAN: MANHATTAN-MONEE ROAD CULVERT OVER DRAINAGE DITCH, WILL COUNTY, ILLINOIS

SCALE: GRAPHICAL | **EXHIBIT 2-2** | DRAWN BY: RKC | CHECKED BY: M. Kothawala

**Wang Engineering** | 1145 N. Main Street | Lombard, IL 60148 | www.wangeng.com

FOR ACCURATE GROUP, INC. | 199-02-08

MODEL: Default  
FILE NAME: O:\Engineering\LiveProjects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\CADD Sheets\Structural\62G85-GPE.dgn



USER NAME = sapanit	DESIGNED - SAT	REVISD -
PLOT SCALE = 21.3333' / in.	CHECKED - JMT	REVISD -
PLOT DATE = 5/6/2019	DRAWN - JN	REVISD -
	CHECKED - SPS	REVISD -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION




SHEET OF SHEETS

F.A.P. RTE. 531	SECTION 2018-063-CR&D	COUNTY WILL	TOTAL SHEETS 1	SHEET NO. 1
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62G85	

Benchmark: Cut "X" in top of the concrete cap for sheet pile wall, west of box culvert.  
Elevation 702.49.

Existing Structure: The existing structure is a retaining wall located at station 71+03. The retaining wall is approximately 50'-0" long and average exposed height of the retaining wall is 4'-6". The existing wall is a gabion wall and will be removed and replaced with a proposed wall.

No salvage.




**ELEVATION-WALL NO. 1**  
(Looking at F.F. of wall)

**ELEVATION-WALL NO. 2**  
(Looking at B.F. of wall)

**ELEVATION-WALL NO. 3**  
(Looking at B.F. of wall)

**MIN BAR LAP**  
#5 Bar = 3'-7"



**LEGEND**

- Soil Borings
- F.F. Front Face
- B.F. Back Face

BORING LOCATION PLAN: MANHATTAN-MONEE RETAINING WALL REPLACEMENT, WILL COUNTY, ILLINOIS			
SCALE: GRAPHICAL	EXHIBIT 2-3	DRAWN BY: RKC CHECKED BY: NSB	
		1145 N. Main Street Lombard, IL 60148 www.wangeng.com	
FOR ACCURATE GROUP, INC.			199-02-09

MODEL: Default  
FILE NAME: Q:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\Sheets\Structural\62G85-06-GPE-Retaining Wall.dgn



	USER NAME = johnn	DESIGNED - SAT	REVISED -
	PLOT SCALE = 21.3333' / in.	CHECKED - JMT	REVISED -
	PLOT DATE = 6/5/2019	DRAWN - JN	REVISED -
		CHECKED - SPS	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SHEET S-06 OF S-08 SHEETS		ILLINOIS FED. AID PROJECT	
F.A.P. RTE. 531	SECTION 2018-063-CR&D	COUNTY WILL	TOTAL SHEETS 82 SHEET NO. 52
CONTRACT NO. 62G85			




N




Site Map Scale 1 inch equals 50 feet

### Explanation:



- Water Level Reading at time of drilling.
- Water Level Reading 24-hr after drilling or at end of drilling



Vertical Exaggeration: 2x


**Wang Engineering, Inc.**  
 1145 North Main Street  
 Lombard, IL 60148

**Subsurface Data Profile**  
**Drainage Ditch Culvert at Station 70+01.53**




Manhattan-Monee Culverts  
 Replacement  
 Will County, Illinois

JOB NUMBER	PLATE NUMBER
199-02-08	EXHIBIT 3-1




**Lithology Graphics**




Site Map Scale 1 inch equals 15 feet

**Explanation:**



- ▽ Water Level Reading at time of drilling.
- ▼ Water Level Reading 24-hr after drilling or at end of drilling



Vertical Exaggeration: 0.5x

**Wang Engineering, Inc.**  
1145 North Main Street  
Lombard, IL 60148

**Subsurface Data Profile  
Retaining Wall No. 1**





Manhattan-Monee Culverts  
Replacement  
Will County, Illinois

JOB NUMBER	PLATE NUMBER
199-02-08	EXHIBIT 3-2




N



Site Map Scale 1 inch equals 40 feet

### Explanation:



- Water Level Reading at time of drilling.
- Water Level Reading 24-hr after drilling or at end of drilling



Vertical Exaggeration: 1.5x


**Wang Engineering, Inc.**  
 1145 North Main Street  
 Lombard, IL 60148

### Subsurface Data Profile Retaining Wall No. 2




Manhattan-Monee Culverts  
 Replacement  
 Will County, Illinois

JOB NUMBER	PLATE NUMBER
199-02-08	EXHIBIT 3-3




**Lithology Graphics**




Site Map Scale 1 inch equals 45 feet

**Explanation:**



- ▽ Water Level Reading at time of drilling.
- ▼ Water Level Reading 24-hr after drilling or at end of drilling



Vertical Exaggeration: 1.5x

**Wang Engineering, Inc.**  
1145 N. Main Street  
Lombard/IL/60148

**Subsurface Data Profile  
Retaining Wall No. 3**



Manhattan-Monee Retaining Wall  
Replacement  
Will County, IL

JOB NUMBER	PLATE NUMBER
199-02-09	EXHIBIT 3-4

## **APPENDIX A**

## BORING LOG LEGEND

Relative Drilling Resistance		
RDR	Term	Criteria
1	Very Easy	No chatter, very little resistance, very fast and steady drill advance
2	Easy	No chatter, some resistance, fast and steady drill advance rate
3	Moderate	Some chatter, firm drill resistance, moderate advance
4	Hard	Frequent chatter, variable drill resistance, slow advance rate
5	Very Hard	Constant chatter, variable and very slow drill advance, nearly refusal

Proportional Terms (%)	
Trace	1-10
Little	10-20
Some	20-35
And	35-50

Coarse Gradation	
Boulder	>200mm
Cobble	200mm to 75mm
Gravel	75mm to 2mm


Relative Density of Non-Cohesive Soils	
N-Blows/12 inches	Relative Density Term
0-3	Very Loose
4-9	Loose
10-29	Medium Dense
30-49	Dense
50-80+	Very Dense

Soil Moisture Conditions	
Term	Appearance and Feel
Dry	Soil sample looks and feels powdery or dusty; no indication of moisture. Free-running granular soils.
Damp	Cohesive soils cannot be molded easily without adding water. Granular soil may not flow very easily.
Moist	Soil is near the optimum moisture content. Cohesive soils are near the plastic limit. Soil changes color slightly when exposed to air for a short period.
Wet	One may feel a high degree of moisture, yet no free water is visible. Water may become visible if the sample is squeezed. Cohesive soil appears weak and sticks to and/or stains hands. Granular soils tend to cohere.
Saturated	Applied to granular soils that have free surface water; water drains freely from the sample.

Consistency of Cohesive Soils	
Unconfined Compressive Strength $Q_u$ , tsf	Consistency Term
<0.25	Very Soft
0.25-0.49	Soft
0.50-0.99	Medium Stiff
1.00-1.99	Stiff
2.00-3.99	Very Stiff
>4.00	Hard

Rock Quality Designation (RQD)	
0-25%	Very Poor
25-50%	Poor
50-75%	Fair
75-90%	Good
90-100%	Excellent

### Sample Type Symbols

	Split Spoon (SS)		Shelby Tube (ST)
	No Recovery (NR)		In-situ Vane Shear Test
	Auger Cuttings		
	Geoprobe		
	Rock Core		

#### Drill Rig:

TMR = Truck Mouted Rig  
 ATV = All Terrain Vehicle Rig  
 [--%] = SPT Hammer Efficiency

SPT = Standard Penetration Test

$Q_u$  = Unconfined Compressive Strength Test

P = Pocket Penetrometer

S = Shear failure (Rimac)

B = Bulge failure (Rimac)

SSA = Solid Stem Auger

HSA = Hollow Stem Auger

N-Value (N-Blows/12 inches) is the sum of the second and the third SPT values



# BORING LOG CB-03

wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

WEI Job No.: 199-02-08

Client **Quigg Engineering Inc.**  
 Project **Manhattan-Monee Culverts Replacement**  
 Location **Will County, Illinois**

Datum: NAVD 88  
 Elevation: 700.71 ft  
 North: 1733502.21 ft  
 East: 1106240.81 ft  
 Station: 69+65.39  
 Offset: 19.27 RT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
	699.7	12-inch thick, brown and black SILTY CLAY LOAM, trace gravel; moist --TOPSOIL-- Medium stiff to stiff, brown and black SILTY CLAY, trace gravel; damp to moist --FILL-- --RDR 2--			1	3 4 4	1.72 B	25			--wet--			9	5 8 10	0.41 B	18
	696.7	Medium stiff, brown and gray SILTY CLAY, trace gravel, organic matter; moist to wet --RDR 2-- --L <sub>L</sub> (%)=48, P <sub>L</sub> (%)=22-- --%Gravel=2.6-- --%Sand=9.0-- --%Silt=52.6-- --%Clay=35.8--	5		2	2 3 3	0.82 B	32			--2-inch sandy gravel lens; saturated--	25		10	8 4 6	1.15 B	15
	692.7	Stiff to hard, brown SILTY CLAY, trace gravel; damp to moist --RDR 2--	10		3	2 1 2	0.66 B	55						11	6 5 12	1.39 B	19
	689.0	Medium dense, gray GRAVEL; saturated			4	4 7 7	1.48 B	28						12	3 5 11	1.97 B	19
	687.7	Loose, gray SAND; saturated			5												
	686.6	Soft to stiff, gray SILTY CLAY, trace gravel; damp to moist --RDR 2--	15		6	7 5 4	0.66 B	16									
					7	3 3 6	1.15 B	17									
					8	3 4 5	1.07 B	16									
										670.7	Boring terminated at 30.00 ft	30					

### GENERAL NOTES

### WATER LEVEL DATA

Begin Drilling **04-22-2019** Complete Drilling **04-22-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **D25 ATV [93%]**  
 Driller **N&A** Logger **E. Yim** Checked by **J. Rowells**  
 Drilling Method **2.25" HSA; boring backfilled upon completion**

While Drilling  $\nabla$  **11.75 ft**  
 At Completion of Drilling  $\nabla$  **27.00 ft**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.





wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

# BORING LOG RW-01

WEI Job No.: 199-02-08

Client: **Quigg Engineering Inc.**  
 Project: **Manhattan-Monee Culverts Replacement**  
 Location: **Will County, Illinois**

Datum: NAVD 88  
 Elevation: 700.84 ft  
 North: 1733543.84 ft  
 East: 1106299.79 ft  
 Station: 70+25.28  
 Offset: 21.06 LT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
	699.8	12-inch thick, brown to black SILTY CLAY LOAM, trace gravel; moist															
	699.5	--TOPSOIL-- Gray SILT, trace gravel; damp			1	4 12 12	1.50 P	15						9	4 7 9	1.64 B	20
	696.8	--FILL-- Stiff, brown to black SILTY CLAY LOAM, trace to little gravel; damp to moist			2	4 4 4	1.31 B	26			--<0.5-inch silty loam lens; saturated--	25		10	5 5 8	2.54 B	18
		--RDR 3 to 4-- Stiff, orange, brown and gray SILTY CLAY, trace gravel; damp to moist			3	2 3 3	1.89 B	29						11	6 5 8	1.23 B	22
		--RDR 2 to 3-- --little gravel-- --moist to wet--			4	3 4 5	1.64 B	18						12	4 5 8	2.87 B	18
	690.6	--rig chatter-- SAND; saturated								670.8	Boring terminated at 30.00 ft	30					
	689.3	Medium stiff, gray SILTY CLAY, trace gravel; moist			5	22 16 6	0.90 B	24									
	687.8	Stiff to very stiff, gray SILTY CLAY, trace gravel; damp to moist			6	5 3 5	1.31 B	16									
		--RDR 2--			7	4 5 6	1.23 B	16									
					8	3 5 7	2.38 B	17									

### GENERAL NOTES

### WATER LEVEL DATA

Begin Drilling **04-22-2019** Complete Drilling **04-22-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **D25 ATV [93%]**  
 Driller **N&A** Logger **E. Yim** Checked by **J. Rowells**  
 Drilling Method **2.25" HSA; boring backfilled upon completion**

While Drilling  $\nabla$  **10.20 ft**  
 At Completion of Drilling  $\nabla$  **30.00 ft**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.



wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

# BORING LOG RW-02

WEI Job No.: 199-02-08

Client **Quigg Engineering Inc.**  
 Project **Manhattan-Monee Culverts Replacement**  
 Location **Will County, Illinois**

Datum: NAVD 88  
 Elevation: 702.15 ft  
 North: 1733529.95 ft  
 East: 1106240.82 ft  
 Station: 69+66.02  
 Offset: 8.47 LT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
	701.93	93-inch thick ASPHALT															
	701.2	9-inch thick CONCRETE															
		Black SILTY CLAY LOAM --FILL--			1	8 3 3	NA	25						9	3 5 7	1.49 B	23
	699.2	Stiff, black SILTY CLAY LOAM, trace gravel and organics; moist --BURIED TOPSOIL--			2	2 2 3	1.00 P	37				25		10	3 6 6	1.64 B	14
	695.9	Stiff to hard, brown and gray SILTY CLAY, trace gravel; damp to wet --RDR 2--			3	1 2 2	1.07 B	37						11	5 3 6	2.05 B	19
					4	2 3 4	4.59 B	24						12	4 6 12	1.56 B	19
	690.7	SANDY GRAVEL; saturated			5	3 4 9	1.50 P	15									
	690.0	Possible SANDY GRAVEL to SAND; saturated															
	687.9	Medium stiff, gray SILTY CLAY LOAM, trace gravel; moist to wet --RDR 2--  --L <sub>l</sub> (%)=25, P <sub>L</sub> (%)=14-- --%Gravel=7.3-- --%Sand=20.6-- --%Silt=49.6-- --%Clay=22.4--			6	5 5 4	NR										
	682.9	Stiff to very stiff, gray to brownish			8	2 3 4	NR										
										672.2	Boring terminated at 30.00 ft	30					

### GENERAL NOTES

### WATER LEVEL DATA

Begin Drilling **04-19-2019** Complete Drilling **04-19-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **B57 TMR [100%]**  
 Driller **N&A** Logger **E. Yim** Checked by **J. Rowells**  
 Drilling Method **2.25" HSA; boring backfilled upon completion**

While Drilling  $\nabla$  **11.50 ft**  
 At Completion of Drilling  $\nabla$  **19.50 ft**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.

WANGENGINC 1990208.GPJ WANGENG.GDT 5/20/19



wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

# BORING LOG 3-HA-1

WEI Job No.: 199-02-09

Client **Quigg Engineering, Inc.**  
 Project **Manhattan-Monee Retaining Wall Replacement**  
 Location **Will County, IL**

Datum: NAVD 88  
 Elevation: 698.15 ft  
 North: 1733550.46 ft  
 East: 1106372.39 ft  
 Station: 70+98.00  
 Offset: 26.08 LT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
	697.7	6-inch thick, dark brown SILTY CLAY LOAM, organic matter --TOPSOIL-- --Running water on surface-- Very stiff, brown, damp SILTY CLAY			1	P C S H	2.77 B	20									
	694.6	Gray, fine to medium, saturated SAND --interbedded clay layer--			2	P C S H	3.15 B	18									
	692.2	Gray, saturated SANDY GRAVEL			3	P C S H	NP	17									
	690.2	Stiff, gray, damp SILTY CLAY			4	P C S H	NP	10									
	688.2	Boring terminated at 10.00 ft	10		5	P C S H	1.50 P	13									

### GENERAL NOTES

### WATER LEVEL DATA

Begin Drilling **06-05-2019** Complete Drilling **06-05-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **GEOPROBE**  
 Driller **M&I** Logger **I. Nenn** Checked by **Nesam. B**  
 Drilling Method **1" IDA Pneumatic Geoprobe LB Sampler**

While Drilling  $\nabla$  **DRY**  
 At Completion of Drilling  $\nabla$  **NA**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.



wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

# BORING LOG 3-HA-2

WEI Job No.: 199-02-09

Client **Quigg Engineering, Inc.**  
 Project **Manhattan-Monee Retaining Wall Replacement**  
 Location **Will County, IL**

Datum: NAVD 88  
 Elevation: 697.92 ft  
 North: 1733550.04 ft  
 East: 1106431.19 ft  
 Station: 71+56.78  
 Offset: 24.37 LT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
		Stiff to hard, brown, damp SILTY CLAY --Running water on surface--			1	P C S H	4.78 B	23									
	695.1	Saturated SANDY GRAVEL --RDR 2--			2	P C S H	1.91 B	21									
			5		3	P C S H	NP	20									
					4	P C S H	NP	22									
	690.2	Stiff, gray SILTY CLAY to SILTY CLAY LOAM, trace gravel --RDR 2--			5	P C S H	1.15 B	15									
	687.9	Boring terminated at 10.00 ft	10														
			15														
			20														

### GENERAL NOTES

### WATER LEVEL DATA

Begin Drilling **06-05-2019** Complete Drilling **06-05-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **GEOPROBE**  
 Driller **M&I** Logger **I. Nenn** Checked by **Nesam. B**  
 Drilling Method **1" IDA Pneumatic Geoprobe LB Sampler**

While Drilling  $\nabla$  **3.00 ft**  
 At Completion of Drilling  $\blacktriangledown$  **NA**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.





wangeng@wangeng.com  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

# BORING LOG 3-RWB-2

WEI Job No.: 199-02-09

Client **Quigg Engineering, Inc.**  
 Project **Manhattan-Monee Retaining Wall Replacement**  
 Location **Will County, IL**

Datum: NAVD 88  
 Elevation: 703.07 ft  
 North: 1733534.73 ft  
 East: 1106441.19 ft  
 Station: 71+66.44  
 Offset: 8.85 LT

Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)	Profile	Elevation (ft)	SOIL AND ROCK DESCRIPTION	Depth (ft)	Sample Type recovery	Sample No.	SPT Values (blw/6 in)	Qu (tsf)	Moisture Content (%)
	701.8	15-inch thick, ASPHALT --PAVEMENT--															
	700.1	Medium dense, light brown SANDY GRAVEL --AGGREGATE BASE--			1	19 21 6	NP			680.6	Stiff, gray, damp SILTY CLAY --RDR 2--			9	5 6 9	0.74 B	16
		Very stiff to hard, brown and gray, damp SILTY CLAY, trace gravel --RDR 2--	5		2	6 3 3	2.13 B	23				25		10	3 4 9	1.39 B	22
					3	5 7 9	2.00 P	20						11	3 3 5	1.31 B	22
			10		4	4 6 9	5.49 B	20						12	4 7 8	1.89 B	18
	691.6 691.3	Loose, gray, saturated GRAVEL Loose, gray, saturated SAND			5	4 5 3	NP	26									
	688.8	Medium stiff to stiff, brown and gray, damp to moist SILTY CLAY LOAM --RDR 2--			6	3 3 2	1.33 B	16		668.1	Boring terminated at 35.00 ft	35		13	4 5 6	1.89 B	18
					7	4 4 6	1.23 B	16									
			20		8	3 4 5	1.15 B	17									

### GENERAL NOTES

Begin Drilling **06-05-2019** Complete Drilling **06-05-2019**  
 Drilling Contractor **Wang Testing Services** Drill Rig **D50 TMR [78%]**  
 Driller **J&M** Logger **I. Nenn** Checked by **Nesam. B**  
 Drilling Method **3.25" HSA; boring backfilled upon completion**

### WATER LEVEL DATA

While Drilling  $\nabla$  **11.50 ft**  
 At Completion of Drilling  $\nabla$  **25.00 ft**  
 Time After Drilling **NA**  
 Depth to Water  $\nabla$  **NA**

The stratification lines represent the approximate boundary between soil types; the actual transition may be gradual.

SN 099-0441



**Professional Service Industries, Inc.**  
A & H Flood Engineering

Sh. 1 of 1 Sh.

**FOUNDATION BORING LOG**

PROJECT 152-05020 Date March 28, 1990

ROUTE Manhattan-Monee Road Bored By \_\_\_\_\_

SEC. \_\_\_\_\_ STA. 94+72 11' Left Checked By \_\_\_\_\_


COUNTY Will  
Boring No. B-4  
Station 94+72  
Offset 11' left

Elevation	BLOWS	Qu t/s.f.	w(%)	Surface Water El.	Groundwater El. at Completion	Elevation	BLOWS	Qu t/s.f.
101.70	0							
100.87								
	10	3.5p	35					
	11							
	12	1.8b						
97.20								
	4	2.5p	21					
	6							
	7	2.0s						
94.70								
	4	2.5p	25					
	4							
	5							
92.20								
	5	4.5+P	21					
	10							
	14	5.0s						
89.70								
	8	3.5p	16					
	12							
	16	4.8s						
87.20								
	5	4.5+P	17					
	9							
	8	3.2b						
84.70								
	5	2.0p	18					
	7							
	8	1.1b						
	9	1.0p	20					
	7							
	7							

Ground Surface 101.70 0  
 4" + Asphalt over 6" + crushed stone 100.87  
 Stiff to very stiff black CLAY with gravel and organics  
 Very stiff black, orange-brown and gray silty CLAY with gravel and organics  
 Very stiff black, greenish-gray and brown silty CLAY  
 Hard brown silty CLAY  
 Very stiff to hard gray silty CLAY  
 Very stiff to hard grayish brown silty clay  
 Stiff gray CLAY

Stiff gray CLAY  
 Stiff to very stiff grayish brown silty CLAY  
 Stiff gray silty CLAY  
 Boring terminated at 36.5' below existing grade

## **APPENDIX B**



COBBLES	GRAVEL	SAND		SILT AND CLAY
		coarse	fine	

Specimen Identification		IDH Classification	LL	PL	PI	Cc	Cu
●	CB-03#3 6.0 ft	<b>Silty Clay</b>	48	22	26		
☒	RW-02#7 16.0 ft	<b>Silty Clay Loam</b>	25	14	11		


Specimen Identification		D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
●	CB-03#3 6.0 ft	4.75	0.007			2.6	9.0	52.6	35.8
☒	RW-02#7 16.0 ft	12.5	0.025	0.004		7.3	20.6	49.6	22.4



Wang Engineering, Inc.  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938

**GRAIN SIZE DISTRIBUTION**  
 Project: Manhattan-Monee Culverts Replacement  
 Location: Will County, Illinois  
 Number: 199-02-08

WEI GRAIN SIZE IDH 1990208.GPJ US LAB.GDT 5/16/19



COBBLES	GRAVEL	SAND		SILT AND CLAY
		coarse	fine	

Specimen Identification	IDH Classification	LL	PL	PI	Cc	Cu
● 3-RWB-1#3 6.0 ft	Clay	42	20	22		

Specimen Identification	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
● 3-RWB-1#3 6.0 ft	9.5	0.006			0.9	12.0	47.0	40.1



Wang Engineering, Inc.  
 1145 North Main Street  
 Lombard, IL 60148  
 Telephone: 630-953-9928  
 Fax: 630-953-9938



**GRAIN SIZE DISTRIBUTION**  
 Project: Manhattan-Monee Retaining Wall Replacement  
 Location: Will County, IL  
 Number: 199-02-09

WEI GRAIN SIZE IDH 1990209.GPJ US LAB.GDT 6/21/19






## **APPENDIX C**



Undrained Analysis, Retaining Wall No. 1, Ref Borings: CB-03 and RW-02

Layer ID	Description	Total Unit Weight (pcf)	Undrained Cohesion (psf)	Undrained Friction Angle (degrees)
1	Medium Stiff to Stiff SI Clay (Fill)	120	1300	0
2	Medium Stiff SI Clay	115	700	0
3	Stiff to Hard SI Clay	120	1500	0
4	M Dense SA to Gravel	115	0	30
5	Soft to Stiff SI Clay	120	1100	0

GLOBAL STABILITY ANALYSIS: MANHATTAN-MONEE ROAD CULVERT OVER DRAINAGE DITCH, WILL COUNTY, ILLINOIS		
SCALE: GRAPHICAL	APPENDIX C-1	DRAWN BY: RKC CHECKED BY: M. Kothawala
		1145 N. Main Street Lombard, IL 60148 www.wangeng.com
		FOR ACCURATE GROUP, INC.
		199-02-08



Drained Analysis, Retaining Wall No. 1, Ref Borings: CB-03 and RW-02

Layer ID	Description	Total Unit Weight (pcf)	Drained Cohesion (psf)	Drained Friction Angle (degrees)
1	Medium Stiff to Stiff SI Clay (Fill)	120	100	30
2	Medium Stiff SI Clay	115	0	28
3	Stiff to Hard SI Clay	120	100	30
4	M Dense SA to Gravel	120	0	30
5	Soft to Stiff SI Clay	120	100	30


GLOBAL STABILITY ANALYSIS: MANHATTAN-MONEE ROAD CULVERT OVER DRAINAGE DITCH, WILL COUNTY, ILLINOIS		
SCALE: GRAPHICAL	APPENDIX C-2	DRAWN BY: RKC CHECKED BY: M. Kothawala
		1145 N. Main Street Lombard, IL 60148 www.wangeng.com
		FOR ACCURATE GROUP, INC. 199-02-08

## **APPENDIX D**

Benchmark: Cut "X" in top of the concrete cap for sheet pile wall, west of box culvert.  
Elevation 702.49.

Existing Structure: The Structure No. 099-0441 carrying Manhattan-Monee Rd. over a ditch is a single barrel reinforced concrete box culvert with 15 degree left ahead skew. Three 24 inch corrugated plastic pipes inserted for the full length of the barrel with grout filling the void around the pipes. The barrel dimensions are 7'W x 3'H and 33'-11" out to out length along the  $\bar{C}$  culvert. There is also a corrugated metal pipe culvert running east-west below the private driveway at the southeast corner of the Structure No. 099-0441. The pipe culvert is 36"  $\bar{O}$  and 30'-0" long. Manhattan-Monee Rd. will be detoured and only open for local traffic during construction. Driveway to the private property will have a temporary runaround during culvert replacement

No salvage.




**INDEX OF SHEETS**

- S-1. General Plan - Culvert
- S-2. General Notes and Total Bill of Materials
- S-3. Culvert Details
- S-4. Wingwall Details
- S-5. Soil Borings - I
- S-6. General Plan - Retaining Walls
- S-7. Retaining Wall Details
- S-8. Soil Borings - II

**SCOPE OF WORK:**

1. Construct a temporary runaround for the driveway just east of Structure No. 099-0441.
2. Remove the pipe culvert under the driveway.
3. Install Temporary Sheet Piling as shown on the plans.
4. Construct proposed Box Culvert under the driveway.
5. Construct proposed ditch on the south side of Manhattan-Monee Road.
6. Remove existing wingwalls and headwalls of existing Structure No. 099-0441 at both upstream and downstream ends.
7. Construct the Retaining wall along north and south side of Manhattan-Monee Road.
8. Fill 3 pipes of Structure No. 099-0441 with CLSM.



**DESIGN SPECIFICATIONS**

2017 AASHTO LRFD Bridge Design Specifications, 8th Edition

**DESIGN STRESSES**

**FIELD UNITS**


$f'_c = 3,500$  psi  
 $f_y = 60,000$  psi (Reinforcement)  
 $f_y = 50,000$  psi (M270 Grade 50)

**PRECAST UNITS**


$f'_c = 5,000$  psi  
 $f_y = 60,000$  psi (Reinforcement)  
 $f_y = 65,000$  psi (Welded Wire Fabric)

**LOADING HL-93**


Allow 50#/sq. ft. for future wearing surface.



**SECTION A-A**




**SECTION B-B**



**LOCATION SKETCH**

**LEGEND**

◆ Soil Borings



**PLAN**

**GENERAL PLAN  
MANHATTAN-MONEE ROAD  
DRIVEWAY CULVERT  
OVER DRAINAGE DITCH  
WILL COUNTY  
STATION 69+96.82**

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


USER NAME = sapani	DESIGNED - SAT	REVISD -
PLOT SCALE = 21.3333' / in.	CHECKED - JMT	REVISD -
PLOT DATE = 6/19/2019	DRAWN - JN	REVISD -
	CHECKED - SPS	REVISD -

SHEET S-01 OF S-08 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	47
CONTRACT NO. 62G85				
ILLINOIS FED. AID PROJECT				

MODEL: Default  
FILE NAME: Q:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\Sheet\Structural\62G85-01-GPE\_Culvert.dgn  
6/19/2019 11:55:51 AM





**LONGITUDINAL SECTION**  
(Looking East)


**END VIEW**

Fill existing PVC pipes with CLSM after construction of proposed ditch on the south side of the Manhattan-Monee Rd.

**LEGEND**

- Concrete Removal
- Guardrail Removal  
(See Roadway Plans for quantity)

**EXISTING STRUCTURE DETAILS**




**SECTION THRU CULVERT**

\*\* Over Excavation beyond the limits of structure excavation. This area will not be measured for payment. (Typ.)

Remove unsuitable material and replace with Rock Fill, See Special Provisions

\*\* Backfill the over excavation beyond the limits of structure excavation with material specified for roadway embankment per Section 205 of Standard Specifications.




**SECTION THRU CULVERT**

**GENERAL NOTES**

1. All excavation required for construction of the culvert as shown in these plans and in accordance with the Standard Specifications shall be included in the cost for Concrete Box Culverts.
2. Reinforcement bars designated (E) shall be epoxy coated.
3. Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.
4. Concrete Sealer shall be applied to the top and outside face of the horizontal cantilever wingwalls and to the exposed concrete for the concrete cap of the sheet pile wall.
5. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
6. The Contractor shall be responsible to divert the stream flow during construction to keep construction area free of water. The method of water diversion shall be subject to the approval of the Engineer and the cost shall be included in the cost for Concrete Box Culverts.

**TOTAL BILL OF MATERIAL**  
(Culvert and Retaining Walls)

ITEM	UNIT	TOTAL
Stone Riprap, Class A4	Sq Yd	164
Filter Fabric	Sq Yd	164
Concrete Removal	Cu Yd	19.7
Pipe Culvert Removal	Foot	30
Structure Excavation	Cu Yd	32.8
Removal and Disposal of Unsuitable Material for Structures	Cu Yd	45
Concrete Structures	Cu Yd	12.9
Stud Shear Connectors	Each	234
Reinforcement Bars, Epoxy Coated	Pound	6,640
Temporary Sheet Piling	Sq Ft	689
Permanent Sheet Piling	Sq Ft	2,135
Concrete Box Culverts	Cu Yd	27.5
Granular Backfill for Structures	Cu Yd	32.8
Concrete Sealer	Sq Ft	614
Controlled Low Strength Material	Cu Yd	12
Membrane Waterproofing System for Buried Structures	Sq Yd	42
Gabion Removal	Cu Yd	29
Rock Fill	Cu Yd	45



**TEMPORARY SHEET PILING DETAILS**

Minimum Section Modulus = 4.63 in<sup>3</sup>/ft

MODEL: Default  
FILE NAME: Q:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\CADD Sheets\Structural\62G85-02-General Notes and Bill of Material.dgn




USER NAME =	sapant	DESIGNED -	SAT	REVISED -	
CHECKED -	JMT	REVISIONS -			
PLOT SCALE =	21.3333 1/8"	DRAWN -	JN	REVISED -	
PLOT DATE =	6/19/2019	CHECKED -	SPS	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GENERAL NOTES AND TOTAL BILL OF MATERIAL  
MANHATTAN-MONEE ROAD OVER UN-NAMED DITCH**

SHEET S-02 OF S-08 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	48
			CONTRACT NO. 62G85	
		ILLINOIS FED. AID PROJECT		




**SE WINGWALL**

(Showing Reinforcement)  
SW Wingwall Similar


**LONGITUDINAL SECTION**

**SW WINGWALL**

(Showing Dimensions)  
SE Wingwall Similar




UPSTREAM




DOWNSTREAM

**SECTION THRU HEADWALL**




**SECTION THRU BARREL**




**SHOWING TOEWALL**

**PLAN**


**SHOWING HEADWALL**




**SECTION A-A**




**BAR s(E)**




**BAR s1(E)**



**BAR a1(E)**



**BAR d(E)**



**BARS h3(E) & h4(E)**

Notes:  
A distance of half the length of the wingwall but not less than six feet of the barrel shall be poured monolithically with the wingwalls.

MODEL: Default  
FILE NAME: Q:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\CADD Sheets\Structural\62G85-03-Culvert Details.dgn



USER NAME =	sapant	DESIGNED -	SAT	REVISED -	
CHECKED -	JMT	REVISIONS			
PLOT SCALE =	21.3333' / in.	DRAWN -	JN	REVISED -	
PLOT DATE =	6/19/2019	CHECKED -	SPS	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**CULVERT DETAILS  
MANHATTAN-MONEE ROAD OVER UN-NAMED DITCH**

SHEET S-03 OF S-08 SHEETS


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	49
CONTRACT NO. 62G85				
ILLINOIS FED. AID PROJECT				

**BILL OF MATERIAL**


Bar	No.	Size	Length	Shape
a1(E)	167	#6	6'-0"	
a2(E)	79	#5	5'-8"	
d(E)	14	#4	4'-5"	
h(E)	28	#5	38'-8"	
h1(E)	10	#4	38'-8"	
h2(E)	8	#7	5'-8"	
h3(E)	24	#5	8'-0"	
h4(E)	24	#5	10'-6"	
h5(E)	8	#5	10'-3"	
h6(E)	9	#5	8'-0"	
h7(E)	18	#5	11'-9"	
h8(E)	9	#5	13'-3"	
s(E)	7	#4	4'-10"	
s1(E)	7	#4	4'-8"	
v(E)	84	#4	5'-4"	
v1(E)	59	#4	8'-3"	
Concrete Box Culverts			Cu. Yd.	27.5
Reinforcement Bars, Epoxy Coated			Pound	5,140
Concrete Sealer			Sq. Ft.	164




**NW WINGWALL ELEVATION**




**NE WINGWALL ELEVATION**




**NW WINGWALL PLAN**




**SECTION B-B**




**NE WINGWALL PLAN**



**SECTION C-C**



**BARS h5(E) & h6(E)**



**BARS h7(E) & h8(E)**

Notes:  
See Sheet S-03 of S-08 for culvert details, SE and SW wingwall details.  
See Sheets S-06 and S-07 of S-08 for Permanent Sheet Pile Details.

MODEL: Default  
FILE NAME: C:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\CADD Sheets\Structural\62G85-04-Wingwall\_Details.dgn



USER NAME =	sapant	DESIGNED -	SAT	REVISED -	
CHECKED -	JMT	REVISED -		REVISED -	
PLOT SCALE =	21.3333' / in.	DRAWN -	JN	REVISED -	
PLOT DATE =	6/19/2019	CHECKED -	SPS	REVISED -	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**WINGWALL DETAILS  
MANHATTAN-MONEE ROAD OVER UN-NAMED DITCH**


SHEET S-04 OF S-08 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	50
CONTRACT NO. 62G85				
ILLINOIS FED. AID PROJECT				


Benchmark: Cut "X" in top of the concrete cap for sheet pile wall, west of box culvert.  
Elevation 702.49.

Existing Structure: The existing structure is a retaining wall located at station 71+03. The retaining wall is approximately 50'-0" long and average exposed height of the retaining wall is 4'-6". The existing wall is a gabion wall and will be removed and replaced with a proposed wall.


No salvage.



**ELEVATION-WALL NO. 1**  
(Looking at F.F. of wall)




**ELEVATION-WALL NO. 2**  
(Looking at B.F. of wall)



**ELEVATION-WALL NO. 3**  
(Looking at B.F. of wall)

**MIN BAR LAP**  
#5 Bar = 3'-7"



**LEGEND**

- ◆ Soil Borings
- F.F. Front Face
- B.F. Back Face

**GENERAL PLAN NO. 1, NO. 2 & NO. 3**  
**RETAINING WALLS ALONG**  
**MANHATTAN-MONEE ROAD**  
**WILL COUNTY**  
**STATION 69+50, 69+84.75 & 71+03**

MODEL: Default  
FILE NAME: Q:\Engineering\LiveProjects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\Sheet\Structural\62G85-06-GPE-Retaining Wall.dgn  
6/19/2019 11:56:03 AM




USER NAME =	sapant	DESIGNED -	SAT	REVISED -	
PLOT SCALE =	21.3333' / in.	CHECKED -	JMT	REVISED -	
PLOT DATE =	6/19/2019	DRAWN -	JN	REVISED -	
		CHECKED -	SPS	REVISED -	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**


SHEET S-06 OF S-08 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	52
CONTRACT NO. 62G85				
ILLINOIS FED. AID PROJECT				


MODEL: Default  
 FILE NAME: Q:\Engineering\Live\Projects\13043\_IDOT DUR AES\Work Order 15 - 62G85\CADD\CADD Sheets\Structural\62G85-07-Retaining Wall Details.dgn




**PROPOSED TYPICAL SECTION**  
 (Looking East)



**PLAN VIEW SHEAR STUDS**




**TYPICAL SECTION THRU WALL**



**DETAIL A**

Note: The cost of the Fabric Reinforced Elastomeric Mat, Geosynthetic Filter Fabric and 1/2" P.J.F. is included in the cost of Concrete Structures.



**BAR u(E)**

**NOTE:**

B.F. denotes Back Face  
 F.F. denotes Front Face

**GENERAL NOTES:**

1. Bars indicated thus 3x2-#5 etc. indicates 3 lines of bars with 2 lengths per line.
2. See Sheet S-06 of S-08 for reinforcement layout for concrete cap.
3. Wall stations, offsets and dimensions are measured at front face of wall.
4. Shear Connectors shall be 3/4" x 8" long granular or solid flux filled headed connectors automatically end welded in field to sheet piling.
5. The details for the concrete cap, reinforcement and required number of shear connectors are based on Section PZ 22 sheet piling. If the Contractor chooses to use any other section, the Contractor shall submit revised configuration for approval by the Engineer. Such changes shall not be cause for additional compensation.
6. For Boring Logs see sheets S-05 and S-08 of S-08.

**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
h9(E)	6	#5	22'-8"	—
h10(E)	6	#5	29'-8"	—
h11(E)	12	#5	26'-5"	—
h12(E)	6	#5	20'-8"	—
u(E)	114	#5	4'-9"	□
v(E)	7	#5	8'-4"	—
Concrete Structures			Cu. Yd.	12.9
Stud Shear Connectors			Each	234
Reinforcement Bars, Epoxy Coated			Pound	1,500
Permanent Sheet Piling			Sq. Ft.	2,135
Concrete Sealer			Sq. Ft.	450



USER NAME =	sapant	DESIGNED -	SAT	REVISED -	
		CHECKED -	JMT	REVISED -	
PLOT SCALE =	21.3333' / in.	DRAWN -	JN	REVISED -	
PLOT DATE =	6/19/2019	CHECKED -	SPS	REVISED -	

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**RETAINING WALL DETAILS  
 MANHATTAN-MONEE ROAD OVER UN-NAMED DITCH**

SHEET S-07 OF S-08 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
531	2018-063-CR&D	WILL	82	53
CONTRACT NO. 62G85				
ILLINOIS FED. AID PROJECT				