

62934

• (1516.1, 1717 & 1818) I-5

INDEX OF SHEETS

SHEET NO.	TITLE				
1	COVER SHEET				
2	INDEX OF SHEETS, INDEX OF STATE STANDARDS, GENERAL NOTES, CALENDAR OF CONSTRUCTION WORK, & COMMITMENTS				
3 - 4	SUMMARY OF QUANTITIES				
5	67TH STREET - MEDIAN PLANTING BED WATER SERVICE PLAN & MEDIAN SECTION				
6	67TH STREET - LANDSCAPING PLAN AND SCHEDULE OF LANDSCAPE ITEMS				
7	75TH AND 76TH STREET - TYPICAL SECTIONS				
8	75TH AND 76TH STREET - ALIGNMENT AND TIES				
9	76TH AND 75TH STREET - MAINTENANCE OF TRAFFIC - NOTES AND TYPICAL SECTIONS				
10	75TH STREET - MAINTENANCE OF TRAFFIC				
11 - 12	75TH AND 76TH STREET - MEDIAN PLANS				
13 - 14	75TH AND 76TH STREET - MEDIAN PLANTERS NO. 1, 2, 3 AND 4				
15 - 16	75TH AND 76TH STREET - CONSTRUCTION DETAILS				
17	MEDIAN PLANTERS - STANDARD METER VAULTS AND WATER SERVICE INSTALLATION DETAILS				
18 - 19	PLANTING BEDS - LANDSCAPING PLAN DETAIL				
20	TC-14 DIST 1, TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)				
20A	TC-22 DIST 1, ARTERIAL ROAD INFORMATION SIGN				
21 - 22	TC-24 DIST 1, CITY OF CHICAGO TYPICAL PAVEMENT MARKINGS				

STATE STANDARDS

SHEET NO.	TITLE
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
606001- <i>0</i> 3	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
606306-02	CORRUGATED PC CONCRETE MEDIANS
701601- <i>05</i>	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606- <i>05</i>	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701- <i>05</i>	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901	TRAFFIC CONTROL DEVICES

CALENDAR OF CONSTRUCTION WORK

		WORK DATES		
PHASE	YEAR	FROM	ТО	CONSTRUCTION WORK
PHASE I	2008	JUNE 16 SEPT. 30		REMOVAL OF PAVEMENT (75TH ST PLANTERS) AND CONCRETE MEDIAN
				SURFACE (SPECIAL) (67TH ST PLANTER). INSTALLATION OF CONCRETE
				MEDIAN WALL (75TH ST PLANTERS), CONCRETE MEDIAN SURFACE, CORRUGATED (75TH ST PLANTERS), AND CONCRETE MEDIAN SURFACE
		1		(SPECIAL) (67TH ST AND 75TH ST PLANTERS).
		ŀ		EXCAVATION AND PLACEMENT OF POROUS GRANULAR MATERIAL. GEOTECHNICAL
				FABRIC, AND PLANTING MIX (75TH ST PLANTERS). INSTALLATION OF WATER
				SERVICE ITEMS, IRRIGATION SYSTEMS, AND MULCH (ALL PLANTERS).
		AUG. 15	SEPT. 30	INSTALLATION OF ALL WOODY PLANTS, WOODY PLANTS MUST BE
				CONTAINER OR DUG WHILE DORMANT AND MAINTAINED PROPERLY
				UNTIL PLANTED, ALL WOODY PLANTS MUST BE INSTALLED PRIOR
				TO PERENNIALS.
		AUG. 15	SEPT. 30	INSTALL PERENNIAL PLANTS AFTER ALL WOODY PLANTS HAVE BEEN
				INSTALLED.
		OCT. 15	NOV. 15	INSTALL BULBS.
		NOV. 20		CERTIFICATION TO THE BUREAU OF MAINTENANCE THAT ALL PLANTS
				HAVE BEEN INSTALLED AND ARE IN A LIVE HEALTHLY CONDITION
PHASE I	2008			AND ELIGIBLE FOR A MAY 1 - MAY 7, 2009 PERIOD OF ESTABLISHMENT INSPECTION.
THASE I	2000			INSI ECTION.
1	YEAR	WORK DATES		
PHASE				CONSTRUCTION WORK
	4.0	FROM	T0	
PHASE II	2009	MARCH 3	APRIL 30	PERIOD OF ESTABLISHMENT. PLANT CARE REQUIRED FOR ALL PLANTS.
		5r		(WEEDING, WATERING, OR OTHER WORK WHICH IS NECESSARY TO
				MAINTAIN HEALTH AND SATISFACTORY APPEARANCE OF THE PLANTING
				IS INCLUDED IN THE COST OF THE INDIVIDUAL ITEMS).
		MAY 1	MAY 7	PERIOD OF ESTABLISHMENT INSPECTION
1		MAY 8	MAY 31	INSTALLATION OF ALL REQUIRED REPLACEMENT PLANTS, AND ALL
				REQUIRED CLEAN UP OF ALL PLANT BEDS SHALL BE COMPLETED
DUAGE ##		MAY 31		BY THIS DATE.
PHASE II	2009 2009		7 31 E 15	COMPLETION DATE
L	2009	L JUN	L 12	FINAL INSPECTION DATE

GENERAL NOTES:

- 1. THE CONTRACTOR SHALL NOT SET UP A YARD OR FIELD OFFICE ON IDOT PROPERTY WITHOUT WRITTEN PERMISSION FROM IDOT.
- 2. THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- 3. NIGHT OPERATIONS: SHALL NOT BE ALLOWED.
- 4. ALL ELEVATIONS SHOWN ARE BASED ON THE CHICAGO CITY DATUM OF 0.00, WHICH IS 579.48 FEET ABOVE MEAN TIDE NEW YORK.
- 5. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- 6. PLANS FOR THE WATER SERVICE CONNECTIONS FOR IRRIGATION SYSTEMS SHALL BE SUBMITTED FOR REVIEW AND APPROVALTO:

MR. JOHN FLYNN, DEPARTMENT OF CONSTRUCTION AND PERMITS, ROOM 906, CITY HALL, 121 NORTH LASALLE STREET, CHICAGO. ILLINOIS 60602.

- 7. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY TRAFFIC CONTROL DEVICES NEEDED TO COMPLETE THE WORK. THIS WORK SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION (SPECIAL).
- 8. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FROM THE CITY OF CHICAGO AND THE STATE OF ILLINOIS PRIOR TO COMMENCING CONSTRUCTION. THE COSTS SHALL BE INCLUDED IN THE COST OF MOBILIZATION.
- PAYMENTS FOR ADJUSTMENTS TO WATER VALVE VAULTS SHALL NOT BE MADE TO THE CONTRACTOR UNTIL THIS WORK HAS BEEN INSPECTED AND APPROVED BY THE CITY OF CHICAGO DEPARTMENT OF WATER MANAGEMENT.
- 10. PERMITS FROM THE DEPARTMENT OF WATER MANAGEMENT ARE REQUIRED FOR ALL WORK INVOLVING ADJUSTMENT OF STRUCTURES. THE DEPARTMENT OF WATER MANAGEMENT'S PERMIT SHALL BE OBTAINED BY A LICENSED SEWER DRAIN LAYER PRIOR TO START OF CONSTRUCTION. THE LICENSED SEWER CONTRACTOR SHALL SUBMIT TWO SETS OF PLANS APPROVED BY THE DEPARTMENT OF WATER MANAGEMENT FOR THE ISSUANCE OF THE SEWER PERMIT TO BUREAU OF ENGINEERING SERVICES-SEWER SECTION, JARDINE PURIFICATION PLANT, EL+51, ROOM 313, 1000 E. OHIO ST., CHICAGO, IL 60611. INSPECTION WILL BE PROVIDED BY THE DEPARTMENT OF WATER MANAGEMENT.
- 11. CITY OF CHICAGO WATER VALVE VAULTS AND SEWER STRUCTURES SHALL NOT BE CLOSED, COVERED OR OTHERWISE OBSTRUCTED DURING CONSTRUCTION WITHOUT WRITTEN PERMISSION FROM THE CITY OF CHICAGO DEPARTMENT OF WATER MANAGEMENT.
- 12. THE RESIDENT ENGINEER AND THE CONTRACTOR SHALL FIELD VERIFY THE CITY'S EXISTING SEWER FACILITIES IN THE LIMITS OF THE REFERENCED PROJECT FOR ANY CONFLICTS DUE TO THE PROPOSED IMPROVEMENT. ANY CONFLICT SHOULD BE RESOLVED WITH THE DEPARTMENT OF WATER MANAGEMENT PRIOR TO START OF CONSTRUCTION.
- 13. IT IS CALLED TO THE CONTRACTOR'S ATTENTION THAT HE/SHE WILL BE REQUIRED TO PAY FOR ANY INSPECTION OR PERMIT FEES TO THE VARIOUS DEPARTMENTS OF THE CITY OF CHICAGO. THE COST FOR THESE FEES WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE COST OF MOBILIZATION. PERMIT FEES SHALL BE PAID PRIOR TO COMMENCING CONSTRUCTION.
- 14. A "BOXED" NOTE INDICATES AN ITEM OF WORK THAT IS NOT PAID FOR SEPARATELY, BUT IS PAID FOR AS PART OF ANOTHER ITEM LISTED IN THE SUMMARY OF QUANTITIES.

SPECIAL COMMITMENTS:

- THE CONTRACTOR AND THE ENGINEER SHALL SUBMIT THE IRRIGATION SHOP DRAWINGS FOR REVIEW AND APPROVAL BY THE CITY OF CHICAGO - STREETSCAPE UNIT, 4 WEEKS IN ADVANCE, PRIOR TO THE START OF THE IRRIGATION WORK.
- 2. THE CITY OF CHICAGO STREETSCAPE UNIT REPRESENTATIVES SHALL BE INVITED TO PARTICIPATE IN THE CONSTRUCTION PROGRESS MEETINGS. THE MEETING'S SCHEDULE SHALL BE PROVIDED TO THE CITY OF CHICAGO IN ADVANCE.
- 3. THE CITY OF CHICAGO STREETSCAPE UNIT REPRESENTATIVES SHALL BE AFFORDED THE OPPORTUNITY TO OBSERVE ALL LANDSCAPING AND IRRIGATION WORK IN COORDINATION WITH AND CONCURRENCE OF THE ENGINEER.
- 4. THE CONTRACTOR AND THE ENGINEER, IN COORDINATION WITH ILLINOIS DEPARTMENT OF TRANSPORTATION'S LANDSCAPING REPRESENTATIVE, SHALL PROVIDE A WRITTEN DESCRIPTION OF THE TURN OVER PROCEDURE OF THE IRRIGATION WORK AT THE END OF THE PROJECT TO THE CITY OF CHICAGO STREETSCAPE UNIT.
- 5. THE CITY OF CHICAGO STREETSCAPE UNIT SHALL BE INVITED BY THE CONTRACTOR AND THE ENGINEER TO ATTEND AND PARTICIPATE IN THE FINAL PROJECT INSPECTION.

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION			
NAME DATE	ILLINOIS DEFARTMENT OF TRANSPORTATION			
	F.A.I. 94 (D/	N RYAN EXPRESSWAY)		
	INDEX O	F SHEETS. INDEX OF		
	J STATE STAN	DARDS, GENERAL NOTES,		
	CALENDAR O	F CONSTRUCTION WORK,		
	l e	COMMITMENTS		
	A COMMITMENTS			
	SCALE, NONE	DRAWN BY. IDE		

TYLININTERNATIONAL

SCALE: NONE DRAWN BY: JDF
DATE: JANUARY 30, 2008 CHECKED BY: JPM