

 $\sim$ 

F.A.I. SECTIO	N	COUNTY		TOTAL SHEETS	SHEET NO.
94/90 •		COOK		29	17
STA.	TO STA.				
FED. ROAD DIST. NO.	ILLINOIS	FED.	AID	PROJECT	•
62993		• 232	4.6-	1P-I-1	

## DETAIL C REINFORCEMENT SCHEDULE AND BILL OF MATERIAL

	0	A/-	Cime	1	China
	Bar	No.	Size	Length	Shape
	h(E)	8	#4	14'-8"	
	n(E)	16	#6	5'-6"	L
	n1(E)	<i>1</i> 6	#5	5'-10"	L
	w(E)	4	#4	14'-8"	
	Item			Unit	Qty.
1	Concrete Structures			Cu. Yd.	2.3
2	Concrete Superstructure			Cu. Yd.	2.0
	Reinforcement Bars, Epoxy Coated			Pound	350
	Rustication Finish			Sq. Ft.	16
	Protective Coat			Sq. Yd.	10

Varies 1'-6" to 1'-1"

— Curb and Gutter 

## NOTES:

- 1. All stations and offsets measured from S. La Salle St. B.
- 2. Concrete: f'c = 3500 psi
- Provide California Finish on top of foundation between stem and Frontage Road. See Roadway Details.
- 4. At locations where Fluted Knee Wall abuts a rigid Structure, a 1" thick Preformed Expansion Joint Filler conforming to the shape of the Structure shall be installed between the Wall and the Structure.
- Apply Protective Coat to top and front face of stem and top of Frontage Road side of foundation.
- 6. For Fluted Knee Wall standard details, see Sheet SD-1
- 7. B.F. = Back Face (Frontage Road Side) F.F. = Front Face (Expressway Side) E.F. = Each Face
- Shape finished grade as required to match existing conditions.
- 9. P.J.F. included in cost of concrete structures.

			SHEET SD-4				
REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION					
NAME	DATE						
REVISED	3-6-08	F.A.I. 94/90 (D	AN RYAN EXPRESSWAY)	ΡM			
		NORTHBOUND KNEE	WALLS (35TH ST TO 33RD ST)	1:24:27			
				12			
	ETAIL C						
				8			
		SCALE: N.T.S.	DRAWN BY: LAM	120			
		DATE: 03/06/08	CHECKED BY: BLU	376			