GENERAL NOTES

Tree planting layout shall be performed by the District Landscape Architect. Mulch shall be placed 4" thick in a 5 foot diameter around the tree. The mulch shall be hardwood wood chips placed on weed barrier fabric. This work shall be included in the cost of the tree.

Right-of-way markers will be erected with the back face of the marker on the right-of-way line unless the new right-ofway line has been surveyed and pinned, in which instance the right-of-way markers will be erected 300 mm (12 inches) inside the new right-of-way line.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

American Natural Resources Pipeline Co.Cambridge TelephoneAmeren IPCorn Belt Energy Corp.

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date + 135 days.

Work on this project will be in progress at the same time as work on the box culvert removal and replacement on IL 81. Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files <u>ONLY</u>. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

Temporary Fencing shall be used to protect the golf course from work zone activities at locations shown on the plans. The temporary fence will conform to SSR&BC, Article 201.05(a) and will be paid for at the contract unit price per Foot for TEMPORARY FENCE.

COMMITMENTS

1.

2.

Program #5 (Arch. Size) Enlarge 200% Enlarge 107

A commitment has been made to not disturb the tee box located within the temporary easement.

The Department will construct a 24' wide field entrance at Sta. 436+70 Rt. The commitment was made by the project technician.

1. C.	COUNTY	TOTAL SHEETS	SHEET NO.
138T	Henry	42	6
ILLINOIS	PROJECT		
			138T Henry 42

GENERAL NOTES