


## POST BASE PLATE DETAIL

(Included in the cost of Handrail)



(Included in the cost of Handrail)

## **GENERAL NOTES:**

ALL HANDRAIL DIMENSIONS SHALL BE VERIFIED BY CONTRACTOR PRIOR TO FABRICATION OF PIPE HANDRAIL, BASED UPON FINAL LOCATION OF MOUNTING BOLTS.

HANDRAIL SHALL CONFORM TO SECTION 509 WITH THE EXCEPTION THAT ALL PIPE AND CONNECTIONS SHALL BE WELDED GALVANIZED OR ALUMINUM ACCORDING TO ARTICLE 1006.27, 1006.30, OR 1006,34.

THE DIAMETER OF THE GRIPPING SURFACE OF THE HANDRAIL SHALL BE 1-1/4" TO 1-1/2"  $\,$ 

ENDS OF HANDRAIL SHALL BE ROUNDED.

HAND & SAFETY RAILS SHALL NOT ROTATE WITHIN THEIR FITTINGS.

GRIPPING SURFACES SHALL BE UNINTERRUPTED BY NEWEL POSTS, OTHER CONSTRUCTION ELEMENTS, OR OBSTRUCTIONS.

THE CONTRACT UNIT PRICE "FOOT" FOR PIPE HANDRAIL SHALL INCLUDE THE PIPE, ANCHOR RODS, ANCHOR BOLTS, BOLTS, NUTS, WASHERS, AND STEEL BASE PLATES.

## COOMBE-BLOXDORF P.C.

Engineers / Land Surveyors
Springfield, Illinois
Design Firm License No. 184-002703

FILE NAME =	USER NAME = CFC-ns	DESIGNED -	REVISED -								F.A.S	SECTION	COUNTY	TOTAL	SHEET
\07\07075\v8-ns\zil306spll.dgn	PLOT SCALE = 50.0000 '/ IN. PLOT DATE = 01/21/2008	DRAWN - CHECKED - DATE -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PIPE HANDRAIL DETAILS					1087	107T-1	STEPHENS	SON 47	21	
			REVISED -									CONTRA	CT NO. 64C64		
			REVISED ~		SCALE:	SHEET NO.	. OF	SHEETS	STA.	TO STA.	FED. ROAD D	IST. NO. ILLING	IS FED. AID PROJECT		