
Contract # 64C74



ELEVATION TEMPORARY SHEET PILING

1'-0"±

Abutment	El. A	EI. B	EI. C	EI. D	L	Н	E	Smin
Α	612.96	613.22	606.76	596.09	8′-10"	6′-2"	10′-8"	4.46
В	607.09	606.86	601.14	590.81	8'-1"	5′-11"	10'-4"	4.09
С	612.10	612.33	606.76	597.26	7'-11"	5′-4"	9'-6"	3.18
D	606.23	606.02	601.14	591.97	7'-2"	5′-1"	9'-2"	2.81

Smin = Minimum Section Modulus Required (in³/ft)

Notes:

- 1. If Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.
- 2. The Contractor shall connect the first sheet to the existing abutment wall to ensure stability of sheets driven to the top of existing footing. The connection shall be reviewed and accepted by the Engineer and included in the cost for Temporary Sheet Piling.
- 3. For details of Temporary Concrete Barrier, see sheet S19 of S25.
- 4. For quantity of Temporary Concrete Barrier, see roadway plans.

BILL OF MATERIAL (For 4 Approach Payements.)


Unit Quantity Sq. Ft. 392 Temporary Sheet Pilina


CONSTRUCTION STAGING INTERSTATE 80 OVER INTERSTATE 88


ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 80 - SECTION 81-1HBY-D
ROCK ISLAND COUNTY STATION 217+81.50 EB S.N. 081-0012 & WB 081-0013

DRAWN BY: A. Yargicoglu CHECKED BY: A. Durbak DATE: FEBRUARY 27, 2008







"STAGE I CONSTRUCTION & TRAFFIC

Ex € I-80 WB----- PGL I-80 WB PGL I-80 EB ---Ex € I-80 EB --- € *I-80* 12'-0" 31'-7"± 32'-5"± 12'-0" (From Survey) (From Survey) Var. 27'-5'2"± to 29'-6"± Var. 27'-5¹₂"± to 29'-6"± 20'-4" 24'-0" ± 24'-10"± 20'-4" Stage II Removal Stage II Removal STAGE 2 TRAFFIC STAGE 2 TRAFFIC 11'-0" 11'-0" 3'-1" 11'-0" 11'-0" Temp. Conc. Barrier Temp. Conc. Barrier Std. 704001 Std. 704001 (See Crown-Notes 3 and 4) 1'-3" -Exist. W30 or W33 to Remain, Typ. Exist. W30 or W33 -to Remain, Typ. 2'-62" 2'-6'2" Var. 28'-8¹₂" to 30'-9" Var. 28'-8'2" to 30'-9" Stage Construction Line Stage Construction Line-Stage II Construction Stage II Construction

STAGE II CONSTRUCTION & TRAFFIC

(LOOKING SOUTH)

PATRICK ENGINEERING INC.

LISLE, ILLINOIS