

GENERAL NOTES

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then, use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Meter (Cubic Yard) for MOBILIZATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION

Location 1 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 1.

Location 2 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 2.

Location 3 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 3.

Location 4 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 4 and 5.

Location 5 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 6 and 7.

Location 6 will be paid for as the Lump Sum total for Cleaning and Painting Steel Bridge No. 8 and 9.

SSPC QP1 AND SSPC QP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS CONTRACT.

STANDARDS

- 701006-02 Off-Road Operations, 2L, 2W, 4.5 m (15') to 600 mm (24") From Pavement Edge
- 701400-02 Approach to Lane Closure, Freeway/Expressway
- 701402-06 Lane Closure, Freeway/Expressway, with Barrier
- 701406-04 Lane Closure, Freeway/Expressway, Day Operations Only
- 701411-04 Lane Closure, Multilane, at Entrance or Exit Ramp, for Speeds > 45 MPH
- 720001 Sign Panel Mounting Details
- 701901 Traffic Control Devices
- 720011 Metal Posts for Signs, Markers and Delineators
- 728001 Telescoping Steel Sign Support
- 729001 Applications of Types A and B Metal Posts (For Signs & Markers)

* FAI ROUTES 74 & 88
** D2 BRIDGE PAINTING 2008-1

FILE NAME = P:\PAINTING\64D89\paint2008-1.dgn	USER NAME = linkdj	DESIGNED - ____	REVISED - ____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & STANDARDS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - ____	REVISED - ____			•	••	ROCK ISLAND	40	3
	PLOT SCALE = 50.0000' / IN.	CHECKED - ____	REVISED - ____			CONTRACT NO. 64D89				
	PLOT DATE = Thu Feb 28 07:41:40 2008	DATE - ____	REVISED - ____			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				
	SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____									