

## **SHRUB PLACEMENT DETAIL**

- 1. PLACEMENT OF SHRUBS AND TREES SHALL NOT INTERFERE WITH EXISTING PREVIOUSLY DEPARTMENT PLANTED SHRUB OR TREE LINES
- 2. EXACT LOCATIONS TO BE DETERMINED BY ENGINEER.

TREE SCHEDULE						
LOCATION	DISTANCE	EVERGREEN PICEA ABIES (NORWAY SPRUCE) 5' HEIGHT BALLED AND BURLAPPED EACH				
I-39 SOUTHBOUND (WEST SIDE)						
MILE MARKER 62.5 TO 63	2640	10				
MILE MARKER 68.5 TO 69.5	5280	16				
MILE MARKER 73 TO 74.5	7920	22				
MILE MARKER 75 TO 76.5	7920	22				
TOTAL		70				

**DETAILS** 

		SHF	RUB SCHEDULE		
LOCATION	DISTANCE	SHRUB, VIBURNUM TRILOBUM (AMERICAN CRANBERRY VIBURNUM) 30" HEIGHT BALLED AND BURLAPPED EACH	SHRUB, CORNUS RACEMOSA (GRAY DOGWOOD), 30" HEIGHT BALLED AND BURLAPPED EACH	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC) 5 GALLON EACH	SHRUB, ARONIA MELANOCARPA (BLACK CHOKEBERRY) 24" HEIGHT BALLED AND BURLAPPED EACH
I-39 SOUTHBOUND (WEST SIDE)					
MILE MARKER 62.5 TO 63	2640		* v.	200	
MILE MARKER 68.5 TO 69.5	5280	250			
MILE MARKER 73 TO 74.5	7920		600		
MILE MARKER 75 TO 76.5	7920				600
TOTAL		250	600	200	600

STATE OF ILLINOIS

F.A. SECTION COUNTY TOTAL SHEETS NO.

412 TREE PLANTING 2008-1 LASALLE 3 3 3