GENERAL NOTES

- 1 ALL ELEVATIONS SHOWN IN THE PLANS ARE U.S.G.S. MEAN SEA LEVEL DATUM.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERRUPTED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS SHOWN IN THE PLANS.
- 3 EXISTING PAVEMENT DAMAGED DUE TO THE CONTRACTOR'S OPERATIONS, AND NOT OTHER WISE NECESSARY TO REPLACE, SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.
- THE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. AFTER THE CONSTRUCTION IS COMPLETED, THE CONTRACTOR WILL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION IF THE ENGINEER DECIDES TO HAVE THE CONTRACTOR RESET THE MONUMENT, THIS WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.
- 6 NO PASSING ZONES SHALL BE FIELD VERIFIED BY DIST. 6 SIGN SHOP, (217) 785-0288, 14 DAYS PRIOR TO FINAL PAVEMENT MARKINGS.
- PRIOR TO ROAD CLOSURE, THE R.E. SHALL VIDEOTAPE THE LOCAL ROAD NETWORK FOR DETERMINATION OF DAMAGES DUE TO THE DETOURED TRAFFIC. THIS SHALL BE USED TO DETERMINE NECESSARY REPAIRS TO RETURN THE LOCAL ROADS TO THEIR ORIGINAL CONDITION AS DETERMINED BY THE ENGINEER. ESTIMATED QUANTITIES FOR REPAIRS TO LOCAL ROADS ARE INCLUDED IN THE PLANS.

COMMITMENTS

- THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES & PLANS CONCERNING ANY MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.
- ALL WORK IN THIS CONTRACT SHALL BE COMPLETED BEFORE AUGUST 20, 2008 AND WITHIN 30 CONSECUTIVE CALENDAR DAYS FROM THE FIRST DAY OF ALLOWED ROAD CLOSURE.

INDEX OF SHEETS

1	COVER SHEET					
2	GENERAL NOTES & COMMITMENTS					
3	SUMMARY OF QUANTITIES					
4	DETOUR PLAN					
5 - 7	STRUCTURE PLANS					

DISTRICT SIX	
EXAMINED February 5 OPERATIONS ENGINEER	20 <u>08</u>
EXAMINED FEBS	20 58
PROGRAM IMPLEMENTATION ENGINE EXAMINED 128	20 08
PROGRAM DEVELOPMENT ENGINEER	

FILE NAME =	USER NAME = mwajejsi	DESIGNED	REVISED		GENERAL NOTES AND COMMITMENTS		SECTION	COUNTY	TOTAL SHEET
c:\projects\d601308\shtgennotes.dgn		DRAWN	REVISED -	STATE OF ILLINOIS			108BR)I-1	PIKE	7 2
	PLOT SCALE = 100.0000 '/ IN.	CHECKED	REVISED -	DEPARTMENT OF TRANSPORTATION		CONTRACT_NO		T NO. 72857	
	PLOT DATE = Feb-08-2008 01:58:46PM	DATE -	REVISED		SCALE: SHEET NO OF SHEETS STA TO STA	FED. ROAD DIST. NO.	ILLINOIS FED. All) PROJECT	