GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THIS WORK INCLUDED IN THIS SECTION CONSISTS OF ERECTING GUARDRAIL, PLACING EMBANKMENT, CONSTRUCTING IMPACT ATTENUATORS, EXTENDING PIPE UNDERDRAINS (SPECIAL) AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U.S.G.S. DATUM.

ALL DISTURBED AREAS WITHIN THE CONSTRUCTION LIMITS SHALL BE FERTILIZED AND SEEDED. SEEDING SHALL BE CLASS 2 IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS.

INDEX OF SHEETS

1	Cover Sheet
2	Index of Sheets, Standards, General Notes
3	Summary of Quantities
4	Typical Sections
5	Schedule of Quantities
6-13	Plan and Profile Sheets
14-19	Details
20-51	Cross Sections

STANDARDS IN THE PLANS

000001-05	Standard Symbol, Abbreviations and Patterns
001001-01	Areas of Reinforcement Bars
001006	Decimal of an Inch and of a Foot
280001-04	Temporary Erosion Control Systems
601001-02	Sub-Surface Drains
601101	Concrete Headwall for Pipe Drain
630001-07	Steel Plate Beam Guardrail
630301-04	Shoulder Widening for Type 1 (Special) Guardrail Terminals
631011-04	Traffic Barrier Terminal, Type 2
635006-02	Reflector and Terminal Marker Placement
635011-01	Reflector Marker and Mounting Details
701011-01	Off-Road Operations, Multilane, 4.5m (15') to 600mm (24") from Pavement Edge
701101-01	Off-Road Operations, Multilane, More Than 4.5m (15') Away
701400-02	Approach to Lane Closure, Freeway/Expressway
701406-04	Lane Closure, Freeway/Expressway, Day Operations Only
701901	Traffic Control Devices