INDEX OF SHEETS

SHEET NO.	<u>ITEM</u>
1	COVER SHEET
2	INDEX OF SHEETS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTION
5-6	STAGE I CONSTRUCTION
7-8	STAGE II CONSTRUCTION
9-11	BRIDGE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 11:

STD. NO.	DESCRIPTION
000001 - 05 701001 - 01	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS OFF-RD OPERATIONS, 2L, 2W MORE THAN 15' AWAY
701006-02	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-01 701301-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701321-09 701326-02	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER LANE CLOSURE. 2L. 2W. PAVEMENT WIDENING FOR SPEEDS >= 45 MPH
701901	TRAFFIC CONTROL DEVICES
704001-04 780001-01	TEMPORARY CONCRETE BARRIER TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS: THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007; AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF REHABILITATING STRUCTURE NUMBER 051-0006 OVER EMBARRAS RIVER ON IL 1. DECK BEAMS SHALL BE REPLACED TO MAINTAIN/ IMPROVE THE

PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO THE CONSTRUCTION OR ORDERING OF MATERIAL. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION OR A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING-LINE 4" CONSISTS OF 258 FEET OF YELLOW AND 2060 FEET OF WHITE.

BASE COURSE WIDENING SHALL INCLUDE ALL EXCAVATION FOR CONSTRUCTION OF THE WIDENING. THE WIDENING SHALL. AT THE CONTRACTOR'S OPTION BE CONSTRUCTED OF EITHER PORTLAND CEMENT CONCRETE 8" THICK, OR HOT-MIX ASPHALT, 10" THICK. THE WIDENING SHALL REMAIN IN PLACE AT THE CONCLUSION OF THE JOB.

THE CONTRACTOR SHALL PROVIDE INTERNET ACCESSIBILITY TO THE HOT-MIX ASPHALT PLANT QUALITY CONTROL LAB SO THAT HOT-MIX ASPHALT PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADOUARTERS. THIS WORK SHALL BE INCLUDED IN THE COST OF ALL HOT-MIX ASPHALT