## GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", ADOPTED JANUARY 1, 2008, AND THE SPECIAL PROVISIONS INCLUDED IN THIS PROPOSAL.

THIS PROJECT IS LOCATED ALONG ILL ROUTE 33 IN PALESTINE FROM VINCENNES STREET TO LAMOTTE CREEK. FROM STATION 28+00 TO STATION 35+00. THE WORK INCLUDED IN THIS SECTION CONSISTS OF EARTH EXCAVATION AND PLACEMENT, RIPRAP, SEEDING, TREE REMOVAL AND REPLACEMENT AND OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL DISTURBANCES TO THIS SITE WILL BE KEPT TO A MINIMUM.

FILTER FABRIC AND BEDDING WILL NOT BE REQUIRED FOR PLACEMENT OF THE STONE DUMPED RIPRAP.

IN ACCORDANCE WITH THE SUPPLEMENTAL SPECIFICATIONS, TEMPORARY OR PERMANENT SEEDING, MULCH, PERIMETER EROSION BARRIER AND TEMPORARY DITCH CHECKS SHALL BE CONSTRUCTED IMMEDIATELY UPON COMPLETION OF THE EARTHWORK PAY ITEMS IN THE DITCH. TEMPORARY DITCH CHECKS MAY BE REQUIRED BEFORE COMPLETION OF THE PAY ITEMS AT THE DIRECTION OF THE ENGINEER.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 48 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

THE TREES LISTED IN THE TREE SCHEDULE SHALL BE HAND PLANTED AT LOCATIONS AS INDICATED BY PATRICIA SCHOFIELD, PRESIDENT, VILLAGE OF PALESTINE, 301 S MAIN, PALESTINE, ILLINOIS 62451, ON PUBLIC RIGHT OF WAY, WITHIN THE VILLAGE LIMITS OF PALESTINE. THE CONTRACTOR WILL BE REQUIRED TO GIVE TWO WEEKS NOTICE TO SCHEDULE TIME FOR THESE LOCATIONS TO BE STAKED. IN ADDITION, TWO WEEKS NOTICE SHALL BE GIVEN TO ROADSIDE MAINTENANCE TECHNICIAN, TOM WILSON (217) -342-8270 TO SCHEDULE A DELIVERY DATE OF THE TREES TO THE JOBSITE AND ON DELIVERY DAY HE WILL INSPECT FOR ACCEPTANCE, THE PLANTING MATERIAL LISTED IN THE TREE PLANTING SCHEDULE.

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -
cr\projects\74292d\shtindex_74292.dgn		DRAWN -	REVISED -
<b>25</b> 00	PLOT SCALE = 40.0000 '/ IN.	CHECKED -	REVISED -
	PLOT DATE = 2/6/2008	DATE -	REVISED -

STATE	0F	ILLINOIS	
DEPARTMENT (	OF 1	<b>TRANSPORTA</b>	TION

SCALE: N/A

GENERAL NOTES		F.A.P RTE.	A.P SECTION		COUNTY	TOTAL SHEETS	SHEE NO.
		781	1081		CRAWFORD	15	2
					CONTRACT	NO.	74292
SHEET NO. OF SHEETS STA.	TO STA.	FED. RO	AD DIST. NO.	ILLINOIS FED. A	D PROJECT		