## THERMOPLASTIC PAVEMENT MARKING SCHEDULE

	4 I	NCH	6 INCH	24 INCH		
LOCATION	WHITE	YELLOW	WHITE	WHITE		
STATION TO STATION	FOOT	FOOT	FOOT	FOOT		
LINDEN STREET						
STA 715+50 LT TO STA 717+09. 30 LT	19	-				
STA 715+50 TO STA 717+09. 3 (SKIP DASH)		31				
STA 715+50 RT TO STA 717+05. 7 RT	156					
STA 717+05.8 RT (STOP BAR)				13		
STA 717+09.7 RT (CROSSWALK)			55			
STA 717+15.7 RT (CROSSWALK)	-		67			
STA 717+63.6 LT (CROSSWALK)			47			
STA 717+69.6 LT (CROSSWALK)			33			
STA 717+73.5 RT (STOP BAR)				15		
STA 717+92.6 LT TO STA 718+15 LT	23					
STA 717+73.74 TO STA 718+15 (SKIP DASH)		10				
STA 717+73.74 RT TO STA 718+15 RT	5					
MAIN STREET						
STA 253+46.5 LT TO STA 253+66.5 LT	20					
STA 253+46.5 TO STA 254+21.7 (SKIP DASH)		15				
STA 253+46.5 RT TO STA 253+96.0 RT	50					
STA 254+21.7 (STOP BAR)				18		
STA 254+25.7 RT (CROSSWALK)			38			
STA 254+31.7 RT (CROSSWALK)			43			
STA 255+03.9 LT (CROSSWALK)			48			
STA 254+97.9 LT (CROSSWALK)			38			
STA 255+07.9 LT (STOP BAR)				18		
STA 255+07.9 TO STA 255+50 (SKIP DASH)		10				
an indicate on the state of the	0.7.7		7.00			
SUBTOTAL	273	66	369	64		
TOTAL	3	39	369	64		

FILE NAME =	USER NAME = carlsonej	DESIGNED -	REVISED -			F.A.P RTF.	SECTION	COUNTY	TOTAL						
c:\projects\78043\78043-sht-sch.dgn		DRAWN -	REVISED -	STATE OF ILLINOIS	SCHEDULES						873	105N	FRANKLIN	46	9
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	department of transportation									CONTRAC	T NO.	8043
PLOT D	PLOT DATE = 2/1/2008	DATE -	REVISED -		SCALE: 50	SHEET NO.	0F	SHEETS	STA.	TO STA.	FED. ROAD DIST.	NO. ILLINOIS FED.	ID PROJECT		