## SEEDING AND EROSION CONTROL SCHEDULE

LOCATION	EROSION CONTROL BLANKET	SEEDING CLASS 1B	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURA GROUND LIMESTONE POUNDS	
STATION TO STATION	SQ YD	SQ YD	POUNDS	POUNDS	POUNDS		
LINDEN STREET							
STA 715+63 LT TO STA 716+01 LT	13	13	1	1	1	11	
STA 716+20 LT TO STA 716+63 LT	25	25	1	1	1	20	
STA 716+74 LT TO STA 717+26 LT	46	46	1	1	1	38	
STA 717+71 LT TO STA 717+98 LT	25	25	1	1	1	21	
MAIN STREET							
STA 253+34 LT TO STA 254+25 LT	96	96	3	3	3	79	
STA 253+34 LT TO STA 254+55 LT (BEHIND SIDEWALK)	61	61	2	2	2	50	
STA 254+32.2 LT TO STA 254+44.5 LT	4	4	1	1	1	3	
	270	270	10	10	10	222	

ALL COSTS INCLUDED WITH EROSION CONTROL BLANKET

## EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	COMMENTS
STATION TO STATION	CU YD	CU YD	CU YD	CU YD	
LINDEN STREET STA 715+68. 9 LT TO STA 717+26. 4 LT	134	101	8	93	
MAIN STREET STA 253+66.5 LT TO STA 254+70 LT	41	31	14	17	
	175			110	

SHRINKAGE FACTOR: EARTH EXCAVATION 25%

T T	FILE NAME =	USER NAME = carlsonej	DESIGNED -	REVISED -								F.A.P	SECTION	COUNTY	TOTAL SHEET
	c:\projects\78043\78043-sht-sch.dgn		DRAWN -	REVISED -	state of illinois				schedules			873	105N	FRANKLIN	46 10
		PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION									CONTRACT NO. 78043	
- 1		PLOT DATE = 2/6/2008	DATE -	REVISED -		SCALE: 50	SHEET NO.	0F	SHEETS	STA.	TO STA.	FED. ROAD	DIST. NO. ILLINOIS FED.	AID PROJECT	