-PLACE ONLY AT EDGES ADJACENT TO SIDEWALK AROUND

PERIMETER OF BENCHES.

SECTION A-A

LIMESTONE BENCH ANCHORAGE DETAILS

5/8"Ø S.S. ANCHOR ROD EPOXY GROUTED, BY OTHERS

0

4-#5 V BARS

SECTION B-B

LIMESTONE PLANTER BASE ANCHORAGE DETAILS

CONTRACT NO. 93450 COUNTY TOTAL SHEET SHEETS NO. SECTION 7982 SANGAMON 114 85 STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT * 05-00447-01-PV CITY OF SPRINGFIELD ---1-1/2"Ø PVC CONDUIT -1/2" CHANNEL CAST IN TOP OF FOOTING ALL FOUR DIRECTIONS -S BAR -5/8"Ø S.S. ANCHOR ROD EPOXY GROUTED, BY OTHERS -V BAR * ANCHOR ROD SHALL HAVE AN EMBEDMENT SUFFICIENT TO OBTAIN 1.25 X THE YIELD STRENGTH OF THE ANCHOR ROD. -4" PCC SIDEWALK BAR S ALL FOUR DIRECTIONS BILL OF MATERIAL ONE PLANTER FOUNDATION ONLY -1-1/2"Ø PVC EMBEDED CONDUIT Structure Excavation Cu. Yd. Concrete Structures Cu. Yd. Reinforcement Bars Pound ILLINOIS DEPARTMENT OF TRANSPORTATION MISCELLANEOUS ANCHORAGE DETAILS FAU RTE 7982 CAPITOL AVE SEC NO. 05-00447-01-PV

SANGAMON COUNTY, ILLINOIS

DRAWN BY DAB CHECKED BY MNM

SCALE: VERT. HORIZ. DATE 09/19/07

5/8"Ø S.S. ANCHOR ROD EPOXY -

* ANCHOR ROD SHALL HAVE AN EMBEDMENT

SUFFICIENT TO OBTAIN 1.25 X THE YIELD STRENGTH OF THE ANCHOR ROD.

GROUTED, BY OTHERS

HANSON