#### INDEX OF SHEETS

SHEET NO.

2

4-6 7-19

20-21

666001

701301-02

701901

DESCRIPTION

GENERAL NOTES, AND DETAILS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS

280001-04 TEMPORARY EROSION CONTROL SYSTEMS

RIGHT OF WAY MARKERS

TRAFFIC CONTROL DEVICES

BEFORE DIGGING IN ILLINOIS
.....CALL JULIE FIRST AT 1-800-892-0123

WESTERN WAYNE WATER DISTRICT CONTACT: ROGER JOHNSON

WABASH TELEPHONE COOP., INC. CONTACT: JEFF WILLIAMS

1-618-895-2813 (OFFICE) 838-3655 (CELL) 838-9511 (PAGER)

1-618-665-3311 (OFFICE)

WAYNE / WHITE ELECTRIC

CONTACT: AARON HAWLEY

1-618-665-4188 (FAX)

1-618-842-2196

000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS

701006-02 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
701201-02 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

BLR 21-7 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
BLR 22-5 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

STORM WATER POLLUTION PREVENTION PLAN

542306-01 PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION

TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

PLAN & PROFILE HORIZONTAL

PROFILE

CROSS

SECTION

VERTICAL

COVER SHEET

SCHEDULES

PLAN SHEETS

CROSS SECTIONS


AND ARE INCLUDED AFTER SHEET NO. 21.

## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

### PLANS FOR

# PROPOSED LOCAL AGENCY IMPROVEMENT FEDERAL-AID SECONDARY PROJECT

F. A. S. ROUTE 2817 SECTION 04-00111-01-FP WAYNE COUNTY PROJECT SR-2817(102) C-97-059-04



GROSS LENGTH

OMISSIONS

NET LENGTH

FUNCTIONAL CLASS:

MAJOR COLLECTOR - RURAL ADT = 1000 DESIGN SPEED = 50 MPH

PLANS PREPARED BY:



Mill & JD ILL. REG. PROF. ENGINEER

MILES

MILES

062-053893 REG, ND.

FEET

FEET

9,439

DATE

EXPIRES : 11-30-2009

1.79

0.00

### SUMMARY OF QUANTITIES

04-00111-01-FP


FAS ROUTE 2817
ILLINOIS PROJECT SR-2817(102)

WAYNE

21 1

CONTRACT NO. 95416

	_		
QUANTITY	UNIT	ITEM	CODE NO.
132.00	CU YD	CONTROLLED LOW-STRENGTH MATERIAL	<b>5</b> 93∞1∞
292.00	UNIT	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	20100110
408.00	UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER)	20100210
1.73	ACRE	TREE REMOVAL, ACRES	20100500
20869.00	CU YD	EARTH EXCAVATION	20200100
12.68	ACRE	SEEDING, CLASS 2 (SPECIAL)	25001000
54.00	EACH	TEMPORARY DITCH CHECKS	28000300
17.00	EACH	INLET AND PIPE PROTECTION	28000500
113.00	TON	STONE DUMPED RIPRAP, CLASS A4	28100807
150.00	SQ YD	FILTER FABRIC	28200200
25,610.00	SQ YD	PROCESSING SOIL-CEMENT BASE COURSE 8"	35200300
14,342.00	100 WT	CEMENT	35200500
5185.00	TON	AGGREGATE SURFACE COURSE, TYPE B	40200800
200.00	GALLON	BITUMINOUS MATERIALS (PRIME COAT)	40300100
11,525.00	GALLON	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	40300300
321.00	TON	COVER COAT AGGREGATE	40300500
321.00	TON	SEAL COAT AGGREGATE	40300600
108.00	FOOT	PIPE CULVERTS, TYPE 1 RCCP 18"	54200433
338.00	FOOT	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	54200640
324.00	FOOT	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	54200643
280.00	FOOT	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	54207165
56.00	FOOT	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	54207171
48.00	FOOT	PIPE CULVERTS, TYPE 2, REINFORCED CONCRETE—ELLIPTICAL, EQUIVALENT ROUND—SIZE 36"	54209901
12.00	EACH	PRECAST REINFORCED CONCRETE END SECTIONS, EQUIVALENT ROUND—SIZE 30"	54214515
2.00	EACH	PRECAST REINFORCED CONCRETE END SECTIONS, EQUIVALENT ROUND—SIZE 36"	54214521
45.00	EACH	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	66600105
4.00	CAL MO	ENGINEER'S FIELD LABORATORY	67000600
1.00	L SUM	MOBILIZATION	67100100
1.00	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	70100450
1.00	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	70101830*
1.00	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	70101835*



CONTRACT NO. 95416